


# Data Science Interview Questions

(30 days of Interview Preparation)



## Q1. What is the difference between AI, Data Science, ML, and DL?

Ans 1 :



**Artificial Intelligence:** AI is purely math and scientific exercise, but when it became computational, it started to solve human problems formalized into a subset of computer science. Artificial intelligence has changed the original computational statistics paradigm to the modern idea that machines could mimic actual human capabilities, such as decision making and performing more “human” tasks. Modern AI into two categories

1. General AI - Planning, decision making, identifying objects, recognizing sounds, social & business transactions
2. Applied AI - driverless/ Autonomous car or machine smartly trade stocks

**Machine Learning:** Instead of engineers “teaching” or programming computers to have what they need to carry out tasks, that perhaps computers could teach themselves – learn something without being explicitly programmed to do so. ML is a form of AI where based on more data, and they can change actions and response, which will make more efficient, adaptable and scalable. e.g., navigation apps and recommendation engines. Classified into:-

1. Supervised
2. Unsupervised
3. Reinforcement learning

**Data Science:** Data science has many tools, techniques, and algorithms called from these fields, plus others –to handle big data

The goal of data science, somewhat similar to machine learning, is to make accurate predictions and to automate and perform transactions in real-time, such as purchasing internet traffic or automatically generating content.

# INEURON.AI

Data science relies less on math and coding and more on data and building new systems to process the data. Relying on the fields of data integration, distributed architecture, automated machine learning, data visualization, data engineering, and automated data-driven decisions, data science can cover an entire spectrum of data processing, not only the algorithms or statistics related to data.

**Deep Learning:** It is a technique for implementing ML.

ML provides the desired output from a given input, but DL reads the input and applies it to another data. In ML, we can easily classify the flower based upon the features. Suppose you want a machine to look at an image and determine what it represents to the human eye, whether a face, flower, landscape, truck, building, etc.

Machine learning is not sufficient for this task because machine learning can only produce an output from a data set – whether according to a known algorithm or based on the inherent structure of the data. You might be able to use machine learning to determine whether an image was of an “X” – a flower, say – and it would learn and get more accurate. But that output is binary (yes/no) and is dependent on the algorithm, not the data. In the image recognition case, the outcome is not binary and not dependent on the algorithm.

The neural network performs MICRO calculations with computational on many layers. Neural networks also support weighting data for ‘confidence’. These results in a probabilistic system, vs. deterministic, and can handle tasks that we think of as requiring more ‘human-like’ judgment.

## Q2. What is the difference between Supervised learning, Unsupervised learning and Reinforcement learning?

**Ans 2:**

### Machine Learning

Machine learning is the scientific study of algorithms and statistical models that computer systems use to effectively perform a specific task without using explicit instructions, relying on patterns and inference instead.

*Building a model by learning the patterns of historical data with some relationship between data to make a data-driven prediction.*

### Types of Machine Learning

- Supervised Learning
- Unsupervised Learning
- Reinforcement Learning

### Supervised learning

In a supervised learning model, the algorithm learns on a labeled dataset, to generate reasonable predictions for the response to new data. (Forecasting outcome of new data)

- Regression
- Classification

## Unsupervised learning


An unsupervised model, in contrast, provides unlabelled data that the algorithm tries to make sense of by extracting features, co-occurrence and underlying patterns on its own. We use unsupervised learning for

- Clustering
- Anomaly detection
- Association
- Autoencoders

## Reinforcement Learning

Reinforcement learning is less supervised and depends on the learning agent in determining the output solutions by arriving at different possible ways to achieve the best possible solution.

## Q3. Describe the general architecture of Machine learning.



**Business understanding:** Understand the give use case, and also, it's good to know more about the domain for which the use cases are built.

**Data Acquisition and Understanding:** Data gathering from different sources and understanding the data. Cleaning the data, handling the missing data if any, data wrangling, and EDA( Exploratory data analysis).

**Modeling:** *Feature Engineering* - scaling the data, feature selection - not all features are important. We use the backward elimination method, correlation factors, PCA and domain knowledge to select the features.

**Model Training** based on trial and error method or by experience, we select the algorithm and train with the selected features.

**Model evaluation** Accuracy of the model , confusion matrix and cross-validation.

If accuracy is not high, to achieve higher accuracy, we tune the model...either by changing the algorithm used or by feature selection or by gathering more data, etc.

**Deployment** - Once the model has good accuracy, we deploy the model either in the cloud or Rasberry py or any other place. Once we deploy, we monitor the performance of the model.if its good...we go live with the model or reiterate the all process until our model performance is good.

It's not done yet!!!


What if, after a few days, our model performs badly because of new data. In that case, we do all the process again by collecting new data and redeploy the model.

## Q4. What is Linear Regression?

**Ans 4:**

Linear Regression tends to establish a relationship between a dependent variable(Y) and one or more independent variable(X) by finding the best fit of the straight line.

The equation for the Linear model is  $Y = mX+c$ , where m is the slope and c is the intercept



In the above diagram, the blue dots we see are the distribution of 'y' w.r.t 'x.' There is no straight line that runs through all the data points. So, the objective here is to fit the best fit of a straight line that will try to minimize the error between the expected and actual value.

## Q5. OLS Stats Model (Ordinary Least Square)

### Ans 5:

OLS is a stats model, which will help us in identifying the more significant features that can have an influence on the output. OLS model in python is executed as:

```
lm = smf.ols(formula = 'Sales ~ am+constant', data = data).fit() lm.conf_int() lm.summary()
```

And we get the output as below,

```
OLS Regression Results
=====
Dep. Variable: mpg R-squared: 0.360
Model: OLS Adj. R-squared: 0.338
Method: Least Squares F-statistic: 16.86
Date: Wed, 17 Jan 2018 Prob (F-statistic): 0.000285
Time: 14:07:51 Log-Likelihood: -95.242
No. Observations: 32 AIC: 194.5
Df Residuals: 30 BIC: 197.4
Df Model: 1
Covariance Type: nonrobust
=====
      coef  std err      t  P>|t|    [0.025  0.975]
-----
constant  17.1474  1.125   15.247  0.000   14.851  19.444
am        7.2449  1.764    4.106  0.000   3.642  10.848
=====
Omnibus: 0.480 Durbin-Watson: 1.065
Prob(Omnibus): 0.787 Jarque-Bera (JB): 0.589
Skew: 0.051 Prob(JB): 0.745
Kurtosis: 2.343 Cond. No. 2.46
=====
```

**The higher the t-value for the feature, the more significant the feature is to the output variable.** And also, the p-value plays a role in rejecting the Null hypothesis(Null hypothesis stating the features has zero significance on the target variable.). **If the p-value is less than 0.05(95% confidence interval) for a feature, then we can consider the feature to be significant.**

## Q6. What is L1 Regularization (L1 = lasso) ?

### Ans 6:

The main objective of creating a model(training data) is making sure it fits the data properly and reduce the loss. Sometimes the model that is trained which will fit the data but it may fail and give a poor performance during analyzing of data (test data). This leads to overfitting. Regularization came to overcome overfitting.

Lasso Regression (**Least Absolute Shrinkage and Selection Operator**) adds “Absolute value of magnitude” of coefficient, as penalty term to the loss function.

Lasso shrinks the less important feature's coefficient to zero; thus, removing some feature altogether. So, this works well for feature selection in case we have a huge number of features.

## L1 Regularization

$$\text{Cost} = \sum_{i=0}^N (y_i - \sum_{j=0}^M x_{ij} W_j)^2 + \lambda \sum_{j=0}^M |W_j|$$

## L2 Regularization

$$\text{Cost} = \sum_{i=0}^N (y_i - \sum_{j=0}^M x_{ij} W_j)^2 + \lambda \sum_{j=0}^M W_j^2$$

Loss function
Regularization Term

Methods like Cross-validation, Stepwise Regression are there to handle overfitting and perform feature selection work well with a small set of features. These techniques are good when we are dealing with a large set of features.

Along with shrinking coefficients, the **lasso performs feature selection**, as well. (Remember the 'selection' in the lasso full-form?) Because some of the coefficients become exactly zero, which is equivalent to the particular feature being excluded from the model.

## Q7. L2 Regularization(L2 = Ridge Regression)


**Ans 7:**

$$\text{Cost function} = \text{Loss} + \frac{\lambda}{2m} * \sum \|w\|^2$$

Overfitting happens when the model learns signal as well as noise in the training data and wouldn't perform well on new/unseen data on which model wasn't trained on.

To avoid overfitting your model on training data like **cross-validation sampling, reducing the number of features, pruning, regularization**, etc.

**So to avoid overfitting, we perform Regularization.**



The Regression model that uses L2 regularization is called Ridge Regression.

The formula for Ridge Regression:-

$$J(\theta) = \frac{1}{2m} \left[ \sum_{i=1}^m (h_\theta(x^{(i)}) - y^{(i)})^2 + \lambda \sum_{j=1}^n \theta_j^2 \right]$$

$$\min_{\theta} J(\theta)$$

Regularization adds the penalty as model complexity increases. The regularization parameter (lambda) penalizes all the parameters except intercept so that the model generalizes the data and won't overfit.

Ridge regression adds "squared magnitude of the coefficient" as penalty term to the loss function. Here the box part in the above image represents the L2 regularization element/term.

$$\sum_{i=1}^n (y_i - \sum_{j=1}^p x_{ij} \beta_j)^2 + \lambda \sum_{j=1}^p \beta_j^2$$

Lambda is a hyperparameter.

If lambda is zero, then it is equivalent to OLS. But if lambda is very large, then it will add too much weight, and it will lead to under-fitting.

Ridge regularization forces the weights to be small but does not make them zero and does not give the sparse solution.

Ridge is not robust to outliers as square terms blow up the error differences of the outliers, and the regularization term tries to fix it by penalizing the weights

Ridge regression performs better when all the input features influence the output, and all with weights are of roughly equal size.

L2 regularization can learn complex data patterns.

## Q8. What is R square(where to use and where not)?

Ans 8.

R-squared is a statistical measure of how close the data are to the fitted regression line. It is also known as the coefficient of determination, or the coefficient of multiple determination for multiple regression.

The definition of R-squared is the percentage of the response variable variation that is explained by a linear model.

R-squared = Explained variation / Total variation

R-squared is always between 0 and 100%.

0% indicates that the model explains none of the variability of the response data around its mean.

100% indicates that the model explains all the variability of the response data around its mean.

In general, the higher the R-squared, the better the model fits your data.

$$R^2 = 1 - \frac{SS_{Regression}}{SS_{Total}}$$

Sum Squared Regression Error →  $SS_{Regression}$   
Sum Squared Total Error →  $SS_{Total}$

$$R^2 = 1 - \frac{SS_{RES}}{SS_{TOT}} = \frac{\sum_i (y_i - \hat{y}_i)^2}{\sum_i (y_i - \bar{y})^2}$$

There is a problem with the R-Square. The problem arises when we ask this question to ourselves.\*\* Is it good to help as many independent variables as possible?\*\*

The answer is No because we understood that each independent variable should have a meaningful impact. But, even\*\* if we add independent variables which are not meaningful\*\*, will it improve R-Square value?

Yes, this is the basic problem with R-Square. How many junk independent variables or important independent variable or impactful independent variable you add to your model, the R-Squared value will always increase. It will never decrease with the addition of a newly independent variable, whether it could be an impactful, non-impactful, or bad variable, so we need another way to measure equivalent R-Square, which penalizes our model with any junk independent variable.

So, we calculate the **Adjusted R-Square** with a better adjustment in the formula of generic R-square.

$$R^2_{\text{adjusted}} = 1 - \frac{(1 - R^2)(N - 1)}{N - p - 1}$$

where

$R^2$  = sample R-square


p = Number of predictors

N = Total sample size.

## Q9. What is Mean Square Error?

The mean squared error tells you how close a regression line is to a set of points. It does this by taking the distances from the points to the regression line (these distances are the “errors”) and squaring them.

### Giving an intuition



The line equation is  $y = Mx + B$ . We want to find **M (slope)** and **B (y-intercept)** that minimizes the squared error.

$$\text{MSE} = \frac{1}{n} \sum_{i=1}^n (y_i - \tilde{y}_i)^2$$


**Q10. Why Support Vector Regression? Difference between SVR and a simple regression model?**

**Ans 10:**


In simple linear regression, try to minimize the error rate. But in SVR, we try to fit the error within a certain threshold.

**Main Concepts:-**

1. Boundary
2. Kernel
3. Support Vector
4. Hyper Plane




Blueline: Hyper Plane; Red Line: Boundary-Line



Our best fit line is the one where the hyperplane has the maximum number of points.

We are trying to do here is trying to decide a decision boundary at 'e' distance from the original hyperplane such that data points closest to the hyperplane or the support vectors are within that boundary line




# **DATA SCIENCE INTERVIEW PREPARATION (30 Days of Interview Preparation)**

**#DAY 02**

## Q1. What is Logistic Regression?

### Answer:

The logistic regression technique involves the dependent variable which can be represented in the binary 0 or true or false yes or no values which means that the outcome could only be in either one form of two. For example it can be utilized when we need to find the probability of a successful or fail event.



Logistic regression is used when the dependent variable (target) is categorical.


### Model

Output = 0 or

$$Z = WX + B$$

$$h_{\Theta}(x) = \text{sigmoid}(Z)$$

$$h_{\Theta}(x) = \log P(X) / (1 - P(X)) = WX + B$$



If  $Z$  goes to infinity  $Y$  predicted will become 1 and if  $Z$  goes to negative infinity  $Y$  predicted will become 0

The output from the hypothesis is the estimated probability. This is used to infer how confident can predicted value be actual value when given an input  $X$ .

### Cost Function

$$\text{Cost}(h_{\Theta}(x), y) = -y \log(h_{\Theta}(x)) - (1-y) \log(1-h_{\Theta}(x))$$

If  $y = 1$ ,  $(1-y)$  term will become zero, therefore  $-\log(h_{\Theta}(x))$  alone will be present

If  $y = 0$ ,  $(y)$  term will become zero, therefore  $-\log(1-h_{\Theta}(x))$  alone will be present

$$\begin{aligned} \text{Cost } h_{\Theta}(x) &= Y \text{ Actual} = -\log h_{\Theta}(x) && \text{if } y=1 \\ &= -\log(1-h_{\Theta}(x)) && \text{if } y=0 \end{aligned}$$

This implementation is for binary logistic regression. For data with more than 2 classes softmax regression has to be used.

## Q2. Difference between logistic and linear regression?

### Answer:

Linear and Logistic regression are the most basic form of regression which are commonly used. The essential difference between these two is that Logistic regression is used when the dependent variable is binary. In contrast Linear regression is used when the dependent variable is continuous and the nature of the regression line is linear.

### Key Differences between Linear and Logistic Regression

Linear regression models data using continuous numeric value. As against logistic regression models the data in the binary values.


Linear regression requires to establish the linear relationship among dependent and independent variables whereas it is not necessary for logistic regression.

In linear regression the independent variable can be correlated with each other. On the contrary in the logistic regression the variable must not be correlated with each other.

## Q3. Why we can't do a classification problem using Regression?

### Answer:-


With linear regression you fit a polynomial through the data - say like on the example below we fit a straight line through tumor size tumor type sample set.



Above malignant tumors get 1 and non-malignant ones get 0 and the green line is our hypothesis  $h(x)$ . To make predictions we may say that for any given tumor size  $x$  if  $h(x)$  gets bigger than 0.5 we predict malignant tumors. Otherwise we predict benignly.

It looks like this way we could correctly predict every single training set sample but now let's change the task a bit.

Intuitively it's clear that all tumors larger certain threshold are malignant. So let's add another sample with huge tumor size and run linear regression again.



Now our  $h(x) > 0.5 \rightarrow$  malignant doesn't work anymore. To keep making correct predictions we need to change it to  $h(x) > 0.2$  or something - but that's not how the algorithm should work.

We cannot change the hypothesis each time a new sample arrives. Instead we should learn it off the training set data and then using the hypothesis we've learned make correct predictions for the data we haven't seen before.


*Linear regression is unbounded.*

#### Q4. What is Decision Tree?

A decision tree is a type of supervised learning algorithm that can be used in classification as well as regressor problems. The input to a decision tree can be both continuous as well as categorical. The decision tree works on an if-then statement. Decision tree tries to solve a problem by using tree representation Node and Leaf.

Assumptions while creating a decision tree  
Initially all the training set is considered as a root 2. Feature values are preferred to be categorical if continuous then they are discretized 3. Records are

distributed recursively on the basis of attribute values 4 Which attributes are considered to be in root node or internal node is done by using a statistical approach



## Q5. Entropy, Information Gain, Gini Index, Reducing Impurity?

### Answer:

There are different attributes which define the split of nodes in a decision tree. There are few algorithms to find the optimal split

**Iterative Optimiser** This solution uses Entropy and Information gain as metrics to form a better decision tree. The attribute with the highest information gain is used as a root node and a similar approach is followed after that. Entropy is the measure that characterizes the impurity of an arbitrary collection of examples

#### Entropy

Entropy  $H(S)$  is a measure of the amount of uncertainty in the (data) set  $S$  (i.e. entropy characterizes the (data) set  $S$ ).

$$H(S) = \sum_{c \in C} -p(c) \log_2 p(c)$$

Where,

- $S$  – The current (data) set for which entropy is being calculated (changes every iteration of the ID3 algorithm)
- $C$  – Set of classes in  $S$   $C=\{yes, no\}$
- $p(c)$  – The proportion of the number of elements in class  $c$  to the number of elements in set  $S$

When  $H(S) = 0$ , the set  $S$  is perfectly classified (i.e. all elements in  $S$  are of the same class).

In ID3, entropy is calculated for each remaining attribute. The attribute with the **smallest** entropy is used to split the set  $S$  on this iteration. The higher the entropy, the higher the potential to improve the classification here.

Entropy varies from 0 to 0 if all the data belong to a single class and if the class distribution is equal. In this way, entropy will give a measure of impurity in the dataset.

Steps to decide which attribute to split

Compute the entropy for the dataset

- 2 For every attribute
  
- 2 Calculate entropy for all categorical values
  - 2.2 Take average information entropy for the attribute
  - 2.3 Calculate gain for the current attribute
    - 3 Pick the attribute with the highest information gain
    - 4 Repeat until we get the desired tree

A leaf node is decided when entropy is zero


Information Gain =  $-\sum \frac{S_b}{S} * \text{Entropy } S_b$   
 Sb - Subset S - entire data

**2) CART Algorithm (Classification and Regression trees):** In CART we use the GINI index as a metric. Gini index is used as a cost function to evaluate split in a dataset.

Steps to calculate Gini for a split

- Calculate Gini for subnodes using formula **sum of the square of probability for success and failure ( $p_2 \cdot p_2$ )**
- 2 Calculate Gini for split using weighted Gini score of each node of that split

Choose the split based on higher Gini value



Split on Gender

$$\text{Gini for sub-node Female} = 0.2 * 0.2 + 0.8 * 0.8 = 0.68$$

$$\text{Gini for sub-node Male} = 0.65 * 0.65 + 0.35 * 0.35 = 0.55$$

Weighted Gini for Split Gender =  $0/30 * 0.68 + 20/30 * 0.55 = 0.59$

Similar for Split on Class

Gini for sub-node Class IX =  $0.43 * 0.43 + 0.57 * 0.57 = 0.5$

Gini for sub-node Class X =  $0.56 * 0.56 + 0.44 * 0.44 = 0.5$

Weighted Gini for Split Class =  $4/30 * 0.5 + 6/30 * 0.5 = 0.5$

Here Weighted Gini is high for gender so we consider splitting based on gender

## Q6. How to control leaf height and Pruning?

### Answer:

To control the leaf size we can set the parameters -

#### Maximum depth :

Maximum tree depth is a limit to stop the further splitting of nodes when the specified tree depth has been reached during the building of the initial decision tree

**NEVER use maximum depth to limit the further splitting of nodes. In other words: use the largest possible value.**

#### 2 Minimum split size:

Minimum split size is a limit to stop the further splitting of nodes when the number of observations in the node is lower than the minimum split size

This is a good way to limit the growth of the tree. When a leaf contains too few observations further splitting will result in overfitting modeling of noise in the data

#### 3 Minimum leaf size

Minimum leaf size is a limit to split a node when the number of observations in one of the child nodes is lower than the minimum leaf size


**Pruning** is mostly done to reduce the chances of overfitting the tree to the training data and reduce the overall complexity of the tree

There are two types of pruning **Pre-pruning** and **Post-pruning**

Pre-pruning is also known as the **early stopping criteria**. As the name suggests the criteria are set as parameter values while building the model. The tree stops growing when it meets any of these pre-pruning criteria or it discovers the pure classes

- 2 In Post-pruning the idea is to allow the decision tree to grow fully and observe the CP value Next we prune/cut the tree with the optimal **CP** Complexity Parameter value as the parameter

The CP complexity parameter is used to control tree growth If the cost of adding a variable is higher then the value of CP tree growth stops



## Q7. How to handle a decision tree for numerical and categorical data?

**Answer:**

Decision trees can handle both categorical and numerical variables at the same time as features There is not any problem in doing that

Every split in a decision tree is based on a feature

**If the feature is categorical□the split is done with the elements belonging to a particular class**

- 2 **If the feature is continuous□the split is done with the elements higher than a threshold□**

At every split the decision tree will take the best variable at that moment This will be done according to an impurity measure with the split branches And the fact that the variable used to do split is categorical or continuous is irrelevant in fact decision trees categorize continuous variables by creating binary regions with the threshold

At last the good approach is to always convert your **categoricals to continuous** using **LabelEncoder** or **OneHotEncoding**□

## Q8. What is the Random Forest Algorithm?

### Answer:

Random Forest is an ensemble machine learning algorithm that follows the bagging technique. The base estimators in the random forest are decision trees. Random forest randomly selects a set of features that are used to decide the best split at each node of the decision tree.

Looking at it step-by-step this is what a random forest model does

Random subsets are created from the original dataset **bootstrapping**

- 2 At each node in the decision tree only a random set of features are considered to decide the best split
- 3 A decision tree model is fitted on each of the subsets
- 4 The final prediction is calculated by averaging the predictions from all decision trees

*To sum up the random forest randomly selects data points and features and builds multiple trees (forest).*

Random Forest is used for feature importance selection. The attribute `feature_importances_` is used to find feature importance

Some Important Parameters -

- n\_estimators** - It defines the number of decision trees to be created in a random forest
- 2 **criterion** - "gini" or "Entropy"
- 3 **min\_samples\_split** - Used to define the minimum number of samples required in a leaf node before a split is attempted
- 4 **max\_features** - It defines the maximum number of features allowed for the split in each decision tree
- 5. **n\_jobs** - The number of jobs to run in parallel for both fit and predict **Always keep (-1) to use all the cores for parallel processing.**

## Q9. What is Variance and Bias tradeoff?

### Answer:


In predicting models the prediction error is composed of two different errors

- Bias
- 2 Variance

It is important to understand the variance and bias trade-off which tells about to minimize the Bias and Variance in the prediction and avoids overfitting & under fitting of the model

**Bias** It is the difference between the expected or average prediction of the model and the correct value which we are trying to predict Imagine if we are trying to build more than one model by collecting different data sets and later on evaluating the prediction we may end up by different prediction for all the models So bias is something which measures how far these model prediction from the correct prediction It always leads to a high error in training and test data


**Variance** Variability of a model prediction for a given data point We can build the model multiple times so the variance is how much the predictions for a given point vary between different realizations of the model



**For example** Voting Republican - 3 Voting Democratic - 6 Non-Respondent - 2 Total - 50 The probability of voting Republican is  $3/50 = 6$  or 44.8% We put out our press release that the Democrats are going to win by over 0 points; but when the election comes around it turns out they lose by 0 points That certainly reflects poorly on us Where did we go wrong in our model?

**Bias scenarios** using a phonebook to select participants in our survey is one of our sources of bias By only surveying certain classes of people it skews the results in a way that will be consistent if we repeated the entire model building exercise Similarly not following up with respondents is another source of bias as it consistently changes the mixture of responses we get On our bulls-eye diagram these move us away from the center of the target but they would not result in an increased scatter of estimates

**Variance scenarios** the small sample size is a source of variance If we increased our sample size the results would be more consistent each time we repeated the survey and prediction The results still might be highly inaccurate due to our large sources of bias but the variance of predictions will be reduced



## Q10. What are Ensemble Methods?

### Answer

#### **Bagging and Boosting**

Decision trees have been around for a long time and also known to suffer from bias and variance  
You will have a large bias with simple trees and a large variance with complex trees

**Ensemble methods** - which combines several decision trees to produce better predictive performance than utilizing a single decision tree. The main principle behind the ensemble model is that a group of weak learners come together to form a strong learner

Two techniques to perform ensemble decision trees

- 1 Bagging
- 2 Boosting

**Bagging (Bootstrap Aggregation)** is used when our goal is to reduce the variance of a decision tree. Here the idea is to create several subsets of data from the training sample chosen randomly with replacement. Now each collection of subset data is used to train their decision trees. As a result we end up with an ensemble of different models. Average of all the predictions from different trees are used which is more robust than a single decision tree.

**Boosting** is another ensemble technique to create a collection of predictors. In this technique learners are learned sequentially with early learners fitting simple models to the data and then analyzing data

for errors. In other words we fit consecutive trees random sample and at every step the goal is to solve for net error from the prior tree.

When a hypothesis misclassifies an input its weight is increased so that the next hypothesis is more likely to classify it correctly. By combining the whole set at the end converts weak learners into a better performing model.

The different types of boosting algorithms are

- 1  AdaBoost
- 2  Gradient Boosting
- 3  XGBoost


## Q11. What is SVM Classification?


**Answer:**

SVM or Large margin classifier is a supervised learning algorithm that uses a powerful technique called SVM for classification.


We have two types of SVM classifiers

**1) Linear SVM** In Linear SVM the data points are expected to be separated by some apparent gap. Therefore the SVM algorithm predicts a straight hyperplane dividing the two classes. The hyperplane is also called as maximum margin hyperplane.





**2) Non-Linear SVM:** It is possible that our data points are not linearly separable in a p-dimensional space but can be linearly separable in a higher dimension Kernel tricks make it possible to draw nonlinear hyperplanes Some standard kernels are a Polynomial Kernel b RBF kernel mostly used



#### Advantages of SVM classifier

- SVMs are effective when the number of features is quite large
- 2 It works effectively even if the number of features is greater than the number of samples
- 3 Non-Linear data can also be classified using customized hyperplanes built by using kernel trick
- 4 It is a robust model to solve prediction problems since it maximizes margin

#### Disadvantages of SVM classifier:

- The biggest limitation of the Support Vector Machine is the choice of the kernel The wrong choice of the kernel can lead to an increase in error percentage
- 2 With a greater number of samples it starts giving poor performances
- 3 SVMs have good generalization performance but they can be extremely slow in the test phase
- 4 SVMs have high algorithmic complexity and extensive memory requirements due to the use of quadratic programming

## Q11. What is Naive Bayes Classification and Gaussian Naive Bayes

**Answer:**

**Bayes Theorem** finds the probability of an event occurring given the probability of another event that has already occurred Bayes theorem is stated mathematically as the following equation

$$P(A|B) = \frac{P(B|A) P(A)}{P(B)}$$

↑ THE PROBABILITY OF "B" BEING TRUE GIVEN THAT "A" IS TRUE      ↓ THE PROBABILITY OF "A" BEING TRUE  
 ↑ THE PROBABILITY OF "A" BEING TRUE GIVEN THAT "B" IS TRUE      ↓ THE PROBABILITY OF "B" BEING TRUE

Now with regards to our dataset we can apply Bayes theorem in following way

$$P(y|X) = \frac{P(X|y) P(y)}{\sum P(X)}$$

where  $y$  is class variable and  $X$  is a dependent feature vector of size  $n$  where

$$X = x_1 \ x_2 \ x_3 \dots x_n$$

	OUTLOOK	TEMPERATURE	HUMIDITY	WINDY	PLAY GOLF
0	Rainy	Hot	High	False	No
1	Rainy	Hot	High	True	No
2	Overcast	Hot	High	False	Yes
3	Sunny	Mild	High	False	Yes
4	Sunny	Cool	Normal	False	Yes
5	Sunny	Cool	Normal	True	No
6	Overcast	Cool	Normal	True	Yes
7	Rainy	Mild	High	False	No
8	Rainy	Cool	Normal	False	Yes
9	Sunny	Mild	Normal	False	Yes
10	Rainy	Mild	Normal	True	Yes
11	Overcast	Mild	High	True	Yes
12	Overcast	Hot	Normal	False	Yes
13	Sunny	Mild	High	True	No

To clear an example of a feature vector and corresponding class variable can be refer st row of the dataset

$X = \text{Rainy Hot High False}$   $y = \text{No So}$  basically  $P(X|y)$  here means the probability of Not playing golf given that the weather conditions are Rainy outlook Temperature is hot high humidity and no wind


### Naive Bayes Classification

We assume that no pair of features are dependent. For example the temperature being Hot has nothing to do with the humidity or the outlook being Rainy does not affect the winds. Hence the features are assumed to be independent.

- 2 Secondly each feature is given the same weight or importance. For example knowing the only temperature and humidity alone can't predict the outcome accurately. None of the attributes is irrelevant and assumed to be contributing equally to the outcome.

#### □ Gaussian Naive Bayes

Continuous values associated with each feature are assumed to be distributed according to a Gaussian distribution. A Gaussian distribution is also called Normal distribution. When plotted it gives a bell-shaped curve which is symmetric about the mean of the feature values as shown below.



This is as simple as calculating the mean and standard deviation values of each input variable  $x$  for each class value.

$$\text{Mean } (x) = 1/n \sum(x_i)$$

Where  $n$  is the number of instances and  $x$  is the values for an input variable in your training data.

We can calculate the standard deviation using the following equation:

$$\text{Standard deviation}(x) = \sqrt{\frac{1}{n} \sum (x_i - \text{mean}(x))^2}$$

**When to use what?** Standard Naive Bayes only supports categorical features while Gaussian Naive Bayes only supports continuously valued features.

## Q12. What is the Confusion Matrix?

#### Answer:

A confusion matrix is a table that is often used to describe the performance of a classification model or classifier on a set of test data for which the true values are known. It allows the visualization of the performance of an algorithm.

A confusion matrix is a summary of prediction results on a classification problem. The number of correct and incorrect predictions are summarized with count values and broken down by each class.

This is the key to the confusion matrix

It gives us insight not only into the errors being made by a classifier but more importantly the types of errors that are being made

	<i>Class 1 Predicted</i>	<i>Class 2 Predicted</i>
<i>Class 1 Actual</i>	TP	FN
<i>Class 2 Actual</i>	FP	TN

Here

- Class 1 Positive
- Class 2 Negative

Definition of the Terms

- 1 **Positive (P)** Observation is positive for example is an apple
- 2 **Negative (N)** Observation is not positive for example is not an apple
- 3 **True Positive (TP)** Observation is positive and is predicted to be positive
- 4 **False Negative (FN)** Observation is positive but is predicted negative
- 5 **True Negative (TN)** Observation is negative and is predicted to be negative
- 6 **False Positive (FP)** Observation is negative but is predicted positive

## Q13. What is Accuracy and Misclassification Rate?

Answer

Accuracy

Accuracy is defined as the ratio of the sum of True Positive and True Negative by Total  $\frac{TP + TN}{TP + TN + FP + FN}$

$$\text{Accuracy} = \frac{TP + TN}{TP + TN + FP + FN}$$

However there are problems with accuracy. It assumes equal costs for both kinds of errors. A model's accuracy can be excellent, good, mediocre, poor, or terrible depending upon the problem.

### Misclassification rate

Misclassification Rate is defined as the ratio of the sum of False Positive and False

Negative by Total  $\frac{TP+TN+FP+FN}{TP+TN+FP+FN}$

Misclassification Rate is also called Error Rate

	Actual Positive	Actual Negative
Predicted Positive	True Positive(TP)	False Positive(FP) (Type 1 Error)
Predicted Negative	False Negative(FN) (Type 2 Error)	True Negative(TN)

$$\text{Accuracy} = \frac{\text{True Positive} + \text{True Negative}}{\text{Total Population}}$$

$$\text{Error Rate/Misclassification rate} = \frac{\text{False Positive} + \text{False Negative}}{\text{Total Population}}$$

$$\text{Precision} = \frac{\text{True Positive}}{\text{Predicted Positive}(TP+FP)}$$

$$\text{Sensitivity/Recall} = \frac{\text{True Positive}}{\text{Actual Positive}(TP+FN)}$$

$$\text{Specificity} = \frac{\text{True Negative}}{\text{Actual Negative}(FP+TN)}$$

$$\text{F1 Score} = \frac{2 * (\text{Recall} * \text{Precision})}{\text{Recall} + \text{Precision}}$$

### Q14. True Positive Rate & True Negative Rate

**Answer:**

#### True Positive Rate:

**Sensitivity (SN)** is calculated as the number of correct positive predictions divided by the total number of positives. It is also called **Recall (REC)** or true positive rate (TPR). The best sensitivity is 1.0, whereas the worst is 0.0.

$$SN = \frac{TP}{TP+FN} = \frac{TP}{P}$$

### True Negative Rate

**Specificity (SP)** is calculated as the number of correct negative predictions divided by the total number of negatives. It is also called a true negative rate (TNR). The best specificity is 1.0, whereas the worst is 0.0.

$$SN = \frac{TP}{TPFN} = \frac{TP}{P}$$

### Q15. What is False Positive Rate & False negative Rate?

#### False Positive rate

False positive rate FPR is calculated as the number of incorrect positive predictions divided by the total number of positives. The best false positive rate is 0.0 whereas the worst is 1.0. It can also be calculated as 1 - specificity

$$SN = \frac{TP}{TPFN} = \frac{TP}{P}$$

#### False Negative rate

False Negative rate FPR is calculated as the number of incorrect negative predictions divided by the total number of negatives. The best false negative rate is 0.0 whereas the worst is 1.0

Name	Formula	Explanation
True Positive Rate (TP rate)	$TP / (TP + FP)$	The closer to 1, the better. TP rate = 1 when FP = 0. (No false positives)
True Negative Rate (TN rate)	$TN / (TN + FN)$	The closer to 1, the better. TN rate = 1 when FN = 0. (No false negatives)
False Positive Rate (FP rate)	$FP / (FP + TN)$	The closer to 0, the better. FP rate = 0 when FP = 0. (No false positives)
False Negative Rate (FN rate)	$FN / (FN + TP)$	The closer to 0, the better. FN rate = 0 when FN = 0. (No false negatives)

## Q16. What are F1 Score, precision and recall?

Recall -

Recall can be defined as the ratio of the total number of correctly classified positive examples divide to the total number of positive examples

High Recall indicates the class is correctly recognized small number of FN

2 Low Recall indicates the class is incorrectly recognized large number of FN

Recall is given by the relation

$$\text{Recall} = \frac{\text{TP}}{\text{TP} + \text{FN}}$$

### Precision:

To get the value of precision we divide the total number of correctly classified positive examples by the total number of predicted positive examples

High Precision indicates an example labeled as positive is indeed positive a small number of FP

2 Low Precision indicates an example labeled as positive is indeed positive large number of FP

The relation gives precision

$$\text{Precision} = \frac{\text{TP}}{\text{TP} + \text{FP}}$$

□ remember -

High recall low precision This means that most of the positive examples are correctly recognized low FN but there are a lot of false positives

Low recall high precision This shows that we miss a lot of positive examples high FN but those we predict as positive are indeed positive low FP

### F-measure/F1-Score

Since we have two measures Precision and Recall it helps to have a measurement that represents both of them We calculate an **F-measure** which uses **Harmonic Mean in place of Arithmetic Mean as it punishes the extreme values more**

The F-Measure will always be nearer to the smaller value of Precision or Recall

$$F\text{-measure} = \frac{2 * \text{Recall} * \text{Precision}}{\text{Recall} + \text{Precision}}$$

## Q17. What is RandomizedSearchCV?

Answer

Randomized search CV is used to perform a random search on hyperparameters Randomized search CV uses a fit and score method predict proba decision\_func transform etc

The parameters of the estimator used to apply these methods are optimized by cross-validated search over parameter settings

In contrast to GridSearchCV not all parameter values are tried out but rather a fixed number of parameter settings is sampled from the specified distributions The number of parameter settings that are tried is given by n\_iter

Code Example

```
class sklearn.model_selection.RandomizedSearchCV(estimator, param_distributions,
n_iter=10, scoring=None, fit_params=None, n_jobs=None, iid='warn', refit=True,
cv='warn', verbose=0, pre_dispatch='2n_jobs', random_state=None, error_score='raise-
deprecating', return_train_score='warn')
```

## Q18. What is GridSearchCV?

Answer

Grid search is the process of performing hyperparameter tuning to determine the optimal values for a given model

CODE Example -

```
from sklearn.model_selection import GridSearchCV from sklearn.svm import SVR gsc =  
GridSearchCV(estimator=SVR(kernel='rbf'), param_grid=[{'C': [0.001, 0.01, 0.1, 1, 10], 'epsilon':  
[0.001, 0.005, 0.01, 0.05, 0.1, 0.5, 1, 5], 'gamma': [0.001, 0.01, 0.05, 0.1, 0.5, 1, 5]},  
cv=5, scoring='neg_mean_squared_error', verbose=0, n_jobs=-1])
```


Grid search runs the model on all the possible range of hyperparameter values and outputs the best model

## Q19. What is BayesianSearchCV?

**Answer:**

Bayesian search in contrast to the grid and random search keeps track of past evaluation results which they use to form a probabilistic model mapping hyperparameters to a probability of a score on the objective function

$$P(score | \text{hyperparameters})$$



Code

```
from skopt import BayesSearchCV  
opt = BayesSearchCV(SVC)
```

```
□
'C'    e-6  e□6 'log-uniform'
'gamma'   e-6  e□  'log-uniform'
'degree'    8  □ integer valued parameter
'kernel'  ['linear' 'poly' 'rbf']
```

```
□
n_iter=32
cv=3
```

## Q20. What is ZCA Whitening?

### Answer:

Zero Component Analysis

Making the co-variance matrix as the Identity matrix is called whitening. This will remove the first and second-order statistical structure.


ZCA transforms the data to zero means and makes the features linearly independent of each other. In some image analysis applications especially when working with images of the color and tiny type it is frequently interesting to apply some whitening to the data before e.g. training a classifier.

**DATA SCIENCE  
INTERVIEW PREPARATION  
(30 Days of Interview  
Preparation)**

**# DAY 03**

## Q1. How do you treat heteroscedasticity in regression?

Heteroscedasticity means unequal scattered distribution. In regression analysis we generally talk about the heteroscedasticity in the context of the error term. Heteroscedasticity is the systematic change in the spread of the residuals or errors over the range of measured values. Heteroscedasticity is the problem because *Ordinary least squares (OLS)* regression assumes that all residuals are drawn from a random population that has a constant variance.



What causes Heteroscedasticity?

Heteroscedasticity occurs more often in datasets where we have a large range between the largest and the smallest observed values. There are many reasons why heteroscedasticity can exist and a generic explanation is that the error variance changes proportionally with a factor.

We can categorize Heteroscedasticity into two general types -

**Pure heteroscedasticity:-** It refers to cases where we specify the correct model and let us observe the non-constant variance in residual plots

**Impure heteroscedasticity:-** It refers to cases where you incorrectly specify the model and that causes the non-constant variance. When you leave an important variable out of a model the omitted effect is absorbed into the error term. If the effect of the omitted variable varies throughout the observed range of data it can produce the telltale signs of heteroscedasticity in the residual plots.

### How to Fix Heteroscedasticity

Redefining the variables

If your model is a cross-sectional model that includes large differences between the sizes of the observations you can find different ways to specify the model that reduces the impact of the size

---

differential To do this change the model from using the raw measure to using rates and per capita values Of course this type of model answers a slightly different kind of question You'll need to determine whether this approach is suitable for both your data and what you need to learn

### Weighted regression

It is a method that assigns each data point to a weight based on the variance of its fitted value The idea is to give small weights to observations associated with higher variances to shrink their squared residuals Weighted regression minimizes the sum of the weighted squared residuals When you use the correct weights heteroscedasticity is replaced by homoscedasticity

## Q2. What is multicollinearity, and how do you treat it?

**Multicollinearity** means independent variables are highly correlated to each other In regression analysis it's an important assumption that the regression model should not be faced with a problem of multicollinearity

If two explanatory variables are highly correlated it's hard to tell which affects the dependent variable Let's say Y is regressed against X and X2 and where X and X2 are highly correlated Then the effect of X on Y is hard to distinguish from the effect of X2 on Y because any increase in X tends to be associated with an increase in X2

Another way to look at the multicollinearity problem is Individual t-test P values can be misleading It means a P-value can be high which means the variable is not important even though the variable is important

### Correcting Multicollinearity

Remove one of the highly correlated independent variables from the model If you have two or more factors with a high VIF remove one from the model

2 Principle Component Analysis PCA - It cuts the number of interdependent variables to a smaller set of uncorrelated components Instead of using highly correlated variables use components in the model that have eigenvalue greater than

3 Run PROC VARCLUS and choose the variable that has a minimum -R2 ratio within a cluster

4 Ridge Regression - It is a technique for analyzing multiple regression data that suffer from multicollinearity

5 If you include an interaction term the product of two independent variables you can also reduce multicollinearity by "centering" the variables By "centering" it means subtracting the mean from the values of the independent variable before creating the products

### **When is multicollinearity not a problem?**

If your goal is to predict Y from a set of X variables then multicollinearity is not a problem. The predictions will still be accurate and the overall R<sup>2</sup> or adjusted R<sup>2</sup> quantifies how well the model predicts the Y values.

- 2 Multiple dummy binary variables that represent a categorical variable with three or more categories

### **Q3. What is market basket analysis? How would you do it in Python?**

Market basket analysis is the study of items that are purchased or grouped in a single transaction or multiple sequential transactions. Understanding the relationships and the strength of those relationships is valuable information that can be used to make recommendations cross-sell up-sell offer coupons etc.

Market Basket Analysis is one of the key techniques used by large retailers to uncover associations between items. It works by looking for combinations of items that occur together frequently in transactions. To put it another way it allows retailers to identify relationships between the items that people buy.

### **Q4. What is Association Analysis? Where is it used?**

*Association analysis uses a set of transactions to discover rules that indicate the likely occurrence of an item based on the occurrences of other items in the transaction.*

The technique of association rules is widely used for retail basket analysis. It can also be used for classification by using rules with class labels on the right-hand side. It is even used for outlier detection with rules indicating infrequent/abnormal association.

Association analysis also helps us to identify cross-selling opportunities for example we can use the rules resulting from the analysis to place associated products together in a catalog in the supermarket or the Webshop or apply them when targeting a marketing campaign for product B at customers who have already purchased product A.

Association rules are given in the form as below

A=>B[Support Confidence] The part before => is referred to as if Antecedent and the part after => is referred to as then Consequent

Where A and B are sets of items in the transaction data a and B are disjoint sets

Computer=>Anti-virusSoftware[Support=20% confidence=60%] Above rule says

20% transaction show Anti-virus software is bought with purchase of a Computer

2 60% of customers who purchase Anti-virus software is bought with purchase of a Computer

An example of Association Rules \* Assume there are 100 customers

0 of them bought milk 8 bought butter and 6 bought both of them 2 bought milk => bought butter


2 support = P Milk & Butter = 6/ 100 = 0.06

3 confidence = support/P Butter = 0.06/0.08 = 0.75

4 lift = confidence/P Milk = 0.75/0.06 = 7.5

## Q5. What is KNN Classifier ?

KNN means **K-Nearest Neighbour** Algorithm It can be used for both classification and regression



It is the simplest machine learning algorithm Also known as **lazy learning** why? Because it does not create a generalized model during the time of training so the testing phase is very important where it does the actual job Hence Testing is very costly - in terms of time & money Also called an instance-based or memory-based learning

In k-NN classification the output is a class membership An object is classified by a plurality vote of its neighbors with the object being assigned to the class most common among its k nearest neighbors k is a positive integer typically small If k = 1 then the object is assigned to the class of that single nearest neighbor

In **k-NN regression** the output is the property value for the object. This value is the average of the values of k nearest neighbors.

#### Distance functions

**Euclidean**

$$\sqrt{\sum_{i=1}^k (x_i - y_i)^2}$$

**Manhattan**

$$\sum_{i=1}^k |x_i - y_i|$$

**Minkowski**

$$\left( \sum_{i=1}^k (|x_i - y_i|)^q \right)^{1/q}$$

All three distance measures are only valid for continuous variables. In the instance of categorical variables the Hamming distance must be used.

#### Hamming Distance

$$D_H = \sum_{i=1}^k |x_i - y_i|$$

$$x = y \Rightarrow D = 0$$

$$x \neq y \Rightarrow D = 1$$

X	Y	Distance
Male	Male	0
Male	Female	1

**How to choose the value of K:** K value is a hyperparameter which needs to choose during the time of model building.

Also a small number of neighbors are most flexible fit which will have a low bias but the high variance and a large number of neighbors will have a smoother decision boundary which means lower variance but higher bias.

We should choose an odd number if the number of classes is even. It is said the most common values are to be 3 & 5.

## Q6. What is Pipeline in sklearn ?

A pipeline is what chains several steps together once the initial exploration is done. For example some codes are meant to transform features normalize numerically or turn text into vectors or fill up missing data and they are transformers; other codes are meant to predict variables by fitting an algorithm.

such as random forest or support vector machine they are estimators Pipeline chains all these together which can then be applied to training data in block

Example of a pipeline that imputes data with the most frequent value of each column and then fit a decision tree classifier

```
From sklearn.pipeline import Pipeline  
steps = [ 'imputation' Imputer missing_values='NaN' strategy = 'most_frequent' axis=0  
         'clf' DecisionTreeClassifier ]  
pipeline = Pipeline steps  
clf = pipeline fit X_train y_train ````
```

Instead of fitting to one model it can be looped over several models to find the best one

```
classifiers = [ KNeighborsClassifier 5 RandomForestClassifier GradientBoostingClassifier ]  
for clf in classifiers
```

```
steps = [ 'imputation' Imputer missing_values='NaN' strategy = 'most_frequent' axis=0  
         'clf' clf ]
```

```
pipeline = Pipeline steps
```

I also learned the pipeline itself can be used as an estimator and passed to cross-validation or grid search

```
from sklearn.model_selection import KFold  
from sklearn.model_selection import cross_val_score  
kfold = KFold n_splits= 0 random_state=seed  
results = cross_val_score pipeline X_train y_train cv=kfold  
print results mean
```

## Q7. What is Principal Component Analysis(PCA), and why we do?

The main idea of principal component analysis PCA is to reduce the dimensionality of a data set consisting of many variables correlated with each other either heavily or lightly while retaining the variation present in the dataset up to the maximum extent The same is done by transforming the variables to a new set of variables which are known as the principal components or simply the PCs and are orthogonal ordered such that the retention of variation present in the original variables decreases as we move down in the order So in this way the st principal component retains maximum variation that was present in the original components The principal components are the eigenvectors of a covariance matrix and hence they are orthogonal

Main important points to be considered

- Normalize the data
- 2 Calculate the covariance matrix
- 3 Calculate the eigenvalues and eigenvectors
- 4 Choosing components and forming a feature vector
- 5 Forming Principal Components

## **Q8. What is t-SNE?**

t-SNE t-Distributed Stochastic Neighbor Embedding is a non-linear dimensionality reduction algorithm used for exploring high-dimensional data. It maps multi-dimensional data to two or more dimensions suitable for human observation. With the help of the t-SNE algorithms you may have to plot fewer exploratory data analysis plots next time you work with high dimensional data.

## **Q9. VIF(Variation Inflation Factor),Weight of Evidence & Information**

### **Value. Why and when to use?**

#### **Variation Inflation Factor**

It provides an index that measures how much the variance the square of the estimate's standard deviation of an estimated regression coefficient is increased because of collinearity

$VIF = \frac{R^2}{1 - R^2}$  where  $R^2$  of jth variable is the coefficient of determination of the model that includes all independent variables except the jth predictor

Where  $R^2$  of j-th variable is the multiple  $R^2$  for the regression of  $X_j$  on the other independent variables a regression that does not involve the dependent variable Y


If  $VIF > 5$  then there is a problem with multicollinearity

#### **Understanding VIF**

If the variance inflation factor of a predictor variable is 5 this means that variance for the coefficient of that predictor variable is 5 times as large as it would be if that predictor variable were uncorrelated with the other predictor variables

In other words if the variance inflation factor of a predictor variable is 5 this means that the standard error for the coefficient of that predictor variable is 2.23 times  $\sqrt{5} = 2.23$  as large as it would be if that predictor variable were uncorrelated with the other predictor variables

**Weight of evidence (WOE) and information value (IV)** are simple yet powerful techniques to perform variable transformation and selection



The formula to create WOE and IV is

$$WOE = \ln\left(\frac{\text{Event}\%}{\text{Non Event}\%}\right)$$

$$IV = \sum (\text{Event}\% - \text{Non Event}\%) * \ln\left(\frac{\text{Event}\%}{\text{Non Event}\%}\right)$$

Here is a simple table that shows how to calculate these values

Variable Name	Min. Value	Max. Value	Count	# Event	# Non Event	Event%	Non event%	WOE	Event% - Non event%	IV
Age	10	20	1200	150	1050	28.3%	19.0%	0.3992	9.3%	0.03718
Age	21	30	900	120	780	22.6%	14.1%	0.4733	8.5%	0.04040
Age	31	40	1090	110	980	20.8%	17.7%	0.1580	3.0%	0.00479
Age	41	50	1460	100	1360	18.9%	24.6%	-0.2650	-5.7%	0.01517
Age	50	inf	1410	50	1360	9.4%	24.6%	-0.9582	-15.2%	0.14525
Total			<b>6060</b>	<b>530</b>	<b>5530</b>					<b>0.24279</b>

The IV value can be used to select variables quickly


Information Value (IV)	Predictive Power
< 0.02	useless for prediction
0.02 to 0.1	weak predictor
0.1 to 0.3	medium predictor
0.3 to 0.5	strong predictor
> 0.5	suspicious or too good to be true

## Q10: How to evaluate that data does not have any outliers ?

In statistics outliers are data points that don't belong to a certain population. It is an abnormal observation that lies far away from other values. An outlier is an observation that diverges from otherwise well-structured data.


### Detection:

**Method 1 Standard Deviation:** In statistics If a data distribution is approximately normal then about 68% of the data values lie within one standard deviation of the mean and about 95% are within two standard deviations and about 99.7% lie within three standard deviations




Therefore if you have any data point that is more than 3 times the standard deviation then those points are very likely to be anomalous or outliers.


**Method 2 Boxplots** Box plots are a graphical depiction of numerical data through their quantiles. It is a very simple but effective way to visualize outliers. Think about the lower and upper whiskers as the boundaries of the data distribution. Any data points that show above or below the whiskers can be considered outliers or anomalous.



**Method 3 - Violin Plots** Violin plots are similar to box plots except that they also show the probability density of the data at different values usually smoothed by a kernel density estimator. Typically a violin plot will include all the data that is in a box plot a marker for the median of the data a box or marker indicating the interquartile range and possibly all sample points if the number of samples is not too high.



**Method 4 - Scatter Plots** A scatter plot is a type of plot or mathematical diagram using Cartesian coordinates to display values for typically two variables for a set of data. The data are displayed as a collection of points each having the value of one variable determining the position on the horizontal axis and the value of the other variable determining the position on the vertical axis.



The points which are very far away from the general spread of data and have a very few neighbors are considered to be outliers.

## Q11: What you do if there are outliers?

Following are the approaches to handle the outliers

- Drop the outlier records
- 2 Assign a new value If an outlier seems to be due to a mistake in your data you try imputing a value
- 3 If percentage-wise the number of outliers is less but when we see numbers there are several then in that case dropping them might cause a loss in insight We should group them in that case and run our analysis separately on them

## Q12: What are the encoding techniques you have applied with Examples ?

In many practical data science activities the data set will contain categorical variables These variables are typically stored as text values" Since machine learning is based on mathematical equations it would cause a problem when we keep categorical variables as is

Let's consider the following dataset of fruit names and their weights

Some of the common encoding techniques are

**Label encoding:** In label encoding we map each category to a number or a label The labels chosen for the categories have no relationship So categories that have some ties or are close to each other lose such information after encoding

**One - hot encoding:** In this method we map each category to a vector that contains 1 and 0 denoting the presence of the feature or not The number of vectors depends on the categories which we want to keep For high cardinality features this method produces a lot of columns that slows down the learning significantly

## Q13: Tradeoff between bias and variances, the relationship between them.


Whenever we discuss model prediction it s important to understand prediction errors bias and variance The prediction error for any machine learning algorithm can be broken down into three parts

- Bias Error
- Variance Error
- Irreducible Error

The irreducible error cannot be reduced regardless of what algorithm is used. It is the error introduced from the chosen framing of the problem and may be caused by factors like unknown variables that influence the mapping of the input variables to the output variable.

**Bias:** Bias means that the model favors one result more than the others. Bias is the simplifying assumptions made by a model to make the target function easier to learn. The model with high bias pays very little attention to the training data and oversimplifies the model. It always leads to a high error in training and test data.

**Variance:** Variance is the amount that the estimate of the target function will change if different training data was used. The model with high variance pays a lot of attention to training data and does not generalize on the data which it hasn't seen before. As a result, such models perform very well on training data but have high error rates on test data.



So the end goal is to come up with a model that balances both Bias and Variance. This is called *Bias Variance Trade-off*. To build a good model we need to find a good balance between bias and variance such that it minimizes the total error.

## Q14: What is the difference between Type 1 and Type 2 error and severity of the error?

### Type I Error

A Type I error is often referred to as a "false positive" and is the incorrect rejection of the true null hypothesis in favor of the alternative.

In the example above the null hypothesis refers to the natural state of things or the absence of the tested effect or phenomenon i.e. stating that the patient is HIV negative. The alternative hypothesis states that the patient is HIV positive. Many medical tests will have the disease they are testing for as the alternative hypothesis and the lack of that disease as the null hypothesis.

---

A Type I error would thus occur when the patient doesn't have the virus but the test shows that they do. In other words, the test incorrectly rejects the true null hypothesis that the patient is HIV negative.

### Type II Error

A Type II error is the inverse of a Type I error and is the false acceptance of a null hypothesis that is not true, i.e., a false negative. A Type II error would entail the test telling the patient they are free of HIV when they are not.

Considering this HIV example, which error type do you think is more acceptable? In other words, would you rather have a test that was more prone to Type I or Type II error? With HIV, the momentary stress of a false positive is likely better than feeling relieved at a false negative and then failing to take steps to treat the disease. Pregnancy tests, blood tests, and any diagnostic tool that has serious consequences for the health of a patient are usually overly sensitive for this reason—they should err on the side of a false positive.

But in most fields of science, Type II errors are seen as less serious than Type I errors. With the Type II error, a chance to reject the null hypothesis was lost, and no conclusion is inferred from a non-rejected null. But the Type I error is more serious because you have wrongly rejected the null hypothesis and ultimately made a claim that is not true. In science, finding a phenomenon where there is none is more egregious than failing to find a phenomenon where there is.

## Q15: What is binomial distribution and polynomial distribution?

**Binomial Distribution:** A binomial distribution can be thought of as simply the probability of a SUCCESS or FAILURE outcome in an experiment or survey that is repeated multiple times. The binomial is a type of distribution that has two possible outcomes—the prefix "bi" means two or twice. For example, a coin toss has only two possible outcomes: heads or tails, and taking a test could have two possible outcomes: pass or fail.

**Multinomial/Polynomial Distribution:** Multi or Poly means many. In probability theory, the multinomial distribution is a generalization of the binomial distribution. For example, it models the probability of counts of each side for rolling a k-sided die n times. For n independent trials, each of which leads to success for exactly one of k categories, with each category having a given fixed success probability, the multinomial distribution gives the probability of any particular combination of numbers of successes for the various categories.

## Q16: What is the Mean Median Mode standard deviation for the sample and population?

**Mean** It is an important technique in statistics Arithmetic Mean can also be called an average It is the number of the quantity obtained by summing two or more numbers/variables and then dividing the sum by the number of numbers/variables

**Mode** The mode is also one of the types for finding the average A mode is a number that occurs most frequently in a group of numbers Some series might not have any mode; some might have two modes which is called a bimodal series

In the study of statistics the three most common averages in statistics are mean median and mode

**Median** is also a way of finding the average of a group of data points It s the middle number of a set of numbers There are two possibilities the data points can be an odd number group or it can be an even number group

If the group is odd arrange the numbers in the group from smallest to largest The median will be the one which is exactly sitting in the middle with an equal number on either side of it If the group is even arrange the numbers in order and pick the two middle numbers and add them then divide by 2 It will be the median number of that set

**Standard Deviation (Sigma)** Standard Deviation is a measure of how much your data is spread out in statistics

## Q17: What is Mean Absolute Error ?

**What is Absolute Error?** Absolute Error is the amount of error in your measurements It is the difference between the measured value and the true value For example if a scale states 90 pounds but you know your true weight is 89 pounds then the scale has an absolute error of 90 lbs - 89 lbs = lbs

This can be caused by your scale not measuring the exact amount you are trying to measure For example your scale may be accurate to the nearest pound If you weigh 89.6 lbs the scale may round up and give you 90 lbs In this case the absolute error is 90 lbs - 89.6 lbs = 4 lbs

**Mean Absolute Error** The Mean Absolute Error MAE is the average of all absolute errors The formula is mean absolute error

$$\text{MAE} = \frac{1}{n} \sum_{i=1}^n |x_i - \bar{x}|$$

Where

$n$  = the number of errors  $\Sigma$  = summation symbol which means add them all up  $|x_i - \bar{x}|$  = the absolute errors The formula may look a little daunting but the steps are easy

Find all of your absolute errors  $x_i - \bar{x}$  Add them all up Divide by the number of errors For example if you had 0 measurements divide by 0

## Q18: What is the difference between long data and wide data?

There are many different ways that you can present the same dataset to the world Let's take a look at one of the most important and fundamental distinctions whether a dataset is wide or long

The difference between wide and long datasets boils down to whether we prefer to have more columns in our dataset or more rows

**Wide Data** A dataset that emphasizes putting additional data about a single subject in columns is called a wide dataset because as we add more columns the dataset becomes wider

**Long Data** Similarly a dataset that emphasizes including additional data about a subject in rows is called a long dataset because as we add more rows the dataset becomes longer It's important to point out that there's nothing inherently good or bad about wide or long data

In the world of data wrangling we sometimes need to make a long dataset wider and we sometimes need to make a wide dataset longer However it is true that as a general rule data scientists who embrace the concept of tidy data usually prefer longer datasets over wider ones

## Q19: What are the data normalization method you have applied, and why?

**Normalization** is a technique often applied as part of data preparation for machine learning The goal of normalization is to change the values of numeric columns in the dataset to a common scale without distorting differences in the ranges of values For machine learning every dataset does not require normalization It is required only when features have different ranges

In simple words when multiple attributes are there but attributes have values on different scales this may lead to poor data models while performing data mining operations So they are normalized to bring all the attributes on the same scale usually something between 0

It is not always a good idea to normalize the data since we might lose information about maximum and minimum values Sometimes it is a good idea to do so

*For example*, ML algorithms such as Linear Regression or Support Vector Machines typically converge faster on normalized data But on algorithms like K-means or K Nearest Neighbours normalization could

be a good choice or a bad depending on the use case since the distance between the points plays a key role here

person_name	Salary	Year_of_experience	Expected Position Level	
Aman	100000	10	2	
Abhinav	78000	7	4	
Ashutosh	32000	5	8	
Dishi	55000	6	7	
Abhishek	92000	8	3	
Avantika	120000	15	1	
Ayushi	65750	7	5	

The attributes salary and year\_of\_experience are on different scale and hence attribute salary can take high priority over attribute year\_of\_experience in the model.

### Types of Normalisation :

**1 Min-Max Normalization:** In most cases standardization is used feature-wise

$$\hat{X}[:, i] = \frac{X[:, i] - \min(X[:, i])}{\max(X[:, i]) - \min(X[:, i])}$$

**2 Z-score normalization** In this technique values are normalized based on a mean and standard deviation of the data

$$v' = \frac{v - \bar{A}}{\sigma_A}$$

v v is new and old of each entry in data respectively  $\sigma_A$  A is the standard deviation and mean of A respectively

standardization or Z-score normalization is that the features will be rescaled so that they'll have the properties of a standard normal distribution with

$\mu=0$  and  $\sigma=1$  where  $\mu$  is the mean average and  $\sigma$  is the standard deviation from the mean; standard scores also called z scores of the samples are calculated as follows

$$z = \frac{x - \mu}{\sigma}$$

## Q20: What is the difference between normalization and Standardization with example?

In ML every practitioner knows that feature scaling is an important issue. The two most discussed scaling methods are **Normalization** and **Standardization**. Normalization typically means it rescales the values into a range of [0, 1].

It is an alternative approach to Z-score normalization or standardization is the so-called Min-Max scaling often also called normalization - a common cause for ambiguities. In this approach the data is scaled to a fixed range - **usually 0 to 1**. Scikit-Learn provides a transformer called **MinMaxScaler** for this. A Min-Max scaling is typically done via the following equation:

$$X_{\text{norm}} = \frac{X - X_{\text{min}}}{X_{\text{max}} - X_{\text{min}}}$$

**Example with sample data: Before Normalization:** Attribute Price in Dollars Storage Space Camera

- Attribute Price in Dollars Storage Space Camera
- Mobile 250 6 2
- Mobile 2 200 6 8
- Mobile 3 300 32 6
- Mobile 4 275 32 8
- Mobile 5 225 6 6

**After Normalization: (Values ranges from 0-1 which is working as expected)**

- Attribute Price in Dollars Storage Space Camera
- Mobile 0.5 0.05
- Mobile 2 0 0 0
- Mobile 3
- Mobile 4 0.75 0
- Mobile 5 0.25 0

Standardization or Z-score normalization typically means rescales data to have a mean of 0 and a standard deviation of unit variance. Formula  $Z \text{ or } X_{\text{new}} = \frac{(x - \mu)}{\sigma}$  where  $\mu$  is the mean average and  $\sigma$  is the standard deviation from the mean; standard scores also called z scores. Scikit-Learn provides a transformer called **StandardScaler** for standardization. **Example:** Let's take an approximately normally distributed set of numbers 2, 2, 3, 3, 3, 4, 4, and 5. Its mean is 3 and its standard deviation is 2. Now let's subtract the mean from all data points we get a new data set of -2, -1, 0, 0, 0, 1, 1, and 2. Now let's divide each data point by 2. As you can see in the picture below we get -0.82, -0.82, 0, 0, 0, 0.82, 0.82, and 0.63.

**DATA SCIENCE  
INTERVIEW PREPARATION  
(30 Days of Interview  
Preparation)**

**# DAY 04**

**Statistics**

## Q1. What is upsampling and downsampling with examples?

The classification data set with skewed class proportions is called an imbalanced data set. Classes which make up a large proportion of the data sets are called majority classes. Those make up smaller proportions are minority classes.

Degree of imbalance Proportion of Minority Class

- 1>> Mild 20-40% of the data set
- 2>> Moderate 1-20% of the data set
- 3>> Extreme <1% of the data set

If we have an imbalanced data set, first try training on the true distribution. If the model works well and generalises, you are done! If not, try the following up sampling and down sampling technique.

### 1. Up-sampling

Upsampling is the process of randomly duplicating observations from the minority class to reinforce its signal.

First, we will import the resampling module from Scikit-Learn:

Module for resampling Python

1- From sklearn.utils import resample

Next, we will create a new Data Frame with an up-sampled minority class. Here are the steps:

1- First, we will separate observations from each class into different Data Frames.

2- Next, we will resample the minority class with replacement, setting the number of samples to match that of the majority class.

3- Finally, we'll combine the up-sampled minority class Data Frame with the original majority class Data Frame.

### 2-Down-sampling

Downsampling involves randomly removing observations from the majority class to prevent its signal from dominating the learning algorithm.

The process is similar to that of sampling. Here are the steps:

1-First, we will separate observations from each class into different Data Frames.

2-Next, we will resample the majority class without replacement, setting the number of samples to match that of the minority class.

3-Finally, we will combine the down-sampled majority class Data Frame with the original minority class Data Frame.

## **Q2. What is the statistical test for data validation with an example,**

**Chi-square, ANOVA test, Z statics, T statics, F statics,**

### **Hypothesis Testing?**

Before discussing the different statistical test, we need to get a clear understanding of what a null hypothesis is. A null hypothesis proposes that has no significant difference exists in the set of a given observation.

**Null:** Two samples mean are equal. **Alternate:** Two samples mean are not equal.

For rejecting the null hypothesis, a test is calculated. Then the test statistic is compared with a critical value, and if found to be greater than the critical value, the hypothesis will be rejected.

### **Critical Value:-**

Critical values are the point beyond which we reject the null hypothesis. Critical value tells us, what is the probability of N number of samples, belonging to the same distribution. Higher, the critical value which means lower the probability of N number of samples belonging to the same distribution.

Critical values can be used to do hypothesis testing in the following way.

1. Calculate test statistic
2. Calculate critical values based on the significance level alpha
3. Compare test statistics with critical values.

**IMP-**If the test statistic is lower than the critical value, accept the hypothesis or else reject the hypothesis.

### **Chi-Square Test:-**

A chi-square test is used if there is a relationship between two categorical variables.

---

Chi-Square test is used to determine whether there is a significant difference between the expected frequency and the observed frequency in one or more categories. Chi-square is also called the non-parametric test as it will not use any parameter

## **2-Anova test:-**

ANOVA, also called an analysis of variance, is used to compare multiples (three or more) samples with a single test.

Useful when there are more than three populations. Anova compares the variance within and between the groups of the population. If the variation is much larger than the within variation, the means of different samples will not be equal. If the between and within variations are approximately the same size, then there will be no significant difference between sample means. Assumptions of ANOVA: 1-All populations involved follow a normal distribution. 2-All populations have the same variance (or standard deviation). 3-The samples are randomly selected and independent of one another.

ANOVA uses the mean of the samples or the population to reject or support the null hypothesis. Hence it is called parametric testing.

## **3-Z Statics:-**

In a z-test, the samples are assumed to be normal distributed. A z score is calculated with population parameters as “population mean” and “population standard deviation” and it is used to validate a hypothesis that the sample drawn belongs to the same population.

The statistics used for this hypothesis testing is called z-statistic, the score for which is calculated as  $z = (x - \mu) / (\sigma / \sqrt{n})$ , where  $x$ = sample mean  $\mu$  = population mean  $\sigma / \sqrt{n}$  = population standard deviation If the test statistic is lower than the critical value, accept the hypothesis or else reject the hypothesis

## **4- T Statics:-**

A t-test used to compare the mean of the given samples. Like z-test, t-test also assumed a normal distribution of the samples. A t-test is used when the population parameters (mean and standard deviation) are unknown.

There are three versions of t-test

1. Independent samples t-test which compare means for two groups
2. Paired sample t-test which compares mean from the same group at different times
3. Sample t-test, which tests the mean of the single group against the known mean. The statistic for hypothesis testing is called t-statistic, the score for which is calculated as  $t = (x_1 - x_2) / (\sigma / \sqrt{n_1} + \sigma / \sqrt{n_2})$ , where

$x_1$  = mean of sample A,  $x_2$  = mean of sample B,

$n_1$  = size of sample 1  $n_2$  = size of sample 2

## 5- F Statics:-

The F-test is designed to test if the two population variances are equal. It compares the ratio of the two variances. Therefore, if the variances are equal, then the ratio of the variances will be 1.

The F-distribution is the ratio of two independent chi-square variables divided by their respective degrees of freedom.

$F = s_1^2 / s_2^2$  and where  $s_1^2 > s_2^2$ .

If the null hypothesis is true, then the F test-statistic given above can be simplified. This ratio of sample variances will be tested statistic used. If the null hypothesis is false, then we will reject the null hypothesis that the ratio was equal to 1 and our assumption that they were equal.

## Q3. What is the Central limit theorem?

### Central Limit Theorem

Definition: The theorem states that as the size of the sample increases, the distribution of the mean across multiple samples will approximate a Gaussian distribution (Normal). Generally, sample sizes equal to or greater than 30 are considered sufficient for the CLT to hold. It means that the distribution of the sample means is normally distributed. The average of the

---

sample means will be equal to the population mean. This is the key aspect of the theorem.

Assumptions:

1. The data must follow the randomization condition. It must be sampled randomly
2. Samples should be independent of each other. One sample should not influence the other samples
3. Sample size should be no more than 10% of the population when sampling is done without replacement
4. The sample size should be sufficiently large. The mean of the sample means is denoted as:

$$\mu \bar{X} = \mu$$

Where,

$\mu \bar{X}$  = Mean of the sample means  $\mu$  = Population mean and, the standard deviation of the sample mean is denoted as:

$$\sigma \bar{X} = \sigma / \sqrt{n}$$

Where,

$\sigma \bar{X}$  = Standard deviation of the sample mean  $\sigma$  = Population standard deviation  $n$  = sample size

A sufficiently large sample size can predict the characteristics of a population accurately. For Example, we shall take a uniformly distributed data:

Randomly distributed data: Even for a randomly (Exponential) distributed data the plot of the means is normally distributed.


The advantage of CLT is that we need not worry about the actual data since the means of it will always be normally distributed. With this, we can create component intervals, perform T-tests and ANOVA tests from the given samples.

## Q4. What is the correlation and coefficient?

### What is the Correlation Coefficient?

The correlation coefficient is a statistical measure that calculates the strength of the relationship between the relative movements of two

variables. We use it to measure both the strength and direction of a linear relationship between two variables the values range between -1.0 and 1.0. A calculated number greater than 1.0 or less than -1.0 means that there was an error in the correlation measurement. A correlation of -1.0 shows a perfect negative correlation, while a correlation of 1.0 shows a perfect positive correlation.



Correlation coefficient formulas are used to find how strong a relationship is between data. The formulas return a value between -1 and 1, where:

1 indicates a strong positive relationship. -1 indicates a strong negative relationship. A result of zero indicates no relationship at all.

## Meaning


1. A correlation coefficient of 1 means that for every positive increase in one variable, there is a positive increase in a fixed proportion in the other. For example, shoe sizes go up in (almost) perfect correlation with foot length.
2. A correlation coefficient of -1 means that for every positive increase in one variable, there is a negative decrease of a fixed proportion in the other. For example, the amount of gas in a tank decreases in (almost) perfect correlation with speed.
3. Zero means that for every increase, there isn't a positive or negative increase. The two just aren't related.

## What is a Negative Correlation?

Negative correlation is a relationship between two variables in which one variable increases as the other decreases, and vice versa. In statistics, a perfect negative correlation is represented by the value -1. Negative correlation or inverse correlation is a relationship between two variables whereby they move in opposite directions. If variables X and Y have a negative correlation (or are negatively correlated), as X increases in value, Y will decrease; similarly, if X decreases in value, Y will increase.

## What Is Positive Correlation?

Positive correlation is a relationship between two variables in which both variables move in tandem—that is, in the same direction. A positive correlation exists when one variable decreases as the other variable decreases or one variable increases while the other increases.



We use the correlation coefficient to measure the strength and direction of the linear relationship between two numerical variables X and Y. The correlation coefficient for a sample of data is denoted by  $r$ .

## Pearson Correlation Coefficient

Pearson is the most widely used correlation coefficient. Pearson correlation measures the linear association between continuous variables. In other words, this coefficient quantifies the degree to which a relationship between two variables can be described by a line. Formula developed by Karl Pearson over 120 years ago is still the most widely used today. The formula for the correlation ( $r$ ) is

Correlation Coefficient Formula

$$r = \frac{n(\Sigma xy) - (\Sigma x)(\Sigma y)}{\sqrt{[n\Sigma x^2 - (\Sigma x)^2][n\Sigma y^2 - (\Sigma y)^2]}}$$

Where n is the number of pairs of data;

Are the sample means of all the x-values and all the y-values, respectively; and sx and sy are the sample standard deviations of all the x- and y-values, respectively.

1. Find the mean of all the x-values and mean of all y-values.
2. Find the standard deviation of all the x-values (call it sx) and the standard deviation of all the y-values (call it sy). For example, to find sx, you would use the following equation:
3. For each of the n pairs (x, y) in the data set, take
4. Add up the n results from Step 3.
5. Divide the sum by sx \* sy.
6. Divide the result by n – 1, where n is the number of (x, y) pairs. (It's the same as multiplying by 1 over n – 1.) This gives you the correlation, r.

# Deep Learning

**Q5: What is the difference between machine learning and deep**

**learning?**

**Machine Learning | deep learning**

Machine Learning is a technique to learn from that data and then apply what has been learnt to make an informed decision | The main difference between deep and machine learning is, machine learning models become better progressively but the model still needs some guidance. If a machine-learning model returns an inaccurate prediction then the programmer needs to fix that problem explicitly but in the case of deep learning, the model does it by himself.

>Machine Learning can perform well with small size data also | Deep Learning does not perform as good with smaller datasets.

>Machine learning can work on some low-end machines also | Deep Learning involves many matrix multiplication operations which are better suited for GPUs

>Features need to be identified and extracted as per the domain before pushing them to the algorithm | Deep learning algorithms try to learn high-level features from data.

>It is generally recommended to break the problem into smaller chunks, solve them and then combine the results | It generally focusses on solving the problem end to end

>Training time is comparatively less | Training time is comparatively more


>Results are more interpretable | Results Maybe more accurate but less interpretable

> No use of Neural networks | uses neural networks

> Solves comparatively less complex problems | Solves more complex problems.

## **Q6: What is perceptron and how it is related to human neurons?**

If we focus on the structure of a biological neuron, it has dendrites, which are used to receive inputs. These inputs are summed in the cell body and using the Axon it is passed on to the next biological neuron as shown below.




**Dendrite:** Receives signals from other neurons

**Cell Body:** Sums all the inputs


**Axon:** It is used to transmit signals to the other cells

Similarly, a perceptron receives multiple inputs, applies various transformations and functions and provides an output. A Perceptron is a linear model used for binary classification. It models a neuron, which has a set of inputs, each of which is given a specific weight. The neuron computes some function on these weighted inputs and gives the output.



## Q7: Why deep learning is better than machine learning?

Though traditional ML algorithms solve a lot of our cases, they are not useful while working with high dimensional data that is where we have a large number of inputs and outputs. For example, in the case of handwriting recognition, we have a large amount of input where we will have different types of inputs associated with different types of handwriting.



The second major challenge is to tell the computer what are the features it should look for that will play an important role in predicting the outcome as well as to achieve better accuracy while doing so.

### **Q8: What kind of problem can be solved by using deep learning?**

Deep Learning is a branch of Machine Learning, which is used to solve problems in a way that mimics the human way of solving problems.

Examples:

- Image recognition
- Object Detection
- Natural Language processing- Translation, Sentence formations, text to speech, speech to text
- understand the semantics of actions

### **Q9: List down all the activation function using mathematical**

**Expression and example. What is the activation function?**

**Activation functions** are very important for an Artificial Neural Network to learn and make sense of something complicated and the Non-linear complex functional mappings between the inputs and response variable. They introduce non-linear properties to our Network. Their main purposes are to convert an input signal of a node in an A-NN to an output signal.


*So why do we need Non-Linearities?*

Non-linear functions are those, which have a degree more than one, and they have a curvature when we plot a Non-Linear function. Now we need a Neural Network Model to learn and represent almost anything and any arbitrary complex function, which maps inputs to outputs. Neural-Networks are considered Universal Function Approximations. It means that they can compute and learn any function at all.

*Most popular types of Activation functions -*


- Sigmoid or Logistic
- Tanh — Hyperbolic tangent
- ReLu -Rectified linear units

**Sigmoid Activation function:** It is a activation function of form  $f(x) = 1 / (1 + \exp(-x))$ . Its Range is between 0 and 1. It is an S-shaped curve. It is easy to understand.




**Hyperbolic Tangent function- Tanh :** It's mathematical formula is  $f(x) = (\exp(x) - \exp(-x)) / (\exp(x) + \exp(-x))$ . Now it's the output is zero centred because its range in between -1 to 1 i.e.  $-1 < \text{output} < 1$  . Hence optimisation is easier in this method; Hence in practice, it is always preferred over Sigmoid function.

### hyperbolic tangent function




**ReLU- Rectified Linear units:** It has become more popular in the past couple of years. It was recently proved that it has six times improvement in convergence from Tanh function. It's  $R(x) = \max(0, x)$  i.e. if  $x < 0$ ,  $R(x) = 0$  and if  $x \geq 0$ ,  $R(x) = x$ . Hence as seen that mathematical form of this function, we can see that it is very simple and efficient. Many times in Machine learning and computer science we notice that most simple and consistent techniques and methods are only preferred and are the best. Hence, it avoids and rectifies the vanishing gradient problem. Almost all the deep learning Models use ReLU nowadays.



**Q10: Detail explanation about gradient decent using example and Mathematical expression?**

Gradient descent is an optimisation algorithm used to minimize some function by iteratively moving in the direction of steepest descent as defined by negative of the gradient. In machine learning, we used gradient descent to update the parameters of our model. Parameters refer to coefficients in the Linear Regression and weights in neural networks.



The size of these steps called the learning rate. With the high learning rate, we can cover more ground each step, but we risk overshooting the lower point since the slope of the hill is constantly changing. With a very lower learning rate, we can confidently move in the direction of the negative gradient because we are recalculating it so frequently. The Lower learning rate is more precise, but calculating the gradient is time-consuming, so it will take a very large time to get to the bottom.

## Math

Now let's run gradient descent using new cost function. There are two parameters in cost function we can control:  $m$  (weight) and  $b$  (bias). Since we need to consider that the impact each one has on the final prediction, we need to use partial derivatives. We calculate the partial derivative of the cost function concerning each parameter and store the results in a gradient.

## Math

Given the cost function:

$$f(m, b) = \frac{1}{N} \sum_{i=1}^n (y_i - (mx_i + b))^2$$

The gradient can be calculated as:


$$f'(m, b) = \begin{bmatrix} \frac{df}{dm} \\ \frac{df}{db} \end{bmatrix} = \begin{bmatrix} \frac{1}{N} \sum -2x_i(y_i - (mx_i + b)) \\ \frac{1}{N} \sum -2(y_i - (mx_i + b)) \end{bmatrix}$$

To solve for the gradient, we iterate by our data points using our new m and b values and compute the partial derivatives. This new gradient tells us about the slope of the cost function at our current position (current parameter values) and the directions we should move to update our parameters. The learning rate controls the size of our update.

### **Q11: What is backward propagation?**

**Back-propagation** is the essence of the neural net training and this method of fine-tuning the weights of a neural net based on the errors rate obtained in the previous epoch. Proper tuning of the weights allows us to reduce error rates and to make the model reliable by increasing its generalisation.

Backpropagation is a short form of "backward propagation of errors." This is the standard method of training artificial neural networks. This helps to calculate the gradient of a loss function with respects to all the weights in the network.



Most prominent advantages of Backpropagation are:

- Backpropagation is the fast, simple and easy to program.
- It has no parameters to tune apart from the numbers of input.
- It is the flexible method as it does not require prior knowledge about the network
- It is the standard method that generally works well.
- It does not need any special mentions of the features of the function to be learned.


## The BackPropagation Algorithm

Main idea:

For each example in the training set:

- compute the output signal
- compute the error corresponding to the output level
- propagate the error back into the network and store the corresponding delta values for each layer
- adjust each weight by using the error signal and input signal for each layer

Computation of the error signal (BACKWARD)



Computation of the output signal (FORWARD)

## Q12: How we assign weights in deep learning?

We already know that in a neural network, weights are usually initialised randomly and that kind of initialisation takes a fair/significant amount of repetitions to converge to the least loss and reach the ideal weight matrix. The problem is, that kind of initialisation is prone to vanishing or exploding gradient problems.

*General ways to make it initialise better weights:*

ReLU activation function in the deep nets.

1. Generate a random sample of weights from a Gaussian distribution having mean 0 and a standard deviation of 1.
2. Multiply the sample with the square root of  $(2/n_i)$ . Where  $n_i$  is the number of input units for that layer.

b) Likewise, if you're using Tanh activation function :

1. Generate a random sample of weights from a Gaussian distribution having mean 0 and a standard deviation of 1.
2. Multiply the sample with the square root of  $(1/n_i)$  where  $n_i$  is several input units for that layer.

### **Q13: What is optimiser in deep learning, and which one is the best?**

Deep learning is an iterative process. With so many hyperparameters to tune or methods to try, it is important to be able to train models fast, to quickly complete the iterative cycle. This is the key to increase the speed and efficiency of a machine learning team.

Hence the importance of optimisation algorithms such as stochastic gradient descent, min-batch gradient descent, gradient descent with momentum and the Adam optimiser.

Adam optimiser is the best one.

Given an algorithm  $f(x)$ , it helps in either minimisation or maximisation of the value of  $f(x)$ . In this context of deep learning, we use optimisation algorithms to train the neural network by optimising the cost function  $J$ .

The cost function is defined as:

$$J(W, b) = \sum_{i=1}^m L(y'^i, y^i)$$

The value of the cost function  $J$  is the mean of the loss  $L$  between the predicted value  $y'$  and actual value  $y$ . The value  $y''$  is obtained during the forward propagation step and makes use of the Weights  $W$  and biases  $b$  of the network. With the help of optimisation algorithms, we minimise the value of Cost Function  $J$  by updating the values of trainable parameters  $W$  and  $b$ .

**Q14: What is gradient descent, mini-batch gradient descent, batch gradient decent, stochastic gradient decent and adam?**

### Gradient Descent

it is an iterative machine learning optimisation algorithm to reduce the cost function, and help models to make accurate predictions.

Gradient indicates the direction of increase. As we want to find the minimum points in the valley, we need to go in the opposite direction of the gradient. We update the parameters in the negative gradient direction to minimise the loss.

$$\theta = \theta - \eta \nabla J(\theta; x, y)$$

Where  $\theta$  is the weight parameter,  $\eta$  is the learning rate, and  $\nabla J(\theta; x, y)$  is the gradient of weight parameter  $\theta$

### Types of Gradient Descent

Different types of Gradient descents are

- Batch Gradient Descent or Vanilla Gradient Descent
- Stochastic Gradient Descent

- Mini batch Gradient Descent

## Batch Gradient Descent

In the batch gradient, we use the entire dataset to compute the gradient of the cost function for each iteration for gradient descent and then update the weights.

## Stochastic Gradient descent

Stochastic gradient descent, we use a single data point or example to calculate the gradient and update the weights with every iteration.

We first need to shuffle the datasets so that we get a completely randomised dataset. As the datasets are random and weights, are updated for every single example, an update of the weights and the cost functions will be noisy jumping all over the place

## Mini Batch Gradient descent

Mini-batch gradients is a variation of stochastic gradient descent where instead of a single training example, a mini-batch of samples are used.

Mini -batch gradient descent is widely used and converges faster and is more stable.

The batch size can vary depending upon the dataset.


As we take batches with different samples, it reduces the noise which is a variance of the weights updates, and that helps to have a more stable converge faster.

## Q15: What are autoencoders?

An **autoencoder**, neural networks that have three layers:

An input layer, a hidden layer which is also known as encoding layer, and a decoding layer. This network is trained to reconstruct its inputs, which forces the hidden layer to try to learn good representations of the inputs.

An autoencoder neural network is an unsupervised Machine-learning algorithm that applies backpropagation, setting the target values to be equal to the inputs. An autoencoder is trained to attempt to copy its input to its output. Internally, it has a hidden layer which describes a code used to represent the input.



## Autoencoder Components:

Autoencoders consist of 4 main parts:

- 1- Encoder: In this, the model learns how to reduce the input dimensions and compress the input data into an encoded representation.
- 2- Bottleneck: In this, the layer that contains the compressed representation of the input data. This is the lowest possible dimension of the input data.
- 3- Decoder: In this, the model learns how to reconstruct the data from the encoded representation to be as close to the original inputs as possible.
- 4- Reconstruction Loss: In this method that measures how well the decoder is performing and how close the output is related to the original input.

## Types of Autoencoders :

1. Denoising auto encoder
2. Sparse auto encoder
3. Variational auto encoder (VAE)
4. Contractive auto encoder (CAE)

# CNN

## Q16: What is CNN?

This is the simple application of a filter to an input that results in inactivation. Repeated application of the same filter to input results in a map of activations called a feature map, indicating the locations and strength of a detected feature in input, such as an image.

Convolutional layers are the major building blocks which are used in convolutional neural networks.


A covnets is the sequence of layers, and every layer transforms one volume to another through differentiable functions.

Different types of layers in CNN:


Let's take an example by running a covnets on of image of dimensions **32 x 32 x 3**.

1. Input Layer: It holds the raw input of image with width 32, height 32 and depth 3.
2. Convolution Layer: It computes the output volume by computing dot products between all filters and image patches. Suppose we use a total of 12 filters for this layer we'll get output volume of dimension 32 x 32 x 12.
3. Activation Function Layer: This layer will apply the element-wise activation function to the output of the convolution layer. Some activation functions are RELU:  $\max(0, x)$ , Sigmoid:  $1/(1+e^{-x})$ , Tanh, Leaky RELU, etc. So the volume remains unchanged. Hence output volume will have dimensions 32 x 32 x 12.
4. Pool Layer: This layer is periodically inserted within the covnets, and its main function is to reduce the size of volume which makes the

computation fast reduces memory and also prevents overfitting. Two common types of pooling layers are max pooling and average pooling. If we use a max pool with  $2 \times 2$  filters and stride 2, the resultant volume will be of dimension  $16 \times 16 \times 12$ .



5. Fully-Connected Layer: This layer is a regular neural network layer that takes input from the previous layer and computes the class scores and outputs the 1-D array of size equal to the number of classes.




## Q17: What is pooling, padding, filtering operations on CNN?


### Pooling Layer

It is commonly used to periodically insert a Pooling layer in-between successive Conv layers in a ConvNet architecture. Its function is to progressively reduce the spatial size of the representation to reduce the number of parameters and computation in the network, and hence to also

control overfitting. The Pooling Layer operates independently on every depth slice of the input and resizes it spatially, using the MAX operation.




The most common form is a pooling layer with filters of size 2x2 applied with a stride of 2 downsamples every depth slice in the input by two along both width and height, discarding 75% of the activations. Every MAX operation would, in this case, be taking a max over four numbers (little 2x2 region in some depth slice). The depth dimension remains unchanged.



**Q18: What is the Evolution technique of CNN?**

It all started with LeNet in 1998 and eventually, after nearly 15 years, lead to groundbreaking models winning the ImageNet Large Scale Visual Recognition Challenge which includes AlexNet in 2012 to Google Net in 2014 to ResNet in 2015 to an ensemble of previous models in 2016. In the last two years, no significant progress has been made, and the new models are an ensemble of previous groundbreaking models.



## LeNet in 1998

LeNet is a 7-level convolutional network by LeCun in 1998 that classifies digits and used by several banks to recognise the hand-written numbers on cheques digitised in 32x32 pixel greyscale input images.

## AlexNet in 2012

AlexNet: It is considered to be the first paper/ model, which rose the interest in CNNs when it won the ImageNet challenge in the year 2012. It is a deep CNN trained on ImageNet and outperformed all the entries that year.

## VGG in 2014

VGG was submitted in the year 2013, and it became a runner up in the ImageNet contest in 2014. It is widely used as a simple architecture compared to AlexNet.

## GoogleNet in 2014

In 2014, several great models were developed like VGG, but the winner of the ImageNet contest was GoogleNet.

GoogLeNet proposed a module called the inception modules that includes skipping connections in the network, forming a mini-module, and this module is repeated throughout the network.

## ResNet in 2015

There are 152 layers in the Microsoft ResNet. The authors showed empirically that if you keep on adding layers, the error rate should keep on decreasing in contrast to “plain nets” we’re adding a few layers resulted in higher training and test errors.

### **Q19: How to initialise biases in deep learning?**

It is possible and common to initialise the biases to be zero since the random numbers in the weights provide the asymmetry breaking. For ReLU non-linearities, some people like to use small constant value such as 0.01 for all biases because this ensures that all ReLU units fire in the beginning, therefore obtain, and propagate some gradient. However, it is unclear if this provides a consistent improvement (in fact some results seem to indicates that this performs worst) and it is more commonly used to use 0 bias initialisation.

### **Q20: What is learning Rate?**

#### **Learning Rate**

The learning rate controls how much we should adjust the weights concerning the loss gradient. Learning rates are randomly initialised.

Lower the values of the learning rate slower will be the convergence to global minima.

Higher values for the learning rate will not allow the gradient descent to converge

---

Since our goal is to minimise the function cost to find the optimised value for weights, we run multiples iteration with different weights and calculate the cost to arrive at a minimum cost

---

---

**DATA SCIENCE  
INTERVIEW PREPARATION  
(30 Days of Interview  
Preparation)  
# Day-5**

## Q1: What are Epochs?

One Epoch is an ENTIRE dataset is passed forwards and backwards through the neural network

Since one epoch is too large to feed to the computer at once we divide it into several smaller batches

We always use more than one Epoch because ~~one epoch needs to understand the data~~

As the number of epochs increases several times the weight are changed in the neural network and the curve goes from underfitting up to optimal to overfitting curve

## Q2. What is the batch size?

### Batch Size

The total number of training and examples present in a single batch

Unlike the learning rate hyperparameter where its value doesn't affect computational time the batch sizes must be examined in conjunctions with the execution time of training. The batch size is limited by hardware's memory while the learning rate is not. Leslie recommends using a batch size that fits in hardware's memory and enables using larger learning rate.

If our server has multiple GPUs the total batch size is the batch size on a GPU multiplied by the numbers of GPU. If the architectures are small or your hardware permits very large batch sizes then you might compare the performance of different batch sizes. Also recall that small batch sizes add regularization while large batch sizes add less so utilize this while balancing the proper amount of regularization. It is often better to use large batch sizes so a larger learning rate can be used.

## Q3: What is dropout in Neural network?

**Dropout** refers to ignoring units during the training phase of a certain set of neurons which is chosen randomly. These units are not considered during the particular forward or backward pass.

More technically at each training stage individual nodes are either dropped out of the net with probability  $1-p$  or kept with probability  $p$  so that a reduced network is left; incoming and outgoing edges to a dropped-out node are also removed.

---

We need Dropout to prevent overfitting

A dropout is an approach to regularization in neural networks which helps to reduce interdependent learning amongst the neurons

#### Where to use

Dropout is implemented per-layer in a neural network

It can be used with most types of layers such as dense fully connected layers convolutional layers and recurrent layers such as the long short-term memory network layer

Dropout may be implemented on any or all hidden layers in the network as well as the visible or input layer It is not used on the output layer

#### Benefits:-

- 1 Dropout forces a neural network to learn more robust features that are very useful in conjunction with different random subsets of the other neurons
- Dropout generally doubles the number of iterations required to converge However the training time for each epoch is less

### Q4: List down hyperparameter tuning in deep learning.

The process of setting the hyper-parameters requires expertise and extensive trial and error There are no simple and easy ways to set hyper-parameters specifically learning rate batch size momentum and weight decay

Approaches to searching for the best configuration:

- Grid Search
- Random Search

## Approach

- 1 Observe and understand the clues available during training by monitoring validation/test loss early in training tune your architecture and hyper-parameters with short runs of a few epochs
  - Signs of underfitting or overfitting of the test or validation loss early in the training process are useful for tuning the hyper-parameters

## Tools for Optimizing Hyperparameters

- Sage Maker
- Comet ml
- Weights & Biases
- Deep Cognition
- Azure ML

## Q5: What do you understand by activation function and error functions?

### Error functions

In most learning networks an error is calculated as the difference between the predicted output and the actual output

$$J(w) = p - \hat{p}$$

The function that is used to compute this error is known as Loss Function ( ) Different loss functions will give different errors for the same prediction and thus have a considerable effect on the performance of the model One of the most widely used loss function is mean square error which calculates the square of the difference between the actual values and predicted value Different loss functions are used to deals with a different type of tasks i e regression and classification

---

Regressive loss functions:

Mean Square Error

Absolute error

Smooth Absolute Error

**Classification loss functions:**

- Binary Cross-Entropy
- Negative Log-Likelihood
- Margin Classifier
- Soft Margin Classifier

Activation functions decide whether a neuron should be activated or not by calculating a weighted sum and adding bias with it. The purpose of the activation function is to introduce non-linearity into the output of a neuron.

In a neural network we would update the weights and biases of the neurons based on the error at the outputs. This process is known as back-propagation. Activation function makes the back-propagation possible since the gradients are supplied along with the errors to update the weights and biases.

## Q6: Why do we need Non-linear activation functions?

A neural network without activation functions is essentially a linear regression model. The activation functions do the non-linear transformation to the input making it capable of learning and performing more complex tasks.

1 Identity

- Binary Step

- Sigmoid

- Tanh

5 ReLU

- Leaky ReLU

- Softmax

The activation functions do the non-linear transformation to the input making it capable of learning and performing more complex tasks


## Q7: What do you understand by vanishing gradient problem and how can we solve that?

### The problem:

As more layers using certain activation function are added to neural networks the gradients of the loss function approach zero making the networks tougher to train

### Why:

Certain activation functions like the sigmoid function squishes a large input space into a small input space between 0 and 1. Therefore a large change in the input of the sigmoid function will cause a small change in the output. Hence the derivative becomes small.



For shallow networks with only a few layers that use these activations this isn't a big problem. However when more layers are used it can cause the gradient to be too small for training to work effectively.

However when hidden layers use an activation like the sigmoid function small derivatives are multiplied together. Thus the gradient decreases exponentially as we propagate down to the initial layers.

## Solutions:

The simplest solution is to use other activation functions such as ReLU which doesn't cause a small derivative

Residual networks are another solution as they provide residual connections straight to earlier layers

Finally batch normalization layers can also resolve the issue

## Q8: What is Transfer learning in deep learning ?


Transfer learning: It is a machine learning method where a model is developed for the task is again used as the starting point for a model on a second task

It is a popular approach in deep learning where pre-trained models are used as the starting point on computer vision and natural language processing tasks given the vast compute and time resources required to develop neural network models on these problems

Transfer learning is a machine learning technique where a model trained on one task is re-purposed on a second related task


Transfer learning is an optimization that allows rapid progress or improved performance when modelling the second task

Transfer learning only works in deep learning if the model features learned from the first task are general



## Q9: What is VGG16 and explain the architecture of VGG16?

VGG-16 is a simpler architecture model since it's not using many hyperparameters. It always uses  $3 \times 3$  filters with the stride of 1 in convolution layer and uses SAME padding in pooling layers  $3 \times 3$  with a stride of 2.




This architecture is from the VGG group Oxford. It improves AlexNet by replacing the large kernel-sized filter with multiple  $3 \times 3$  kernel-sized filters one after another. With a given receptive field (the effective area size of input image on which output depends) multiple stacked smaller size kernel is better than the one with a larger size kernel because multiple non-linear layers increases the depth of the network which enables it to learn more complex features and that too at a lower cost.

Three fully connected layers follow the VGG convolutional layers. The width of the networks starts at the small value of 64 and increases by a factor of 2 after every sub-sampling pooling layer. It achieves the top-5 accuracy of 92.3% on ImageNet.

## Q10: What is RESNET?

The winner of ILSVRC 2015, it is also called as Residual Neural Network (ResNet) by Kaiming. This architecture introduced a concept called skip connections. Typically the input matrix calculates in two linear transformations with ReLU activation function. In Residual network, it directly copies the input matrix to the second transformation output and sums the output in final ReLU function.



Skip Connection




Figure 2. Residual learning: a building block.

Experiments in paper four can judge the power of the residual network. The plain 34 layer network had high validation error than the 18 layers plain network. This is where we realize the degradation problems. And the same 34 layers network when converted to the residual network has much less training error than the 18 layers residual network.

## Q11: What is ImageNet?

**ImageNet** is a project aimed at (manually) labelling and categorizing images into almost 1000 separate object categories for computer vision researches

When we hear the about *ImageNet* in the context of deep learning and Convolutional Neural Network we are referring to *ImageNet et sorte de concurrence initiale*

The main aim of this image classification challenge is to train the model that can correctly classify an input image into the 1000 separate objects category

Models are trained on the 11 million training images with another 50 000 images for validation and 100 000 images for testing

These 1 000 image categories represent object classes that we encounter in our day-to-day lives such as species of dogs cats various household objects vehicle types and much more

When it comes to the image classification the ImageNet challenge is the de facto benchmark for computer vision classification algorithms and the leaderboard for this challenge has been dominated by Convolutional Neural Networks and Deep learning techniques since 2010



## Q12: What is DarkNet?

DarkNet is a framework used to train neural networks; it is open source and written in C/CUDA and serves as the basis for YOLO. Darknet is also used as the framework for training YOLO meaning it sets the architecture of the network

Clone the repo locally and you have it. To compile it run a make. But first if you intend to use the GPU capability you need to edit the **Makefile** in the first two lines where you tell it to compile for GPU usage with CUDA drivers

## Q13: What is YOLO and explain the architecture of YOLO (you only

Look Once). One use case?

OpenCV

The first YOLO You only look once (YOLO) version came about May 2014 and sets the core of the algorithm the following versions are improvements that fix some drawbacks

In short YOLO is a network inspired by Google Net. It has two convolutional layers working as the feature extractors and two dense layers for making the predictions. The architecture works upon is called Darknet a neural network framework created by the first author of the YOLO paper.


Core Concept:-

The algorithm works off by dividing the image into the grid of the cells for each cell bounding boxes and their scores are predicted alongside class probabilities. The confidence is given in terms of IOU (*Intersection over Union*) metric which is measuring how much the detected object overlaps with the ground truth as a fraction of the total area spanned by the two together (the union).

YOLO v1-

This improves on some of the shortcomings of the first version namely the fact that it is not very good at detecting objects that are very near and tends to make some of the mistakes on localization.

It introduces a few newer things: Which are *anchor boxes* (pre-determined sets of boxes such that the network moves from predicting the bounding boxes to predicting the offsets from these) and the use of features that are more fine-grained so smaller objects can be predicted better.



YOLO v1-

YOLOv2 came about April 2018 and it adds small improvements including the fact that bounding boxes get predicted at the different scales. The underlying meaty part of the YOLO network Darknet is expanded in this version to have 52 convolutional layers.




**DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview  
Preparation)**

**# DAY 06**

**NLP**

## Q1. What is NLP?

Natural language processing NLP It is the branch of artificial intelligence that helps computers understand interpret and manipulate human language NLP draws from many disciplines including computer science and computational linguistics in its pursuit to fill the gap between human communication and computer understanding



## Q2. What are the Libraries we used for NLP?

We usually use these libraries in NLP which are

NLTK Natural language Tool kit TextBlob CoreNLP Polyglot

Gensim SpaCy Scikit-learn

And the new one is Megatron library launched recently

## Q3. What do you understand by tokenisation?

Tokenisation is the act of breaking a sequence of strings into pieces such as words keywords phrases symbols and other elements called tokens Tokens can be individual words phrases or even whole sentences In the process of tokenisation some characters like punctuation marks are discarded

**Natural Language Processing**  
['Natural', 'Language', 'Processing']


#### Q4. What do you understand by stemming?

Stemming It is the process of reducing inflexions in words to their root forms such as mapping a group of words to the same stem even if stem itself is not a valid word in the Language

	words	stemmed words
0	connect	connect
1	connected	connect
2	connection	connect
3	connections	connect
4	connects	connect

#### Q5. What is lemmatisation?

Lemmatisation It is the process of the group together the different inflected forms of the word so that they can be analysed as a single item It is quite similar to stemming but it brings context to the words So it links words with similar kind meaning to one word



#### Q6. What is Bag-of-words model?

We need the way to represent text data for the machine learning algorithms and the bag-of-words model helps us to achieve the task This model is very understandable and to implement It is the way of extracting features from the text for the use in machine learning algorithms

In this approach we use the tokenised words for each of observation and find out the frequency of each token

Let's do an example to understand this concept in depth

It is going to rain today

Today I am not going outside

---

I am going to watch the season premiere

We treat each sentence as the separate document and we make the list of all words from all the three documents excluding the punctuation. We get

It is going to rain today I am not outside watch the season premiere

The next step is to create vectors. Vectors convert text that can be used by the machine learning algorithm.

We take the first document “It is going to rain today”, and we check the frequency of words from the ten unique words

It =

is =

going =

to =

rain =

today =

I = 0

am = 0

not = 0

outside = 0

Rest of the documents will be

“It is going to rain today” = [1, 1, 1, 1, 1, 1, 0, 0, 0, 0]

“Today I am not going outside” = [0, 0, 1, 0, 0, 1, 1, 1, 1, 1]

“I am going to watch the season premiere” = [0, 0, 0, 0, 0, 0, 0, 0, 0, 0]

In this approach, each word (a token) is called a “gram”. Creating the vocabulary token-word pairs is called a bag-of-words model.

The process of converting the NLP text into numbers is called **vectorisation** in ML. There are different ways to convert text into the vectors

- Counting the number of times that each word appears in the document.
- Calculating the frequency that each word appears in a document out of all the words in the document.

## Q7.What do you understand by TF-IDF?

TF-IDF It stands for the term of frequency-inverse document frequency

TF-IDF weight It is a statistical measure used to evaluate how important a word is to a document in a collection or corpus The importance increases proportionally to the number of times a word appears in the document but is offset by the frequency of the word in the corpus

- **Term Frequency (TF)** is a scoring of the frequency of the word in the current document Since every document is different in length it is possible that a term would appear much more times in long documents than shorter ones The term frequency is often divided by the document length to normalise

$$TF(t) = \frac{\text{Number of times term } t \text{ appears in a document}}{\text{Total number of terms in the document}}$$

- **Inverse Document Frequency (IDF)** It is a scoring of how rare the word is across the documents It is a measure of how rare a term is Rarer the term and more is the IDF score

$$IDF(t) = \log_e\left(\frac{\text{Total number of documents}}{\text{Number of documents with term } t \text{ in it}}\right)$$

Thus

$$TF - IDF \text{ score} = TF * IDF$$

## Q8. What is Word2vec?

Word2Vec is a shallow two-layer neural network which is trained to reconstruct linguistic contexts of words It takes as its input a large corpus of words and produces a vector space typically of several of hundred dimensions with each of unique word in the corpus being assigned to the corresponding vector in space

Word vectors are positioned in a vector space such that words which share common contexts in the corpus are located close to one another in the space

Word2Vec is a particularly computationally-efficient predictive model for learning word embeddings from raw text

Word2Vec is a group of models which helps derive relations between a word and its contextual words Let's look at two important models inside Word2Vec Skip-grams and CBOW

## Skip-grams

Source Text	Training Samples
The <span style="background-color: #ADD8E6; border: 1px solid black; padding: 2px;">quick</span> brown fox jumps over the lazy dog. ➔	(the, quick) (the, brown)
The quick <span style="background-color: #ADD8E6; border: 1px solid black; padding: 2px;">brown</span> fox jumps over the lazy dog. ➔	(quick, the) (quick, brown) (quick, fox)
The quick <span style="background-color: #ADD8E6; border: 1px solid black; padding: 2px;">brown</span> fox <span style="background-color: #ADD8E6; border: 1px solid black; padding: 2px;">jumps</span> over the lazy dog. ➔	(brown, the) (brown, quick) (brown, fox) (brown, jumps)
The quick <span style="background-color: #ADD8E6; border: 1px solid black; padding: 2px;">brown</span> fox <span style="background-color: #ADD8E6; border: 1px solid black; padding: 2px;">jumps</span> <span style="background-color: #ADD8E6; border: 1px solid black; padding: 2px;">over</span> the lazy dog. ➔	(fox, quick) (fox, brown) (fox, jumps) (fox, over)

In Skip-gram model we take a centre word and a window of context neighbour words and we try to predict the context of words out to some window size for each centre word. So our model is going to define a probability distribution i.e. probability of a word appearing in the context given a centre word and we are going to choose our vector representations to maximise the probability.

## Continuous Bag-of-Words (CBOW)

CBOW predicts target words e.g. mat from the surrounding context words the cat sits on the

Statistically it affects that CBOW smoothes over a lot of distributional information by treating an entire context as one observation. For the most part this turns out to be a useful thing for smaller datasets.

1. I enjoy flying.
2. I like NLP.
3. I like deep learning.

The resulting counts matrix will then be:

$$X = \begin{matrix} & \begin{matrix} I & like & enjoy & deep & learning & NLP & flying & . \end{matrix} \\ \begin{matrix} I \\ like \\ enjoy \\ deep \\ learning \\ NLP \\ flying \\ . \end{matrix} & \left[ \begin{matrix} 0 & 2 & 1 & 0 & 0 & 0 & 0 & 0 \\ 2 & 0 & 0 & 1 & 0 & 1 & 0 & 0 \\ 1 & 0 & 0 & 0 & 0 & 0 & 1 & 0 \\ 0 & 1 & 0 & 0 & 1 & 0 & 0 & 0 \\ 0 & 0 & 0 & 1 & 0 & 0 & 0 & 1 \\ 0 & 1 & 0 & 0 & 0 & 0 & 0 & 1 \\ 0 & 0 & 1 & 0 & 0 & 0 & 0 & 1 \\ 0 & 0 & 0 & 0 & 1 & 1 & 1 & 0 \end{matrix} \right] \end{matrix}$$

---

This was about converting words into vectors. But where does the learning happen? Essentially we begin with small random initialisation of word vectors. Our predictive model learns the vectors by minimising the loss function. In Word2vec this happens with feed-forward neural networks and optimisation techniques such as Stochastic gradient descent. There are also count-based models which make the co-occurrence count matrix of the words in our corpus; we have a very large matrix with each row for the words and columns for the context. The number of contexts is of course very large since it is very essentially combinatorial in size. To overcome this issue we apply SVD to a matrix. This reduces the dimensions of the matrix to retain maximum pieces of information.

## Q9. What is Doc2vec?

Paragraph Vector more popularly known as *Doc2vec*      Distributed Memory *DM*

Paragraph Vector Doc2Vec is supposed to be an extension to Word2Vec such that *Word2vec learns to project words into a latent d-dimensional space* whereas *Doc2vec aims at learning how to project a document into a latent d-dimensional space*


The basic idea behind PV-DM is inspired by Word2Vec. In CBOW model of Word2Vec the model learns to predict a centre word based on the contexts. For example- given a sentence "The cat sat on the table" CBOW model would learn to predict the words "sat" given the context words "the cat" and "on". Similarly in PV-DM the main idea is randomly sample consecutive words from the paragraph and ***predict a centre word*** from the randomly sampled set of words by taking as the ***input the context words and the paragraph id***.

Let's have a look at the model diagram for some more clarity. In this given model we see Paragraph matrix, Average/Concatenate and classifier sections.

**Paragraph matrix** It is the matrix where each column represents the vector of a paragraph.

**Average/Concatenate** It means that whether the word vectors and paragraph vector are averaged or concatenated.

**Classifier** In this it takes the hidden layer vector (the one that was concatenated/averaged) as input and predicts the Centre word.



In the matrix D It has the embeddings for seen paragraphs i e arbitrary length documents the same way Word2Vec models learns embeddings for words For unseen paragraphs the model is again run through gradient descent 5 or so iterations to infer a document vector

## Q9. What is Time-Series forecasting?

Time series forecasting is a technique for the prediction of events through a sequence of time. The technique is used across many fields of study from the geology to behaviour to economics. The techniques predict future events by analysing the trends of the past on the assumption that future trends will hold similar to historical trends.

## Q10. What is the difference between in Time series and regression?

### Time-series


- 1 Whenever data is recorded at regular intervals of time
- 2 Time-series forecast is Extrapolation
- 3 Time-series refers to an ordered series of data

### Regression

- Whereas in regression whether data is recorded at regular or irregular intervals of time we can apply
- 2 Regression is Interpolation
- 3 Regression refer both ordered and unordered series of data


## Q11. What is the difference between stationary and non-stationary data?

**Stationary:** A series is said to be "STRICTLY STATIONARY" if the Mean Variance & Covariance is constant over some time or time-invariant



### Non-Stationary:

A series is said to be "STRICTLY STATIONARY" if the Mean Variance & Covariance is not constant over some time or time-invariant



---

## Q12. Why you cannot take non-stationary data to solve time series Problem?

- Most models assume stationary of data In other words standard techniques are invalid if data is "NON-STATIONARY"
  - Autocorrelation may result due to "NON-STATIONARY"
  - Non-stationary processes are a random walk with or without a drift a slow steady change
  - Deterministic trends trends that are constant positive or negative independent of time for the whole life of the series
-

**DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview  
Preparation)**

**# DAY 07**

## Q1. What is the process to make data stationary from non-stationary in time series?

**Ans:**

The two most common ways to make a non-stationary time series stationary are:

- Differencing
- Transforming

Let us look at some details for each of them:

### Differencing:


To make your series stationary, you take a difference between the data points So let us say, your original time series was:

$X_1, X_2, X_3, \dots, X_n$

Your series with a difference of degree 1 becomes:


$(X_2 - X_1, X_3 - X_2, X_4 - X_3, \dots, X_n - X_{n-1})$

Once, you make the difference, plot the series and see if there is any improvement in the ACF curve If not, you can try a second or even a third-order differencing Remember, the more you difference, the more complicated your analysis is becoming



### Transforming:


If we cannot make a time series stationary, you can try out transforming the variables Log transform is probably the most commonly used transformation if we see the diverging time series However, it is suggested that you use transformation only in case differencing is not working



### Q2. What is the process to check stationary data ?

#### Ans:

**Stationary series:** It is one in which the properties mean, variance and covariance, do not vary with time




Let us get an idea with these three plots:

- In the first plot, we can see that the mean varies (increases) with time, which results in an upward trend This is the non-stationary series  
For the series classification as stationary, it should not exhibit the trend
- Moving on to the second plot, we do not see a trend in the series, but the variance of the series is a function of time As mentioned previously, a stationary series must have a constant variance

- If we look at the third plot, the spread becomes closer, as the time increases, which implies that covariance is a function of time

These three plots refer to the non-stationary time series Now give your attention to fourth:



In this case, Mean, Variance and Covariance are constant with time This is how a stationary time series looks like

Most of the statistical models require the series to be stationary to make an effective and precise prediction

The various process you can use to find out your data is stationary or not by the following terms:

- 1 Visual Test
- 2 Statistical Test
- 3 ADF(Augmented Dickey-Fuller) Test
- 4 KPSS(Kwiatkowski-Phillips-Schmidt-Shin) Test


### Q3. What are ACF and PACF?.

**Ans:**

ACF is a (complete) auto-correlation function which gives us the values of the auto-correlation of any series with lagged values We plot these values along with a confidence band We have an ACF plot In simple terms, it describes how well the present value of the series is related to its past values A time series can have components like the trend, seasonality, cyclic and residual ACF considers all the components while finding correlations hence, it's a complete auto-correlation plot

PACF is a partial autocorrelation function Instead of finding correlations of present with lags like ACF, it finds the correlations of the residuals with the next lag value thus partial and not complete as we remove already found variations before we find next correlation So if there are any hidden pieces of information in the residual which can be modelled by next lag, we might get a good correlation, and we'll keep that next lag as a feature while modelling Remember, while

modelling we don't want to keep too many correlated features, as that it can create multicollinearity issues. Hence we need to retain only relevant features.




#### Q4. What do you understand by the trend of data?


**Ans:**

A general systematic linear or (most often) nonlinear component that changes over time and does not repeat

There are different approaches to understanding trend. A positive trend means it is likely that growth continues. Let's illustrate this with a simple example:



Hmm, this looks like there is a trend. To build up confidence, let's add a linear regression for this graph:



Great, now it's clear there's a trend in the graph by adding Linear Regression

## Q5. What is the Augmented Dickey-Fuller Test?


**Ans:**

**The Dickey-Fuller test:** It is one of the most popular statistical tests. It is used to determine the presence of unit root in a series, and hence help us to understand if the series is stationary or not. The null and alternate hypothesis for this test is:

**Null Hypothesis:** The series has a unit root (value of  $\alpha = 1$ )

**Alternate Hypothesis:** The series has no unit root

If we fail to reject the null hypothesis, we can say that the series is non-stationary. This means that the series can be linear or difference stationary.



## Q6. What is AIC and BIC into time series?

**Ans:**

**Akaike's information criterion (AIC)** compares the quality of a set of statistical models to each other. For example, you might be interested in what variables contribute to low socioeconomic status and how the variables contribute to that status. Let's say you create several regression models for various factors like education, family size, or disability status. The AIC will take each model and rank them from best to worst. The best model will be the one that neither under-fits nor over-fits.

- AIC
- K = number of estimated parameters in the model
- L = Maximized likelihood function for the estimated model

$$AIC = 2k - 2 \ln(L)$$

The Bayesian Information Criterion (BIC) can be defined as:

$$k \log(n) - 2 \log(L(\hat{\theta}))$$

Here n is the sample size

K is the number of parameters which your model estimates

is the set of all parameter

L ( ) represents the likelihood of the model tested, when evaluated at maximum values of

## Q7. What are the components of the Time -Series?

**Ans:**

**Time series analysis:** It provides a body of techniques to understand a dataset better. The most useful one is the decomposition of the time series into four constituent parts-

- 1 Level- The baseline value for the series if it were a straight line
- 2 Trend - The optional and linear, increasing or decreasing behaviour of series over time
- 3 Seasonality - Optional repeated patterns /cycles of behaviour over time
- 4 Noise - The optional variability in the observations that cannot be explained by the model

## Q8. What is Time Series Analysis?

**Ans:**

**Time series analysis:** It involves developing models that best capture or describe an observed time series to understand the underlying cause. This study seeks the why behind the time-series datasets. This involves making assumptions about the form of data and decomposing time-series into the constitution component

- Quality of descriptive model is determined by how well it describes all available data and the interpretation it provides to inform the problem domain better

---

## Q9. Give some examples of the Time-Series forecast?

**Ans:**

There is almost an endless supply of the time series forecasting problems Below are ten examples from a range of industries to make the notions of time series analysis and forecasting more concrete

- 1 Forecasting the corn yield in tons by the state each year
- 2 Forecasting whether an EEG trace in seconds indicates a patient is having a seizure or not
- 3 Forecasting the closing price of stocks every day
- 4 Forecasting the birth rates at all hospitals in the city every year
- 5 Forecasting product sales in the units sold each day for the store
- 6 Forecasting the number of passengers through the train station each day
- 7 Forecasting unemployment for a state each quarter
- 8 Forecasting the utilisation demand on the server every hour
- 9 Forecasting the size of the rabbit populations in the state each breeding season
- 10 Forecasting the average price of gasoline in a city each day

## Q10. What are the techniques of Forecasting?

**Ans:**

There are so many statistical techniques available for time series forecast however we have found a few effective ones which are listed below:

- Simple Moving Average (SMA)
- Exponential Smoothing (SES)
- Autoregressive Integration Moving Average (ARIMA)

## Q11. What is the Moving Average?

**Ans:**

The moving average model is probably the most naive approach to time series modelling This model states that the next observation is the mean of all past observations

Although simple, this model might be surprisingly good, and it represents a good starting point

Otherwise, the moving average can be used to identify interesting trends in the data We can define a window to apply the moving average model to smooth the time series and highlight different trends



#### Example of a moving average on a 24h window

In the plot above, we applied the moving average model to a 24h window. The green line smoothed the time series, and we can see that there are two peaks in the 24h period.

The longer the window, the smoother the trend will be

Below is an example of moving average on a smaller window



#### Example of a moving average on a 12h window

## Q12. What is Exponential smoothing?


**Ans:**

Exponential smoothing uses similar logic to moving average, but this time, different decreasing weight is assigned to each observation. We can also say, less importance is given to the observations as we move further from the present.

Mathematically, exponential smoothing is expressed as:

$$y = \alpha x_t + (1 - \alpha)y_{t-1}, t > 0$$

Here, alpha is the smoothing factor which takes values between 0 to 1. It determines how fast the weight will decrease for the previous observations.



From the above plot, the dark blue line represents the exponential smoothing of the time series using a smoothing factor of 0.3, and the orange line uses a smoothing factor of 0.05. As we can see, the smaller the smoothing factor, the smoother the time series will be. Because as smoothing factor approaches 0, we approach to the moving average model.

**DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview  
Preparation)**

**# DAY 08**

## Q1. What is Tensorflow?

**Ans:**

TensorFlow is an open-source software library released in 2015 by Google to make it easier for the developers to design, build, and train deep learning models. TensorFlow originated as an internal library that the Google developers used to build the models in house, and we expect additional functionality to be added in the open-source version as they are tested and vetted in internal flavour. Although TensorFlow is the only one of several options available to the developers and we choose to use it here because of thoughtful design and ease of use.

At a high level, TensorFlow is a Python library that allows users to express arbitrary computation as a graph of *data flows*. Nodes in this graph represent mathematical operations, whereas edges represent data that is communicated from one node to another. Data in TensorFlow are represented as tensors, which are multidimensional arrays. Although this framework for thinking about computation is valuable in many different fields, TensorFlow is primarily used for deep learning in practice and research.




## Q2. What are Tensors?

**Ans:**

In mathematics, it is an algebraic object that describes the linear mapping from one set of algebraic objects to the another. Objects that the tensors may map between include, but are not limited to the vectors, scalars and recursively, even other tensors (for example, a matrix is the map between vectors and thus a tensor. Therefore the linear map between matrices is also the tensor). Tensors are inherently related to the vector spaces and their dual spaces and can take several different forms. For


example, a scalar, a vector, a dual vector at a point, or a multi-linear map between vector spaces. Euclidean vectors and scalars are simple tensors. While tensors are defined as independent of any basis. The literature on physics, often referred by their components on a basis related to a particular coordinate system.



### Q3. What is TensorBoard?

**Ans:**

TensorBoard is a suite of visualising tools, is an easy solution to Tensorflow offered by the creators that lets you visualise the graphs, plot quantitative metrics about the graph with additional data like images to pass through it.



This one is some example of how the TensorBoard is working.

---

#### Q4. What are the features of TensorFlow?

**Ans:**

- One of the main features of TensorFlow is its ability to build neural networks.
- By using these neural networks, machines can perform logical thinking and learn similar to humans.
- There are other tensors for processing, such as data loading, preprocessing, calculation, state and outputs.
- It is considered not only as deep learning but also as the library for performing tensor calculations, and it is the most excellent library when considered as the deep learning framework that can also describe basic calculation processing.
- TensorFlow describes all calculation processes by calculation graph, no matter how simple the calculation is.

#### Q5. What are the advantages of TensorFlow?

**Ans:**

- It allows Deep Learning.
- It is open-source and free.
- It is reliable (and without major bugs)
- It is backed by Google and a good community.
- It is a skill recognised by many employers.
- It is easy to implement.

#### Q6. List a few limitations of Tensorflow.

**Ans:**

- Has GPU memory conflicts with Theano if imported in the same scope.
- It has dependencies with other libraries.
- Requires prior knowledge of advanced calculus and linear algebra along with a pretty good understanding of machine learning.

## Q7. What are the use cases of Tensor flow?

**Ans:**

Tensorflow is an important tool of deep learning, it has mainly five use cases, and they are:


- Time Series
- Image recognition
- Sound Recognition
- Video detection
- Text-based Applications

## Q8. What are the very important steps of Tensorflow architecture?

**Ans:**

There are three main steps in the Tensorflow architecture are:

- Pre-process the Data
- Build a Model
- Train and estimate the model




*Image Recognition  
Classification using Softmax Regressions and Convolutional Neural Networks*

## Q9. What is Keras?

**Ans:**


- **eras:** It is an Open Source Neural Network library written in Python that runs on the top of Theano or Tensorflow. It is designed to be the modular, fast and easy to use. It was developed by François Chollet, a Google engineer.



## Q10. What is a pooling layer?

**Ans:**

- **ooling layer:** It is generally used in reducing the spatial dimensions and not depth, on a convolutional neural network model.



## Q11. What is the difference between CNN and RNN?

**Ans:**

C□□□Convolutional□eural□et□or□□

- Best suited for spatial data like images
- CNN is powerful compared to RNN
- This network takes a fixed type of inputs and outputs
- These are the ideal for video and image processing

---

R□□□Recurrent□eural□et□or□□

- Best suited for sequential data
- RNN supports less feature set than CNN.
- This network can manage the arbitrary input and output lengths.
- It is ideal for text and speech analysis.

## Q12. What are the benefits of Tensorflow over other libraries?

**Ans:**

The following benefits are:

- Scalability
  - Visualisation of Data
  - Debugging facility
  - Pipelining
-

**DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview  
Preparation)**


**# DAY 09**

## Q1: How would you define Machine Learning?

**Ans:**

**Machine learning:** It is an application of artificial intelligence (AI) that provides systems the ability to learn automatically and to improve from experiences without being programmed. It focuses on the development of computer applications that can access the data and use it to learn for themselves.


The process of learning starts with the observations or data such as examples, direct experience or instruction to look for the patterns in data and to make better decisions in the future based on examples that we provide. The primary aim is to allow the computers to learn automatically without human intervention or assistance and adjust actions accordingly.



## Q2. What is a labeled training set?

**Ans:**

**Machine learning** is derived from the availability of the labeled data in the form of a **training set** and **test set** that is used by the learning algorithm. The separation of data into the training portion and a test portion is the way the algorithm learns. We split up the data containing known response variable values into two pieces. The training set is used to train the algorithm and then you use the trained model on the test set to predict the variable response values that are already known. The final step is to compare with the predicted responses against actual (observed) responses to see how close they are. The difference is the test error metric. Depending on the test error, you can go back to refine the model and repeat the process until you're satisfied with the accuracy.




### Q3. What are the two common supervised tasks?

**Ans:**

The two common supervised tasks are regression and classification


#### **Regression-**

The regression problem is when the output variable is the real or continuous value such as salary or weight. Many different models can be used and the simplest is linear regression. It tries to fit the data with the best hyper-plane which goes through the points.



#### **Classification**

It is the type of supervised learning. It specifies the class to which the data elements belong to and is best used when the output has finite and discrete values. It predicts a class for an input variable as well.




### Q4. Can you name four common unsupervised tasks?

**Ans:**

The common unsupervised tasks include clustering, visualization, dimensionality reduction, and association rule learning.


#### **Clustering**

It is a Machine Learning technique that involves the grouping of the data points. Given a set of data points and we can use a clustering algorithm to classify each data point into the specific group. In theory, data points that lie in the same group should have similar properties and/or features and data points in the different groups should have high dissimilar properties and/or features. Clustering is the method of unsupervised learning and is a common technique for statistical data analysis used in many fields.



## Visualization

**Data visualization** is the technique that uses an array of static and interactive visuals within the specific context to help people to understand and make sense of the large amounts of data. The data is often displayed in the story format that visualizes patterns, trends, and correlations that may go otherwise unnoticed. It is regularly used as an avenue to monetize data as the product. An example of using monetization and data visualization is Uber. The app combines visualization with real-time data so that customers can request a ride.



## Q5. What type of Machine Learning algorithm we use to allow a robot to walk in various unknown terrains?


**Ans:**

Reinforcement Learning is likely to perform the best if we want a robot to learn how to walk in the various unknown terrains since this is typically the type of problem that the reinforcement learning

tackles It may be possible to express the problem as a supervised or semisupervised learning problem but it would be less natural

### **Reinforcement Learning-**

It's about to take suitable actions to maximize rewards in a particular situation. It is employed by the various software and machines to find out the best possible behavior/path it should take in specific situations. Reinforcement learning is different from the supervised learning in a way that in supervised learning training data has answer key with it so that the model is trained with the correct answer itself but in reinforcement learning there is no answer and the reinforcement agent decides what to do to perform the given task. In the absence of the training dataset it is bound to learn from its experience.



### **Q6. What type of algorithm would we use to segment your customers into multiple groups?**

**Ans:**


If we don't know how to define the groups then we can use the clustering algorithm (unsupervised learning) to segment our customers into clusters of similar customers. However if we know what groups we would like to have then we can feed many examples of each group to a classification algorithm (supervised learning) and it will classify all your customers into these groups.

### **Q7: What is an online machine learning?**

**Ans:**

**Online machine learning:** It is a method of machine learning in which data becomes available in sequential order and to update our best predictor for the future data at each step as opposed to batch learning techniques that generate the best predictor by learning on entire training data set at once. Online learning is a common technique and used in the areas of machine learning where it is computationally infeasible to train over the datasets requiring the need for Out-of-core algorithms. It is also used in situations where the algorithm must adapt to new patterns in the data dynamically or when the data itself is generated as the function of time for example stock

price prediction Online learning algorithms might be prone to catastrophic interference and problem that can be addressed by the incremental learning approaches




## Q8: What is out-of-core learning?

**Ans:**

**Out-of-core:** It refers to the processing data that is too large to fit into the computer's main memory. Typically when the dataset fits neatly into the computer's main memory randomly accessing sections of data has a (relatively) small performance penalty.

When data must be stored in a medium like a large spinning hard drive or an external computer network it becomes very expensive to seek an arbitrary section of data randomly or to process the same data multiple times. In such a case an out-of-core algorithm will try to access all the relevant data in a sequence.

However modern computers have deep memory hierarchy and replacing random access with the sequential access can increase the performance even on datasets that fit within memory.



## Q9. What is the Model Parameter?

**Ans:**

**Model parameter:** It is a configuration variable that is internal to a model and whose value can be predicted from the data

- While making predictions the model parameter is needed
- The values define the skill of a model on problems
- It is estimated or learned from data
- It is often not set manually by the practitioner
- It is often saved as part of the learned model

Parameters are key to machine learning algorithms. They are part of the model that is learned from historical training data.


## Q11: What is Model Hyperparameter?

**Ans:**

**Model hyperparameter:** It is a configuration that is external to a model and whose values cannot be estimated from the data.

- It is often used in processes to help estimate model parameters
- The practitioner often specifies them
- It can often be set using heuristics
- It is tuned for the given predictive modeling problems

We cannot know the best value for the model hyperparameter on the given problem. We may use the rules of thumb, copy values used on other problems, or search for the best value by trial and error.



## Q12. What is cross-validation?


**Ans:**

**Cross-validation:** It is a technique for evaluating Machine Learning models by training several Machine Learning models on subsets of available input data and evaluating them on the complementary subset of data. Use cross-validation to detect overfitting i.e. failing to generalize a pattern.

There are three steps involved in cross-validation are as follows :

- Reserve some portion of the sample dataset

- Using the rest dataset and train models
- Test the model using a reserve portion of the data-set




# **DATA SCIENCE INTERVIEW PREPARATION (30 Days of Interview Preparation)**

## **# DAY 10**

## Q1. What is a Recommender System?

### Answer:

A recommender system is today widely deployed in multiple fields like movie recommendations music preferences social tags research articles search queries and so on. The recommender systems work as per collaborative and content-based filtering or by deploying a personality-based approach. This type of system works based on a person's past behavior in order to build a model for the future. This will predict the future product buying movie viewing or book reading by people. It also creates a filtering approach using the discrete characteristics of items while recommending additional items.




## Q2. Compare SAS, R and Python programming?

### Answer:

**SAS:** it is one of the most widely used analytics tools used by some of the biggest companies on earth. It has some of the best statistical functions graphical user interface but can come with a price tag and hence it cannot be readily adopted by smaller enterprises.

**R:** The best part about R is that it is an Open Source tool and hence used generously by academia and the research community. It is a robust tool for statistical computation, graphical representation and reporting. Due to its open source nature it is always being updated with the latest features and then readily available to everybody.

**Python:** Python is a powerful open source programming language that is easy to learn, works well with most other tools and technologies. The best part about Python is that it has innumerable libraries and community created modules making it very robust. It has functions for statistical operation, model building and more.



### Q3. Why is important in data analysis?

#### Answer:

With data coming in from multiple sources it is important to ensure that data is good enough for analysis. This is where data cleansing becomes extremely vital. Data cleansing extensively deals with the process of detecting and correcting of data records ensuring that data is complete and accurate and the components of data that are irrelevant are deleted or modified as per the needs. This process can be deployed in concurrence with data wrangling or batch processing.

Once the data is cleaned it confirms with the rules of the data sets in the system. Data cleansing is an essential part of the data science because the data can be prone to error due to human negligence or corruption during transmission or storage among other things. Data cleansing takes a huge chunk of time and effort of a Data Scientist because of the multiple sources from which data emanates and the speed at which it comes.



#### **Q4. What are the various aspects of a Machine Learning process?**

##### **Answer:**

Here we will discuss the components involved in solving a problem using machine learning.

##### **Domain knowledge**

This is the first step wherein we need to understand how to extract the various features from the data and learn more about the data that we are dealing with. It has got more to do with the type of domain that we are dealing with and familiarizing the system to learn more about it.

## Feature Selection

This step has got more to do with the feature that we are selecting from the set of features that we have. Sometimes it happens that there are a lot of features and we have to make an intelligent decision regarding the type of feature that we want to select to go ahead with our machine learning endeavor.

## Algorithm

This is a vital step since the algorithms that we choose will have a very major impact on the entire process of machine learning. You can choose between the linear and nonlinear algorithm. Some of the algorithms used are Support Vector Machines, Decision Trees, Naïve Bayes, K-Means Clustering, etc.

## Training

This is the most important part of the machine learning technique and this is where it differs from the traditional programming. The training is done based on the data that we have and providing more real world experiences. With each consequent training step the machine gets better and smarter and able to take improved decisions.

## Evaluation

In this step we actually evaluate the decisions taken by the machine in order to decide whether it is up to the mark or not. There are various metrics that are involved in this process and we have to closed deploy each of these to decide on the efficacy of the whole machine learning endeavor.


## Optimization

This process involves improving the performance of the machine learning process using various optimization techniques. Optimization of machine learning is one of the most vital components wherein the performance of the algorithm is vastly improved. The best part of optimization techniques is that machine learning is not just a consumer of optimization techniques but it also provides new ideas for optimization too.

## Testing

Here various tests are carried out and some these are unseen set of test cases. The data is partitioned into test and training set. There are various testing techniques like cross-validation in order to deal with multiple situations.

## The Machine Learning Process




## Q4. What is Interpolation and Extrapolation?

**Answer:**

The terms of interpolation and extrapolation are extremely important in any statistical analysis. Extrapolation is the determination or estimation using a known set of values or facts by extending it and taking it to an area or region that is unknown. It is the technique of inferring something using data that is available.

Interpolation on the other hand is the method of determining a certain value which falls between a certain set of values or the sequence of values. This is especially useful when you have data at the two extremities of a certain region but you don't have enough data points at the specific point. This is when you deploy interpolation to determine the value that you need.




## Q5. What does P-value signify about the statistical data?

Answer:

P-value is used to determine the significance of results after a hypothesis test in statistics. P-value helps the readers to draw conclusions and is always between 0 and 1.

- P-Value > 0.05 denotes weak evidence against the null hypothesis which means the null hypothesis cannot be rejected.
- P-value <= 0.05 denotes strong evidence against the null hypothesis which means the null hypothesis can be rejected.
- P-value = 0.05 is the marginal value indicating it is possible to go either way.



## Q6. During analysis, how do you treat missing values?

Answer:

The extent of the missing values is identified after identifying the variables with missing values. If any patterns are identified the analyst has to concentrate on them as it could lead to interesting and meaningful business insights. If there are no patterns identified then the missing values can be substituted with mean or median values (imputation) or they can simply be ignored.

There are various factors to be considered when answering this question-

Understand the problem statement understand the data and then give the answer Assigning a default value which can be mean minimum or maximum value Getting into the data is important

If it is a categorical variable the default value is assigned The missing value is assigned a default value

If you have a distribution of data coming for normal distribution give the mean value

Should we even treat missing values is another important point to consider? If 80% of the values for a variable are missing then you can answer that you would be dropping the variable instead of treating the missing values

## **Q7. Explain the difference between a Test Set and a Validation Set?**

### **Answer:**


Validation set can be considered as a part of the training set as it is used for parameter selection and to avoid Overfitting of the model being built On the other hand test set is used for testing or evaluating the performance of a trained machine learning model

In simple terms the differences can be summarized as-

Training Set is to fit the parameters i e weights

Test Set is to assess the performance of the model i e evaluating the predictive power and generalization

Validation set is to tune the parameters




## Q8. What is the curse of dimensionality? Can you list some ways to deal with it?

### Answer:

The curse of dimensionality is when the training data has a high feature count but the dataset does not have enough samples for a model to learn correctly from so many features. For example a training dataset of 100 samples with 100 features will be very hard to learn from because the model will find random relations between the features and the target. However if we had a dataset of 100k samples with 100 features the model could probably learn the correct relationships between the features and the target.

There are different options to fight the curse of dimensionality:

- **Feature selection.** Instead of using all the features we can train on a smaller subset of features
- **Dimensionality reduction.** There are many techniques that allow to reduce the dimensionality of the features. Principal component analysis (PCA) and using autoencoders are examples of dimensionality reduction techniques
- **L1 regularization.** Because it produces sparse parameters L1 helps to deal with high-dimensionality input
- **Feature engineering.** It's possible to create new features that sum up multiple existing features. For example we can get statistics such as the mean or median



## Q9. What is data augmentation? Can you give some examples?


### Answer:

Data augmentation is a technique for synthesizing new data by modifying existing data in such a way that the target is not changed or it is changed in a known way

Computer vision is one of fields where data augmentation is very useful. There are many modifications that we can do to images:

- Resize
- Horizontal or vertical flip
- Rotate
- Add noise
- Deform
- Modify colors

Each problem needs a customized data augmentation pipeline. For example on OCR doing flips will change the text and won't be beneficial; however resizes and small rotations may help.



## Q10. What is stratified cross-validation and when should we use it?

### Answer:

Cross-validation is a technique for dividing data between training and validation sets. On typical cross-validation this split is done randomly. But in *stratified* cross-validation the split preserves the ratio of the categories on both the training and validation datasets.

For example if we have a dataset with 10% of category A and 90% of category B and we use stratified cross-validation we will have the same proportions in training and validation. In contrast if we use simple cross-validation in the worst case we may find that there are no samples of category A in the validation set.

Stratified cross-validation may be applied in the following scenarios:

- **n a dataset with multiple categories.** The smaller the dataset and the more imbalanced the categories the more important it will be to use stratified cross-validation
- **n a dataset with data of different distributions.** For example in a dataset for autonomous driving we may have images taken during the day and at night. If we do not ensure that both types are present in training and validation we will have generalization problems



**DATA SCIENCE  
INTERVIEW PREPARATION  
(30 Days of Interview  
Preparation)**


**# DAY 11**

## Q1. What are tensors?

### Answer:

The tensors are no more than a method of presenting the data in deep learning. If put in the simple term, tensors are just multidimensional arrays that allow developers to represent the data in a layer, which means deep learning you are using contains high-level data sets where each dimension represents a different feature.


The foremost benefit of using tensors is it provides the much-needed platform-flexibility and is easy to trainable on CPU. Apart from this, tensors have the auto differentiation capabilities, advanced support system for queues, threads, and asynchronous computation. All these features also make it customizable.



## Q2. Define the concept of RNN?

### Answer:


RNN is the artificial neural which were created to analyze and recognize the patterns in the sequences of the data. Due to their internal memory, RNN can certainly remember the things about the inputs they receive.



## Most common issues faced with RNN

Although RNN is around for a while and uses backpropagation, there are some common issues faced by developers who work it out of all, some of the most common issues are:

- Exploding gradients
- Vanishing gradients



### Q3. What is a ResNet, and where would you use it? Is it efficient?


**Answer:**

Among the various neural networks that are used for computer vision, ResNet (Residual Network), is one of the most popular ones. It allows us to train extremely deep neural networks, which is the prime reason for its huge usage and popularity. Before the invention of this network, training extremely deep neural networks was almost impossible.

To understand why we must look at the vanishing gradient problem which is an issue that arises when the gradient is backpropagated to all the layers. As a large number of multiplications are performed, the size of the network keeps decreasing till it becomes extremely small, and thus, the network starts performing badly. ResNet helps to counter the vanishing gradient problem.

The efficiency of this network is highly dependent on the concept of skip connections. Skip connections are a method of allowing a shortcut path through which the gradient can flow, which in effect helps counter the vanishing gradient problem.

An example of a skip connection is shown below:



In general, a skip connection allows us to skip the training of a few layers. Skip connections are also called identity shortcut connections as they allow us to directly compute an identity function by just relying on these connections and not having to look at the whole network.

The skipping of these layers makes ResNet an extremely efficient network.

## Q4. Transfer learning is one of the most useful concepts today. Where can it be used?

### Answer:

Pre-trained models are probably one of the most common use cases for transfer learning

For anyone who does not have access to huge computational power, training complex models is always a challenge. Transfer learning aims to help by both improving the performance and speeding up your network.

In layman terms, transfer learning is a technique in which a model that has already been trained to do one task is used for another without much change. This type of learning is also called multi-task learning.

Many models that are pre-trained are available online. Any of these models can be used as a starting point in the creation of the new model required. After just using the weights, the model must be refined and adapted on the required data by tuning the parameters of the model.

Model name	Speed (ms)	COCO mAP[^1]	Outputs
ssd_mobilenet_v1_coco	30	21	Boxes
ssd_mobilenet_v1_0.75_depth_coco ☆	26	18	Boxes
ssd_mobilenet_v1_quantized_coco ☆	29	18	Boxes
ssd_mobilenet_v1_0.75_depth_quantized_coco ☆	29	16	Boxes
<u>ssd_mobilenet_v1_ppn_coco ☆</u> 	26	20	Boxes
ssd_mobilenet_v1_fpn_coco ☆	56	32	Boxes
ssd_resnet_50_fpn_coco ☆	76	35	Boxes
ssd_mobilenet_v2_coco	31	22	Boxes
ssd_mobilenet_v2_quantized_coco	29	22	Boxes
ssdlite_mobilenet_v2_coco	27	22	Boxes
ssd_inception_v2_coco	42	24	Boxes
faster_rcnn_inception_v2_coco	58	28	Boxes

---

The general idea behind transfer learning is to transfer knowledge not data. For humans, this task is easy – we can generalize models that we have mentally created a long time ago for a different purpose. One or two samples is almost always enough – however, in the case of neural networks, a huge amount of data and computational power are required.

Transfer learning should generally be used when we don't have a lot of labeled training data, or if there already exists a network for the task you are trying to achieve, probably trained on a much more massive dataset. Note, however, that the input of the model must have the same size during training. Also, this works only if the tasks are fairly similar to each other, and the features learned can be generalized. For example, something like learning how to recognize vehicles can probably be extended to learn how to recognize airplanes and helicopters.

## **Q5. What does tuning of hyperparameters signify? Explain with examples.**

### **Answer:**


A hyperparameter is just a variable that defines the structure of the network. Let's go through some hyperparameters and see the effect of tuning them.

- 1 A number of hidden layers Most times, the presence or absence of a large number of hidden layers may determine the output, accuracy and training time of the neural network. Having a large number of these layers may sometimes cause an increase in accuracy.
- 2 Learning rate This is simply a measure of how fast the neural network will change its parameters. A large learning rate may lead to the network not being able to converge, but might also speed up learning. On the other hand, a smaller value for the learning rate will probably slow down the network but might lead to the network being able to converge.
- 3 Number of epochs This is the number of times the entire training data is run through the network. Increasing the number of epochs leads to better accuracy.
- 4 Momentum Momentum is a measure of how and where the network will go while taking into account all of its past actions. A proper measure of momentum can lead to a better network.
- 5 Batch Size Batch size determines the number of subsamples that are inputs to the network before every parameter update.

## Q6. Why are deep learning models referred as black boxes?

### Answer:

- ately, the concept of deep learning being a black box has been floating around A black box is a system whose functioning cannot be properly grasped, but the output produced can be understood and utilized
- ow, since most models are mathematically sound and are created based on legit equations, how is it possible that we do not know how the system works▫



First, it is almost impossible to visualize the functions that are generated by a system Most machine learning models end up with such complex output that a human cant make sense of it

Second, there are networks with millions of hyperparameters As a human, we can grasp around 10 to 15 parameters But analysing a million of them seems out of the question

Third and most important, it becomes very hard, if not impossible, to trace back why the system made the decisions it did This may not sound like a huge problem to worry about but consider the case of a self driving car If the car hits someone on the road, we need to understand why that happened and prevent it But this isn t possible if we do not understand how the system works

To make a deep learning model not be a black box, a new field called Explainable Artificial Intelligence or simply, Explainable AI is emerging. This field aims to be able to create intermediate results and trace back the decision-making process of a system.

## Q7. Why do we have gates in neural networks?

### Answer:

To understand gates, we must first understand recurrent neural networks.

Recurrent neural networks allow information to be stored as a memory using loops. Thus, the output of a recurrent neural network is not only based on the current input but also the past inputs which are stored in the memory of the network. Backpropagation is done through time, but in general, the truncated version of this is used for longer sequences.

Gates are generally used in networks that are dependent on time. In effect, any network which would require memory, so to speak, would benefit from the use of gates. These gates are generally used to keep track of any information that is required by the network without leading to a state of either vanishing or exploding gradients. Such a network can also preserve the error through time. Since a sense of constant error is maintained, the network can learn better.

## Logic Gates


Name	NOT	AND	NAND	OR	NOR	XOR	XNOR																																																																																																
Alg. Expr.	$\bar{A}$	$AB$	$\bar{A}\bar{B}$	$A+B$	$\bar{A}+\bar{B}$	$A \oplus B$	$\bar{A} \oplus \bar{B}$																																																																																																
Symbol																																																																																																							
Truth Table	<table border="1"> <tr> <th>A</th><th>X</th></tr> <tr> <td>0</td><td>1</td></tr> <tr> <td>1</td><td>0</td></tr> </table>	A	X	0	1	1	0	<table border="1"> <tr> <th>B</th><th>A</th><th>X</th></tr> <tr> <td>0</td><td>0</td><td>0</td></tr> <tr> <td>0</td><td>1</td><td>0</td></tr> <tr> <td>1</td><td>0</td><td>0</td></tr> <tr> <td>1</td><td>1</td><td>1</td></tr> </table>	B	A	X	0	0	0	0	1	0	1	0	0	1	1	1	<table border="1"> <tr> <th>B</th><th>A</th><th>X</th></tr> <tr> <td>0</td><td>0</td><td>1</td></tr> <tr> <td>0</td><td>1</td><td>1</td></tr> <tr> <td>1</td><td>0</td><td>1</td></tr> <tr> <td>1</td><td>1</td><td>1</td></tr> </table>	B	A	X	0	0	1	0	1	1	1	0	1	1	1	1	<table border="1"> <tr> <th>B</th><th>A</th><th>X</th></tr> <tr> <td>0</td><td>0</td><td>0</td></tr> <tr> <td>0</td><td>1</td><td>0</td></tr> <tr> <td>1</td><td>0</td><td>0</td></tr> <tr> <td>1</td><td>1</td><td>0</td></tr> </table>	B	A	X	0	0	0	0	1	0	1	0	0	1	1	0	<table border="1"> <tr> <th>B</th><th>A</th><th>X</th></tr> <tr> <td>0</td><td>0</td><td>1</td></tr> <tr> <td>0</td><td>1</td><td>1</td></tr> <tr> <td>1</td><td>0</td><td>1</td></tr> <tr> <td>1</td><td>1</td><td>1</td></tr> </table>	B	A	X	0	0	1	0	1	1	1	0	1	1	1	1	<table border="1"> <tr> <th>B</th><th>A</th><th>X</th></tr> <tr> <td>0</td><td>0</td><td>0</td></tr> <tr> <td>0</td><td>1</td><td>1</td></tr> <tr> <td>1</td><td>0</td><td>1</td></tr> <tr> <td>1</td><td>1</td><td>1</td></tr> </table>	B	A	X	0	0	0	0	1	1	1	0	1	1	1	1	<table border="1"> <tr> <th>B</th><th>A</th><th>X</th></tr> <tr> <td>0</td><td>0</td><td>1</td></tr> <tr> <td>0</td><td>1</td><td>0</td></tr> <tr> <td>1</td><td>0</td><td>0</td></tr> <tr> <td>1</td><td>1</td><td>1</td></tr> </table>	B	A	X	0	0	1	0	1	0	1	0	0	1	1	1
A	X																																																																																																						
0	1																																																																																																						
1	0																																																																																																						
B	A	X																																																																																																					
0	0	0																																																																																																					
0	1	0																																																																																																					
1	0	0																																																																																																					
1	1	1																																																																																																					
B	A	X																																																																																																					
0	0	1																																																																																																					
0	1	1																																																																																																					
1	0	1																																																																																																					
1	1	1																																																																																																					
B	A	X																																																																																																					
0	0	0																																																																																																					
0	1	0																																																																																																					
1	0	0																																																																																																					
1	1	0																																																																																																					
B	A	X																																																																																																					
0	0	1																																																																																																					
0	1	1																																																																																																					
1	0	1																																																																																																					
1	1	1																																																																																																					
B	A	X																																																																																																					
0	0	0																																																																																																					
0	1	1																																																																																																					
1	0	1																																																																																																					
1	1	1																																																																																																					
B	A	X																																																																																																					
0	0	1																																																																																																					
0	1	0																																																																																																					
1	0	0																																																																																																					
1	1	1																																																																																																					

These gated units can be considered as units with recurrent connections. They also contain additional neurons, which are gates. If you relate this process to a signal processing system, the gate is used to

regulate which part of the signal passes through. A sigmoid activation function is used which means that the values taken are from 0 to 1.

An advantage of using gates is that it enables the network to either forget information that it has already learned or to selectively ignore information either based on the state of the network or the input the gate receives.

Gates are extensively used in recurrent neural networks, especially in Long Short-Term Memory (LSTM) networks. A general LSTM network will have 3 to 5 gates, typically an input gate, output gate, hidden gate, and activation gate.



$$z_t = \sigma(W_z \cdot [h_{t-1}, x_t])$$

$$r_t = \sigma(W_r \cdot [h_{t-1}, x_t])$$

$$\tilde{h}_t = \tanh(W \cdot [r_t * h_{t-1}, x_t])$$

$$h_t = (1 - z_t) * h_{t-1} + z_t * \tilde{h}_t$$

## Q8. What is a Sobel filter?

**Answer:**

The Sobel filter performs a two-dimensional spatial gradient measurement on a given image, which then emphasizes regions that have a high spatial frequency. In effect, this means finding edges.

In most cases, Sobel filters are used to find the approximate absolute gradient magnitude for every point in a grayscale image. The operator consists of a pair of  $3 \times 3$  convolution kernels. One of these kernels is rotated by 90 degrees.

-1	0	+1
-2	0	+2
-1	0	+1

x filter

+1	+2	+1
0	0	0
-1	-2	-1

y filter

These kernels respond to edges that run horizontal or vertical with respect to the pixel grid, one kernel for each orientation. A point to note is that these kernels can be applied either separately or can be combined to find the absolute magnitude of the gradient at every point.

The Sobel operator has a large convolution kernel, which ends up smoothing the image to a greater extent, and thus, the operator becomes less sensitive to noise. It also produces higher output values for similar edges compared to other methods.


To overcome the problem of output values from the operator overflowing the maximum allowed pixel value per image type, avoid using image types that support pixel values

## Q9. What is the purpose of a Boltzmann Machine?

### Answer:

Boltzmann machines are algorithms that are based on physics, specifically thermal equilibrium. A special and more well-known case of Boltzmann machines is the Restricted Boltzmann machine, which is a type of Boltzmann machine where there are no connections between hidden layers of the network.

The concept was coined by Geoff Hinton, who most recently won the Turing award. In general, the algorithm uses the laws of thermodynamics and tries to optimize a global distribution of energy in the system.



In discrete mathematical terms, a restricted Boltzmann machine can be called a symmetric bipartite graph, i.e., two symmetric layers. These machines are a form of unsupervised learning, which means that there are no labels provided with data. It uses stochastic binary units to reach this state.

Boltzmann machines are derived from Markov state machines. A Markov State Machine is a model that can be used to represent almost any computable function. The restricted Boltzmann machine can be regarded as an undirected graphical model. It is used in dimensionality reduction, collaborative filtering, learning features as well as modeling. It can also be used for classification and regression. In general, restricted Boltzmann machines are composed of a two-layer network, which can then be extended further.

Note that these models are probabilistic since each of the nodes present in the system learns low-level features from items in the dataset. For example, if we take a grayscale image, each node that is responsible for the visible layer will take just one pixel value from the image.

A part of the process of creating such a machine is a feature hierarchy where sequences of activations are grouped in terms of features. In thermodynamics principles, simulated annealing is a process that the machine follows to separate signal and noise.

---

## Q10. What are the types of weight initialization?

### Answer:

There are two major types of weight initialization:- zero initialization and random initialization

□ **Zero initialization:** In this process, biases and weights are initialised to 0. If the weights are set to 0, all derivatives with respect to the loss functions in the weight matrix become equal. Hence, none of the weights change during subsequent iterations. Setting the bias to 0 cancels out any effect it may have.

All hidden units become symmetric due to zero initialization. In general, zero initialization is not very useful or accurate for classification and thus must be avoided when any classification task is required.

**Random initialization:** As compared to 0 initialization, this involves setting random values for the weights. The only disadvantage is that setting very high values will increase the learning time as the sigmoid activation function maps close to 1. Likewise, if low values are set, the learning time increases as the activation function is mapped close to 0.

Setting too high or too low values thus generally leads to the exploding or vanishing gradient problem.

□ Few types of weight initialization like **He initialization** and **Xavier initialization** have also emerged. These are based on specific equations and are not mentioned here due to their sheer complexity.

**DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview  
Preparation)**

**# DAY 12**

## Q1. Where is the confusion matrix used? Which module would you use to show it?

### Answer:

In machine learning confusion matrix is one of the easiest ways to summarize the performance of your algorithm

At times it is difficult to judge the accuracy of a model by just looking at the accuracy because of problems like unequal distribution So a better way to check how good your model is is to use a confusion matrix

First let's look at some key terms

**Classification accuracy** This is the ratio of the number of correct predictions to the number of predictions made

**True positives** Correct predictions of true events

**False positives** Incorrect predictions of true events

**True negatives** Correct predictions of false events

**False negatives** Incorrect predictions of false events

The confusion matrix is now simply a matrix containing true positives false positives true negatives false negatives

		Predicted Class		
		Positive	Negative	
Actual Class	Positive	True Positive (TP)	False Negative (FN) <i>Type II Error</i>	Sensitivity $\frac{TP}{(TP + FN)}$
	Negative	False Positive (FP) <i>Type I Error</i>	True Negative (TN)	Specificity $\frac{TN}{(TN + FP)}$
	Precision $\frac{TP}{(TP + FP)}$	Negative Predictive Value $\frac{TN}{(TN + FN)}$	Accuracy $\frac{TP + TN}{(TP + TN + FP + FN)}$	

## Q2: What is Accuracy?

### Answer:

It is the most intuitive performance measure and it simply a ratio of correctly predicted to the total observations. We can say as if we have high accuracy then our model is best. Yes we could say that accuracy is a great measure but only when you have symmetric datasets where false positives and false negatives are almost same.

$$\text{Accuracy} = \frac{\text{True Positive} + \text{True Negative}}{\text{True Positive} + \text{False Positive} + \text{False Negative} + \text{True Negative}}$$

		Condition Absent	Condition Present
Negative Result	True Negative	False Negative	
	False Positive	True Positive	
Positive Result			

## Q3: What is Precision?

### Answer:

It is also called as the positive predictive value Number of correct positives in your model that predicts compared to the total number of positives it predicts.

$$\text{Precision} = \frac{\text{True Positives}}{\text{True Positives} + \text{False Positives}}$$

$$\text{Precision} = \frac{\text{True Positives}}{\text{Total predicted positive}}$$

It is the number of positive elements predicted properly divided by the total number of positive elements predicted.

We can say Precision is a measure of exactness quality or accuracy. High precision

Means that more or all of the positive results you predicted are correct.

## Q4: What is Recall?

### Answer:

Recall we can also called as sensitivity or true positive rate

It is several positives that our model predicts compared to the actual number of positives in our data

$$\text{Recall} = \text{True Positives} / (\text{True Positives} + \text{False Positives})$$

$$\text{Recall} = \text{True Positives} / \text{Total Actual Positive}$$

Recall is a measure of completeness High recall which means that our model classified most or all of the possible positive elements as positive


## Q5: What is F1 Score?

### Answer:

We use Precision and recall together because they complement each other in how they describe the effectiveness of a model The F1 score that combines these two as the weighted harmonic mean of precision and recall

$$\text{F1 Score} = 2 * (\text{Precision} * \text{Recall}) / (\text{Precision} + \text{Recall})$$

$$\begin{aligned} \text{Precision} &= \frac{\text{True Positive}}{\text{Actual Results}} \quad \text{or} \quad \frac{\text{True Positive}}{\text{True Positive} + \text{False Positive}} \\ \text{Recall} &= \frac{\text{True Positive}}{\text{Predicted Results}} \quad \text{or} \quad \frac{\text{True Positive}}{\text{True Positive} + \text{False Negative}} \\ \text{Accuracy} &= \frac{\text{True Positive} + \text{True Negative}}{\text{Total}} \end{aligned}$$



## Q6: What is Bias and Variance trade-off?

### Answer:

#### Bias

Bias means it's how far are the predicted values from the actual values. If the average predicted values are far off from the actual values then we call this as high bias.


When our model has a high bias then it means that our model is too simple and does not capture the complexity of data thus underfitting the data.

#### Variance


It occurs when our model performs good on the trained dataset but does not do well on a dataset that it is not trained on like a test dataset or validation dataset. It tells us that actual value is how much scattered from the predicted value.

Because of High variance it causes overfitting that implies that the algorithm models random noise present in the training data.

When model has high variance then model becomes very flexible and tunes itself to the data points of the training set.



Bias-variance: It decomposition essentially decomposes the learning error from any algorithm by adding bias the variance and a bit of irreducible error due to noise in the underlying dataset. Essentially if we make the model more complex and add more variables We ll lose bias but gain some variance to get the optimally reduced amount of error you ll have to tradeoff bias and variance. We don t want either high bias or high variance in your model.



Bias and variance using bulls-eye diagram

## Q7. What is data wrangling? Mention three points to consider in the process.

### Answer:

Data wrangling is a process by which we convert and map data. This changes data from its raw form to a format that is a lot more valuable.

Data wrangling is the first step for machine learning and deep learning. The end goal is to provide data that is actionable and to provide it as fast as possible.

There are three major things to focus on while talking about data wrangling

## 1. Acquiring data

The first and probably the most important step in data science is the acquiring sorting and cleaning of data. This is an extremely tedious process and requires the most amount of time.

One needs to:

- Check if the data is valid and up-to-date
- Check if the data acquired is relevant for the problem at hand

Sources for data collection Data is publicly available on various websites like kaggle.com [data.gov](#) [World Bank](#) [Five Thirty Eight Datasets](#) AWS Datasets Google Datasets

## 2. Data cleaning


Data cleaning is an essential component of data wrangling and requires a lot of patience. To make the job easier it is first essential to format the data make the data readable for humans at first.

The essentials involved are:

- Format the data to make it more readable
- Find outliers (data points that do not match the rest of the dataset) in data
- Find missing values and remove them from the data set (without this any model being trained becomes incomplete and useless)

## 3. Data Computation

At times your machine not have enough resources to run your algorithm e.g. you might not have a GPU. In these cases you can use publicly available APIs to run your algorithm. These are standard end points found on the web which allow you to use computing power over the web and process data without having to rely on your own system. An example would be the Google Colab Platform.



## Q8. Why is normalization required before applying any machine learning model? What module can you use to perform normalization?

### Answer:

Normalization is a process that is required when an algorithm uses something like distance measures. Examples would be clustering data, finding cosine similarities, creating recommender systems.

Normalization is not always required and is done to prevent variables that are on higher scale from affecting outcomes that are on lower levels. For example, consider a dataset of employees' income. This data won't be on the same scale if you try to cluster it. Hence, we would have to normalize the data to prevent incorrect clustering.

A key point to note is that normalization does not distort the differences in the range of values.

A problem we might face if we don't normalize data is that gradients would take a very long time to descend and reach the global maxima/minima.

For numerical data, normalization is generally done between the range of 0 to 1.

The general formula is:

$$X_{\text{new}} = (x - \text{xmin}) / (\text{xmax} - \text{xmin})$$

## Normalization Formula

$$X_{\text{normalized}} = \frac{(X - X_{\text{minimum}})}{(X_{\text{maximum}} - X_{\text{minimum}})}$$



## Q9. What is the difference between feature selection and feature extraction?

Feature selection and feature extraction are two major ways of fixing the curse of dimensionality

### 1. Feature selection:

Feature selection is used to filter a subset of input variables on which the attention should focus  
Every other variable is ignored This is something which we as humans tend to do subconsciously


Many domains have tens of thousands of variables out of which most are irrelevant and redundant  
Feature selection limits the training data and reduces the amount of computational resources used  
It can significantly improve a learning algorithms performance

In summary we can say that the goal of feature selection is to find out an optimal feature subset  
This might not be entirely accurate however methods of understanding the importance of features also exist Some modules in python such as gboost help achieve the same

### 2. Feature extraction

Feature extraction involves transformation of features so that we can extract features to improve the process of feature selection For example in an unsupervised learning problem the extraction of bigrams from a text or the extraction of contours from an image are examples of feature extraction

The general workflow involves applying feature extraction on given data to extract features and then apply feature selection with respect to the target variable to select a subset of data In effect this helps improve the accuracy of a model



## Q10. Why is polarity and subjectivity an issue?

Polarity and subjectivity are terms which are generally used in sentiment analysis

Polarity is the variation of emotions in a sentence. Since sentiment analysis is widely dependent on emotions and their intensity, polarity turns out to be an extremely important factor.

In most cases, opinions and sentiment analysis are evaluations. They fall under the categories of emotional and rational evaluations.

Rational evaluations, as the name suggests, are based on facts and rationality while emotional evaluations are based on non-tangible responses which are not always easy to detect.


Subjectivity in sentiment analysis is a matter of personal feelings and beliefs which may or may not be based on any fact. When there is a lot of subjectivity in a text, it must be explained and analysed in context. On the contrary, if there was a lot of polarity in the text, it could be expressed as a positive, negative or neutral emotion.

## Q11. When would you use ARIMA?

Answer:

ARIMA is a widely used statistical method which stands for Auto Regressive Integrated Moving Average. It is generally used for analyzing time series data and time series forecasting. Let's take a quick look at the terms involved.

Auto Regression is a model that uses the relationship between the observation and some numbers of lagging observations.



---

Integrated means use of differences in raw observations which help make the time series stationary

Moving Averages is a model that uses the relationship and dependency between the observation and residual error from the models being applied to the lagging observations

Note that each of these components are used as parameters After the construction of the model a linear regression model is constructed

Data is prepared by:

- Finding out the differences
- Removing trends and structures that will negatively affect the model
- Finally making the model stationary

**DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview  
Preparation)  
# Day13**

## Q1. What is Autoregression?

### Answer:

The autoregressive (AR) model is commonly used to model time-varying processes and solve problems in the fields of natural science, economics and finance, and others. The models have always been discussed in the context of random process and are often perceived as statistical tools for time series data.

A regression model, like linear regression, models an output value which are based on a linear combination of input values

**Example:**  $y = b_0 + b_1 X$

Where  $y$  is the prediction,  $b_0$  and  $b_1$  are coefficients found by optimising the model on training data, and  $X$  is an input value

This model technique can be used on the time series where input variables are taken as observations at previous time steps, called lag variables


For example, we can predict the value for the next time step ( $t+1$ ) given the observations at the last two time steps ( $t-1$  and  $t-2$ ). As a regression model, this would look as follows:

$$X(t+1) = b_0 + b_1 * X(t-1) + b_2 * X(t-2)$$

Because the regression model uses the data from the same input variable at previous time steps, it is referred to as an autoregression

The notation  $AR(p)$  refers to the autoregressive model of order  $p$ . The  $AR(p)$  model is written

$$X_t = c + \sum_{i=1}^p \varphi_i X_{t-i} + \varepsilon_t.$$



## Q2. What is Moving Average?


**Answer:**

**Moving average:** From a dataset, we will get an overall idea of trends by this technique; it is an average of any subset of numbers. For forecasting long-term trends, the moving average is extremely useful for it. We can calculate it for any period. For example: if we have sales data for twenty years, we can calculate the five-year moving average, a four-year moving average, a three-year moving average and so on. Stock market analysts will often use a 50 or 200-day moving average to help them see trends in the stock market and (hopefully) forecast where the stocks are headed.

The notation  $MA(q)$  refers to the moving average model of order  $q$ :

$$X_t = \mu + \varepsilon_t + \sum_{i=1}^q \theta_i \varepsilon_{t-i}$$

where the  $\theta_1, \dots, \theta_q$  are the parameters of the model,  $\mu$  is the expectation of  $X_t$  (often assumed to equal 0), and the  $\varepsilon_t, \varepsilon_{t-1}, \dots$  are again, white noise error terms.



The notation  $MA(q)$  refers to the moving average model of order  $q$ :

## Q3. What is Autoregressive Moving Average (ARMA)?

**Answer:**

**ARMA:** It is a model of forecasting in which the methods of autoregression (AR) analysis and moving average (MA) are both applied to time-series data that is well behaved. In ARMA it is assumed that the time series is stationary and when it fluctuates, it does so uniformly around a particular time.

**AR (Autoregression model)-**

Autoregression (AR) model is commonly used in current spectrum estimation

The following is the procedure for using ARMA

- Selecting the AR model and then equalizing the output to equal the signal being studied if the input is an impulse function or the white noise It should at least be good approximation of signal
- Finding a model s parameters number using the known autocorrelation function or the data
- Using the derived model parameters to estimate the power spectrum of the signal

### **Moving Average (MA) model-**


It is a commonly used model in the modern spectrum estimation and is also one of the methods of the model parametric spectrum analysis The procedure for estimating MA model s signal spectrum is as follows

- Selecting the MA model and then equalising the output to equal the signal understudy in the case where the input is an impulse function or white noise It should be at least a good approximation of the signal
- Finding the model s parameters using the known autocorrelation function
- Estimating the signal s power spectrum using the derived model parameters

In the estimation of the ARMA parameter spectrum, the AR parameters are first estimated, and then the MA parameters are estimated based on these AR parameters The spectral estimates of the ARMA model are then obtained The parameter estimation of the MA model is, therefore often calculated as a process of ARMA parameter spectrum association

The notation ARMA( $p, q$ ) refers to the model with  $p$  autoregressive terms and  $q$  moving-average terms This model contains the AR( $p$ ) and MA( $q$ ) models,

$$X_t = c + \varepsilon_t + \sum_{i=1}^p \varphi_i X_{t-i} + \sum_{i=1}^q \theta_i \varepsilon_{t-i}.$$



## Q4. What is Autoregressive Integrated Moving Average (ARIMA)?

### Answer:

ARIMA: It is a statistical analysis model that uses time-series data to either better understand the data set or to predict future trends

An ARIMA model can be understood by the outlining each of its components as follows-

- **Autoregression (AR):** It refers to a model that shows a changing variable that regresses on its own lagged, or prior, values
- **Integrated (I):** It represents the differencing of raw observations to allow for the time series to become stationary, i.e., data values are replaced by the difference between the data values and the previous values
- **Moving average (MA):** It incorporates the dependency between an observation and the residual error from the moving average model applied to the lagged observations

Each component functions as the parameter with a standard notation. For ARIMA models, the standard notation would be the ARIMA with p, d, and q, where integer values substitute for the parameters to indicate the type of the ARIMA model used. The parameters can be defined as-


- *p*: It is the number of lag observations in the model; also known as the lag order
- *d*: It is the number of times that the raw observations are differenced; also known as the degree of differencing
- *q*: It is the size of the moving average window; also known as the order of the moving average

### ARIMA

Autoregressive Moving  
Averages

$ARIMA(p,d,q)(P,D,Q)m$

- *p* = non-seasonal AR order
- *d* = non-seasonal differencing
- *q* = non-seasonal MA order
- *P* = seasonal AR order
- *D* = seasonal differencing
- *Q* = seasonal MA order
- *m* = number of periods/season



$ARIMA(1,0,1)(4, 0, 7, 24)$

## Q5.What is SARIMA (Seasonal Autoregressive Integrated Moving-Average)?

### Answer:

Seasonal ARIMA: It is an extension of ARIMA that explicitly supports the univariate time series data with the seasonal component

It adds three new hyper-parameters to specify the autoregression (AR), differencing (I) and the moving average (MA) for the seasonal component of the series, as well as an additional parameter for the period of the seasonality

Configuring the SARIMA requires selecting hyperparameters for both the trend and seasonal elements of the series

### Trend Elements

Three trend elements requires the configuration

They are same as the ARIMA model, specifically-

**p**: It is Trend autoregression order

**d**: It is Trend difference order

**o**: It is Trend moving average order

### Seasonal Elements-

Four seasonal elements are not the part of the ARIMA that must be configured, they are-

**P**: It is Seasonal autoregressive order

**D**: It is Seasonal difference order


**o** : It is Seasonal moving average order

**m**: It is the number of time steps for the single seasonal period

Together, the notation for the SARIMA model is specified as-

**SARIMA(p,d,o)(P,D,o )m-**

The elements can be chosen through careful analysis of the ACF and PACF plots looking at the correlations of recent time steps



## Q6. What is Seasonal Autoregressive Integrated Moving-Average with Exogenous Regressors (SARIMAX) ?


**Answer:**

SARIMAX: It is an extension of the SARIMA model that also includes the modelling of the exogenous variables

Exogenous variables are also called the covariates and can be thought of as parallel input sequences that have observations at the same time steps as the original series. The primary series may be referred as endogenous data to contrast it from exogenous sequence(s). The observations for exogenous variables are included in the model directly at each time step and are not modeled in the same way as the primary endogenous sequence (e.g. as an AR, MA, etc process)

The SARIMAX method can also be used to model the subsumed models with exogenous variables, such as ARX, MAX, ARMAX, and ARIMAX

The method is suitable for univariate time series with trend and/or seasonal components and exogenous variables



## Q7. What is Vector autoregression (VAR)?


**Answer:**

**VAR:** It is a stochastic process model used to capture the linear interdependencies among multiple time series. VAR models generalise the univariate autoregressive model (AR model) by allowing for more than one evolving variable. All variables in the VAR enter the model in the same way: each variable has an equation explaining its evolution based on its own lagged values, the lagged values of the other model variables, and an error term. VAR modelling does not require as much knowledge about the forces influencing the variable as do structural models with simultaneous equations: The only prior knowledge required is a list of variables which can be hypothesised to affect each other intertemporally.

A VAR model describes the evolution of the set of  $k$  variables over the same sample period ( $t = 1, \dots, T$ ) as the linear function of only their past values. The variables are collected in the  $k$ -vector ( $(k \times 1)$ -matrix)  $y_t$ , which has as the ( $i^{\text{th}}$ ) element,  $y_{i,t}$ , the observation at time  $t$  of the ( $i^{\text{th}}$ ) variable. Example: if the ( $i^{\text{th}}$ ) variable is the GDP, then  $y_{i,t}$  is the value of GDP at time  $t$ .

$$y_t = c + A_1 y_{t-1} + A_2 y_{t-2} + \dots + A_p y_{t-p} + e_t,$$

where the observation  $y_{t-i}$  is called the ( $i^{\text{th}}$ ) **lag** of  $y$ ,  $c$  is the  $k$ -vector of constants (intercepts),  $A_i$  is a time-invariant ( $k \times k$ )-matrix, and  $e_t$  is a  $k$ -vector of error terms satisfying




## Q8. What is Vector Autoregression Moving-Average (VARMA)?

**Answer:**

**VARMA:** It is a method that models the next step in each time series using an ARMA model. It is the generalisation of ARMA to multiple parallel time series. Example- multivariate time series

The notation for a model involves specifying the order for the AR(p) and the MA(q) models as parameters to the VARMA function, e.g. VARMA (p, q). The VARMA model can also be used to develop VAR or VMA models.

This method is suitable for multivariate time series without trend and seasonal components.



## Q9. What is Vector Autoregression Moving-Average with Exogenous Regressors (VARMAX)?

**Answer:**

**VARMAX:** It is an extension of the VARMA model that also includes the modelling of the exogenous variables. It is the multivariate version of the ARMAX method.

Exogenous variables are also called the covariates and can be thought of as parallel input sequences that have observations at the same time steps as the original series. The primary series(es) are referred as the endogenous data to contrast it from the exogenous sequence(s). The observations for the exogenous variables are included in the model directly at each time step and are not modeled in the same way as the primary endogenous sequence (Example- as an AR, MA, etc.)

This method can also be used to model subsumed models with exogenous variables, such as VARX and the VMAX.

This method is suitable for multivariate time series without trend and seasonal components and exogenous variables.

## Q10. What is Simple Exponential Smoothing (SES)?

### Answer:

SES: It method models the next time step as an exponentially weighted linear function of observations at prior time steps

This method is suitable for univariate time series without trend and seasonal components

**Exponential smoothing** is the rule of thumb technique for smoothing time series data using the exponential window function Whereas in the simple moving average, the past observations are weighted equally, exponential functions are used to assign exponentially decreasing weights over time It is easily learned and easily applied procedure for making some determination based on prior assumptions by the user, such as seasonality Exponential smoothing is often used for analysis of time-series data


Exponential smoothing is one of many window functions commonly applied to smooth data in signal processing, acting as low-pass filters to remove high-frequency noise

The raw data sequence is often represented by  $\{x_t\}$  beginning at time  $t = 0$ , and the output of the exponential smoothing algorithm is commonly written as  $\{s_t\}$  which may be regarded as a best estimate of what the next value of  $x$  will be When the sequence of observations begins at time  $t=0$ , the simplest form of exponential smoothing is given by the formulas:

$$s_0 = x_0$$

$$s_t = \alpha x_t + (1 - \alpha)s_{t-1}, t > 0$$

where  $\alpha$  is the *smoothing factor*, and  $0 < \alpha < 1$ .



**DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview  
Preparation)**

**# DAY 14**


## Q1. What is Alexnet?

### Answer:

The Alex Krizhevsky, Geoffrey Hinton and Ilya Sutskever created the neural network architecture called AlexNet and won Image Classification Challenge (ILSVRC) in 2012. They trained their network on 1.2 million high-resolution images into 1000 different classes with 60 million parameters and 650,000 neurons. The training was done on two GPUs with split layer concept because GPUs were a little bit slow at that time.

AlexNet is the name of convolutional neural network which has had a large impact on the field of machine learning, specifically in the application of deep learning to machine vision. The network had very similar architecture as the LeNet by Yann LeCun et al but was deeper with more filters per layer, and with the stacked convolutional layers. It consists of ( $11 \times 11$ ,  $5 \times 5$ ,  $3 \times 3$ , convolutions), max pooling, dropout, data augmentation, ReLU activations and SGD with the momentum. It attached with ReLU activations after every convolutional and fully connected layer. AlexNet was trained for six days simultaneously on two Nvidia Geforce GTX 580 GPUs, which is the reason for why their network is split into the two pipelines.

### Architecture



AlexNet contains eight layers with weights, first five are convolutional, and the remaining three are fully connected. The output of last fully-connected layer is fed to a 1000-way softmax which produces a distribution over the 1000 class labels. The network maximises the multinomial logistic regression objective, which is equivalent to maximising the average across training cases of the log-probability of the correct label under the prediction distribution. The kernels of second, fourth, and the fifth convolutional layers are connected only with those kernel maps in the previous layer which reside on the same GPU. The kernels of third convolutional layer are connected to all the kernel maps in second layer. The neurons in fully connected layers are connected to all the neurons in the previous layers.


In short, AlexNet contains five convolutional layers and three fully connected layers. ReLU is applied after the very convolutional and the fully connected layer. Dropout is applied before the first and second fully connected layer. The network has 62.3 million parameters and needs 1.1 billion computation units in a forward pass. We can also see convolution layers, which accounts for 6% of all the parameters, consumes 95% of the computation.

## Q2. What is VGGNet?

### Answer:


VGGNet consists of 16 convolutional layers and is very appealing because of its very uniform architecture. Similar to AlexNet, only 3x3 convolutions, but lots of filters. Trained on 4 GPUs for 2-3 weeks. It is currently the most preferred choice in the community for extracting features from images. The weight configuration of the VGGNet is publicly available and has been used in many other applications and challenges as a baseline feature extractor. However, VGGNet consists of 138 million parameters, which can be a bit challenging to handle.

There are multiple variants of the VGGNet (VGG16, VGG19 etc.) which differ only in total number of layers in the networks. The structural details of the VGG16 network has been shown:



The idea behind having the fixed size kernels is that all the variable size convolutional kernels used in the Alexnet (11x11, 5x5, 3x3) can be replicated by making use of multiple 3x3 kernels as the building blocks. The replication is in term of the receptive field covered by kernels.

Let's consider the example. Say we have an input layer of the size  $5 \times 5 \times 1$ . Implementing the conv layer with kernel size of  $5 \times 5$  and stride one will result in the output feature map of  $(1 \times 1)$ . The same output feature map can be obtained by implementing the two  $(3 \times 3)$  Conv layers with stride of 1 as below:




Now, let's look at the number of variables needed to be trained. For a  $5 \times 5$  Conv layer filter, the number of variables is 25. On the other hand, two conv layers of kernel size  $3 \times 3$  have a total of  $3 \times 3 \times 2 = 18$  variables (a reduction of 28%).

### Q3. What is VGG16?


#### Answer:

**VGG16:** It is a convolutional neural network model proposed by the K Simonyan and A Zisserman from the University of Oxford in the paper Very Deep Convolutional Networks for the Large-Scale Image Recognition. The model achieves 92.7% top 5 test accuracy in ImageNet, which is the dataset of over 14 million images belonging to the 1000 classes. It was one of famous model submitted to ILSVRC-2014. It improves AlexNet by replacing the large kernel-sized filters (11 and 5 in the first and second convolutional layer, respectively) with multiple  $3 \times 3$  kernel-sized filters one after another. VGG16 was trained for weeks and was using NVIDIA Titan Black GPU's.



#### The Architecture

The architecture depicted below is VGG16



The input to the Cov1 layer is of fixed size of  $224 \times 224$  RGB image. The image is passed through the stack of convolutional (conv) layers, where the filters were used with a very small receptive field:  $3 \times 3$  (which is the smallest size to capture the notion of left/right, up/down, centre). In one of the configurations, it also utilises the  $1 \times 1$  convolution filters, which can be seen as the linear transformation of the input channels. The convolution stride is fixed to the 1 pixel, the spatial padding of the Conv layer input is such that, the spatial resolution is preserved after the convolution, i.e. the

padding is 1-pixel for  $3 \times 3$  Conv layers. Spatial pooling is carried out by the five max-pooling layers, which follows some of the Conv Layers. Max-pooling is performed over the  $2 \times 2$  pixel window, with stride 2.


Three Fully-Connected (FC) layers follow the stack of convolutional layers (which has the different depth in different architectures): the first two have 4096 channels each, the third performs 1000-way ILSVRC classification and thus contains 1000 channels. The final layer is softmax layer. The configurations of the fully connected layers is same in all the networks.

All hidden layers are equipped with rectification (ReLU) non-linearity. It is also noted that none of the networks (except for one) contain the Local Response Normalisation (LRN), such normalisation does not improve the performance on the ILSVRC dataset, but leads to increased memory consumption and computation time.

## Q4. What is ResNet?

### Answer:

At the ILSVRC 2015, so-called Residual Neural Network (ResNet) by the Kaiming He et al introduced the anovel architecture with skip connections and features heavy batch normalisation. Such skip connections are also known as the gated units or gated recurrent units and have the strong similarity to recent successful elements applied in RNNs. Thanks to this technique as they were able to train the NN with 152 layers while still having lower complexity than the VGGNet. It achieves the top-5 error rate of 3.57%, which beats human-level performance on this dataset.



## Q5. What is HAAR CASCADE?

### Answer:


**Haar Cascade:** It is the machine learning object detections algorithm used to identify the objects in an image or the video and based on the concept of features proposed by Paul Viola and Michael Jones in their paper "Rapid Object Detection using a Boosted Cascade of Simple Features" in 2001.

It is a machine learning-based approach where the cascade function is trained from the lot of positive and negative images. It is then used to detect the objects in other images.

The algorithm has four stages:

- Haar Feature Selection
- Creating Integral Images
- Adaboost Training
- Cascading Classifiers

It is well known for being able to detect faces and body parts in an image but can be trained to identify almost any object




## Q6. What is Transfer Learning?

### Answer:

**Transfer learning:** It is the machine learning method where the model developed for a task is reused as the starting point for the model on the second task

Transfer Learning differs from the traditional Machine Learning in that it is the use of pre-trained models that have been used for another task to jump-start the development process on a new task or problem



The benefits of the Transfer Learning are that it can speed up the time as it takes to develop and train the model by reusing these pieces or modules of already developed models. This helps to speed up the model training process and accelerate results.


## Q7. What is Faster, R-CNN?

### Answer:

**Faster R-CNN:** It has two networks: region proposal network (RPN) for generating region proposals and a network using these proposals to detect objects. The main difference here with the Fast R-CNN is that the later uses selective search to generate the region proposals. The time cost of generating the region proposals is much smaller in the RPN than selective search, when RPN shares the most computation with object detection network. In brief, RPN ranks region boxes (called anchors) and proposes the ones most likely containing objects.


### Anchors

Anchors play a very important role in Faster R-CNN. An anchor is the box. In default configuration of Faster R-CNN, there are nine anchors at the position of an image. The graph shows 9 anchors at the position (320, 320) of an image with size (600, 800).



### Region Proposal Network:

The output of the region proposal network is the bunch of boxes/proposals that will be examined by a classifier and regressor to check the occurrence of objects eventually To be more precise, RPN predicts the possibility of an anchor being background or foreground, and refine the anchor




### Q8. What is RCNN?

#### Answer:

To bypass the problem of selecting the huge number of regions, Ross Girshick et al proposed a method where we use the selective search to extract just 2000 regions from the image, and he called them as region proposals Therefore, instead of trying to classify the huge number of regions, you can work with 2000 regions

## R-CNN: Regions with CNN features



### Problems with R-CNN:


- It still takes the huge amount of time to train the network as we would have to classify 2000 region proposals per image
- It cannot be implemented real-time as it takes around 47 seconds for each test image
- The selective search algorithm is the fixed algorithm. Therefore, no learning is happening at that stage. This leads to the generation of the bad candidate region proposals

## Q9.What is GoogLeNet/Inception?

### Answer:

The winner of the ILSVRC 2014 competition was GoogLeNet from Google. It achieved a top-5 error rate of 6.67%. This was very close to human-level performance which the organisers of the challenge were now forced to evaluate. As it turns out, this was rather hard to do and required some human training to beat GoogLeNet's accuracy. After the few days of training, the human expert (Andrej Karpathy) was able to achieve the top-5 error rate of 5.1% (single model) and 3.6% (ensemble). The network used the CNN inspired by LeNet but implemented a novel element which is dubbed an inception module. It used batch normalisation, image distortions and RMSprop. This module is based on several very small convolutions to reduce the number of parameters drastically. Their architecture consisted of the 22-layer deep CNN but reduced the number of parameters from 60 million (AlexNet) to 4 million.


It contains  $1 \times 1$  Convolution at the middle of network, and global average pooling is used at the end of the network instead of using the fully connected layers. These two techniques are from another paper Network In-Network (NIN). Another technique, called inception module, is to have different sizes/types of convolutions for the same input and to stack all the outputs.



## Q10. What is LeNet-5?

### Answer:

**LeNet-5**, a pioneering 7-level convolutional network by the LeCun et al in 1998, that classifies digits, was applied by several banks to recognise hand-written numbers on checks (cheques) digitised in 32x32 pixel greyscale input images. The ability to process higher-resolution images requires larger and more convolutional layers, so the availability of computing resources constrains this technique.



LeNet-5 is a very simple network. It only has seven layers, among which there are three convolutional layers (C1, C3 and C5), two sub-sampling (pooling) layers (S2 and S4), and one fully connected layer (F6), that are followed by output layers. Convolutional layers use 5 by 5 convolutions with stride 1. Sub-sampling layers are 2 by 2 average pooling layers. Tanh sigmoid activations are used throughout the network. Several interesting architectural choices were made in LeNet-5 that are not very common in the modern era of deep learning.

# DATA SCIENCE INTERVIEW PREPARATION


(30 Days of Interview  
Preparation)

## # DAY 15

## Q1. What is Autoencoder?

**Answer:**

Autoencoder neural network: It is an unsupervised Machine learning algorithm that applies backpropagation setting the target values to be equal to the inputs. It is trained to attempt to copy its input to its output. Internally it has the hidden layer that describes a code used to represent the input.



It is trying to learn the approximation to the identity function to output  $\hat{x}$  that is similar to the  $x$ .

Autoencoders belongs to the neural network family but they are also closely related to PCA principal components analysis.


Auto encoders although it is quite similar to PCA but its Autoencoders are much more flexible than PCA. Autoencoders can represent both liners and non-linear transformation in encoding but PCA can perform linear transformation. Autoencoders can be layered to form deep learning network due to its Network representation.

**Types of Autoencoders:**

### 1 Denoising autoencoder


Autoencoders are Neural Networks which are used for feature selection and extraction. However when there are more nodes in hidden layer than there are inputs the Network is risking to learn so-called Identity Function also called Null Function meaning that output equals the input marking the Autoencoder useless.

Denoising Autoencoders solve this problem by corrupting the data on purpose by randomly turning some of the input values to zero. In general, the percentage of input nodes which are being set to zero is about 50%. Other sources suggest a lower count such as 30%. It depends on the amount of data and input nodes you have.



## 2 Sparse autoencoder

An autoencoder takes the input image or vector and learns code dictionary that changes the raw input from one representation to another. Where in sparse autoencoders with a sparsity enforcer that directs a single-layer network to learn code dictionary which in turn minimizes the error in reproducing the input while restricting number of code words for reconstruction. The sparse autoencoder consists a single hidden layer which is connected to the input vector by a weight matrix forming the encoding step. The hidden layer then outputs to a reconstruction vector using a tied weight matrix to form the decoder.



## Q2. What Is Text Similarity?


**Answer:**

When talking about text similarity different people have a slightly different notion on what text similarity means. In essence the goal is to compute how close two pieces of text are in 1 meaning or 2 surface closeness. The first is referred to as **semantic similarity** and the latter is referred to as **lexical similarity**. Although the methods for *lexical similarity* are often used to achieve *semantic similarity* to a certain extent achieving true semantic similarity is often much more involved.

## Lexical or Word Level Similarity


When referring to text similarity people refer to how similar the two pieces of text are at the surface level Example- how similar are the phrases *the cat ate the mouse* with *the mouse ate the cat food* by just looking at the words? On the surface if you consider only word-level similarity these two phrases with determiners disregarded appear very similar as 3 of the 6 unique words are an exact overlap

$$\text{Overlap} = \text{'cat ate mouse'} \cap \text{'mouse ate cat food'} = 3$$



## Semantic Similarity:

Another notion of similarity mostly explored by NLP research community is how similar in meaning are any two phrases? If we look at the phrases *the cat ate the mouse* and *the mouse ate the cat food* As we know that while the words significantly overlaps these two phrases have different meaning Meaning out of the phrases is often the more difficult task as it requires deeper level of analysis Example we can actually look at the simple aspects like order of words: *cat== ate== mouse* and *mouse== ate== cat food* Words overlap in this case the order of the occurrence is different and we can tell that these two phrases have different meaning This is just the one example Most people use the syntactic parsing to help with the semantic similarity Let's have a look at the parse trees for these two phrases What can you get from it?



### Q3. What is dropout in neural networks?


**Answer:**

When we training our neural network or model by updating each of its weights it might become too dependent on the dataset we are using. Therefore when this model has to make a prediction or classification it will not give satisfactory results. This is known as over-fitting. We might understand this problem through a real-world example: If a student of science learns *only* one chapter of a book and then takes a test on the *whole* syllabus he will probably fail.


To overcome this problem we use a technique that was introduced by Geoffrey Hinton in 2012. This technique is known as **dropout**.

Dropout refers to ignoring units i.e. neurons during the training phase of certain set of neurons which is chosen at random. By ignoring I mean these units are not considered during a particular forward or backward pass.

At each training stage individual nodes are either dropped out of the net with probability  $1-p$  or kept with probability  $p$  so that a reduced network is left; incoming and outgoing edges to a dropped-out node are also removed.



(a) Standard Neural Network




(b) Network after Dropout

## Q4. What is Forward Propagation?

**Answer:**

Input  $X$  provides the information that then propagates to hidden units at each layer and then finally produce the output  $y$ . The architecture of network entails determining its depth width and the activation functions used on each layer. **Depth** is the number of the hidden layers. **Width** is the number of units/nodes on each hidden layer since we don't control neither input layer nor output layer dimensions. There are quite a few set of activation functions such as *Rectified Linear Unit*, *Sigmoid*, *Hyperbolic tangent*, etc. Research has proven that deeper networks outperform networks with more hidden units. Therefore, it's always better and won't hurt to train a deeper network.



## Q5. What is Text Mining?

**Answer:**

**Text mining:** It is also referred as *text data mining* roughly equivalent to *text analytics* is the process of deriving high-quality information from text. High-quality information is typically derived through the devising of patterns and trends through means such as statistical pattern learning. Text mining usually involves the process of structuring the input text usually parsing along with the addition of some derived linguistic features and the removal of others and subsequent insertion into a database deriving patterns within the structured data and finally evaluation and interpretation of the output. 'High quality' in text mining usually refers to some combination of relevance, novelty, and interest. Typical text mining tasks include text categorization, text clustering, concept/entity extraction, production of granular taxonomies, sentiment analysis, document summarization, and entity relation modeling, i.e., learning relations between named entities.

### Sources of Data




### Q6. What is Information Extraction?

Answer:

**Information extraction IE** : It is the task of automatically extracting structured information from the unstructured and/or semi-structured machine-readable documents. In most of the cases this activity concerns processing human language texts using natural language processing NLP

Information extraction depends on named entity recognition NE a sub-tool used to find targeted information to extract NE recognizes entities first as one of several categories such as location LOC persons PE or organizations O G Once the information category is recognized an information extraction utility extracts the named entity s related information and constructs a machine-readable document from it which algorithms can further process to extract meaning IE finds meaning by way of other subtasks including co-reference resolution relationship extraction language and vocabulary analysis and sometimes audio extraction



## Q7. What is Text Generation?


**Answer:**

**Text Generation:** It is a type of the Language Modelling problem **Language Modelling** is the core problem for several of natural language processing tasks such as speech to text conversational system and the text summarization. The trained language model learns the likelihood of occurrence of the word based on the previous sequence of words used in the text. Language models can be operated at the character level n-gram level sentence level or even paragraph level.

A language model is at the core of many NLP tasks and is simply a probability distribution over a sequence of words:

$$p(w_1, \dots, w_n)$$

It can also be used to estimate the conditional probability of the next word in a sequence:



## Q8. What is Text Summarization?

### Answer:

We all interact with the applications which uses the text summarization. Many of the applications are for the platform which publishes articles on the daily news, entertainment, sports. With our busy schedule, we like to read the summary of those articles before we decide to jump in for reading entire article. Reading a summary helps us to identify the interest area, gives a brief context of the story.

Text summarization is a subdomain of Natural Language Processing (NLP) that deals with extracting summaries from huge chunks of texts. There are two main types of techniques used for text summarization: NLP-based techniques and deep learning-based techniques.

**Text summarization:** It refers to the technique of shortening long pieces of text. The intention is to create the coherent and fluent summary having only the main points outlined in the document.

### How text summarization works:

The two types of summarization abstractive and the extractive summarization

- 1 **Abstractive Summarization:** It selects words based on the semantic understanding; even those words did not appear in the source documents. It aims at producing important material in the new way. They interpret and examine the text using advanced natural language techniques to generate the new shorter text that conveys the most critical information from the original text.


It can be correlated in the way human reads the text article or blog post and then summarizes in their word.

*Input document → understand context → semantics → create own summary.*

- 2 **Extractive Summarization:** It attempts to summarize articles by selecting the subset of words that retain the most important points.

This approach weights the most important part of sentences and uses the same to form the summary. Different algorithms and the techniques are used to define the weights for the sentences and further rank them based on importance and similarity among each other.

*Input document → sentences similarity → weight sentences → select sentences with higher rank.*



## Q9. What is Topic Modelling?

### Answer:

Topic Modelling is the task of using unsupervised learning to extract the main topics represented as a set of words that occur in a collection of documents

Topic modeling in the context of Natural Language Processing is described as a method of uncovering hidden structure in a collection of texts

### Dimensionality reduction:


Topic modeling is the form of dimensionality reduction rather than representing the text  $T$  in its feature space as  $\text{Word}_i$ : count Word $_i$  in  $T$  for Word $_i$  in  $V$  we can represent the text in its topic space as  $\text{Topic}_i$ : weight Topic $_i$  in  $T$  for Topic $_i$  in Topics

### Unsupervised learning:

Topic modeling can be compared to the clustering As in the case of clustering the number of topics like the number of clusters is the hyperparameter By doing the topic modeling we build clusters of words rather than clusters of texts A text is thus a mixture of all the topics each having a certain weight

### A Form of Tagging

If document classification is assigning a single category to a text topic modeling is assigning multiple tags to a text A human expert can label the resulting topics with human-readable labels and use different heuristics to convert the weighted topics to a set of tags




## Q10.What is Hidden Markov Models?

**Answer:**

Hidden Markov Models HMMs are the class of probabilistic graphical model that allow us to predict the sequence of unknown hidden variables from the set of observed variables. The simple example of an HMM is predicting the weather hidden variable based on the type of clothes that someone wears observed. An HMM can be viewed as the Bayes Net unrolled through time with observations made at the sequence of time steps being used to predict the best sequence of the hidden states.


The below diagram from Wikipedia shows that HMM and its transitions. The scenario is the room that contains urns  $X_1$ ,  $X_2$  and  $X_3$  each of which contains a known mix of balls each ball labeled  $y_1$ ,  $y_2$ ,  $y_3$  and  $y_4$ . The sequence of four balls is randomly drawn. In this particular case the user observes the sequence of balls  $y_1$ ,  $y_2$ ,  $y_3$  and  $y_4$  and is attempting to discern the hidden state which is the right sequence of three urns that these four balls were pulled from.



### Why Hidden Markov Model?

The reason it is called the Hidden Markov Model is because we are constructing an inference model based on the assumptions of a Markov process. The Markov process assumption is simply that the future is independent of the past given the present.

To make this point clear let us consider the scenario below where the weather the hidden variable can be hot, mild or cold and the observed variables are the type of clothing worn. The arrows represent transitions from a hidden state to another hidden state or from a hidden state to an observed variable.



iNeuron

**DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview  
Preparation)  
# Day-16**

## Q1.What is Statistics Learning?

## Answer:

**Statistical learning:** It is the framework for understanding data based on the statistics which can be classified as the supervised or unsupervised. Supervised statistical learning involves building the statistical model for predicting or estimating an output based on one or more inputs while in unsupervised statistical learning there are inputs but no supervising output but we can learn relationships and structure from such data.

$$Y = f(X) + \epsilon \quad X = [X_1 \ X_2] \quad X_p$$

$f$ : It is an unknown function &  $\epsilon$  is random error reducible & irreducible


## Prediction & Inference:

In the situations where the set of inputs  $X$  are readily available but the output  $Y$  is not known we often treat  $f$  as the black box not concerned with the exact form of  $f$  as long as it yields the accurate predictions for  $Y$ . This is the *prediction*.

There are situations where we are interested in understanding the way that  $Y$  is affected as  $X$  changes. In this type of situation we wish to estimate  $f$  but our goal is not necessarily to make predictions for  $Y$ . Here we are more interested in understanding the relationship between the  $X$  and  $Y$ . Now  $f$  cannot be treated as the black box because we need to know its exact form. This is *inference*.

# Machine Learning

Statistics




## Parametric & Non-parametric methods

**Parametric statistics:** This statistical tests based on underlying the assumptions about data s distribution In other words It is based on the parameters of the normal curve Because parametric statistics are based on the normal curve data must meet certain assumptions or parametric statistics cannot be calculated Before running any parametric statistics you should always be sure to test the assumptions for the tests that you are planning to run

$$fX = \beta_0 + \beta_1 X_1 + \beta_2 X_2 + \dots + \beta_p X_p$$

As by the name nonparametric statistics are not based on parameters of the normal curve Therefore if our data violate the assumptions of a usual parametric and nonparametric statistics might better define the data try running the nonparametric equivalent of the parametric test We should also consider using nonparametric equivalent tests when we have limited sample sizes e.g.  $n < 30$  Though the nonparametric statistical tests have more flexibility than do parametric statistical tests nonparametric tests are not as robust; therefore most statisticians recommend that when appropriate parametric statistics are preferred



### Prediction Accuracy and Model Interpretability:

Out of many methods that we use for the statistical learning some are less flexible and more restrictive When inference is the goal then there are clear advantages of using the simple and relatively inflexible statistical learning methods When we are only interested in the prediction we use flexible models available




## Q2. What is ANOVA?

**Answer:**

**ANOVA:** it stands for Analysis of Variance is an extremely important tool for analysis of data both One Way and Two Way ANOVA is used It is a statistical method to compare the population means of two or more groups by analyzing variance The variance would differ only when the means are significantly different

ANOVA test is the way to find out if survey or experiment results are significant In other words It helps us to figure out if we need to reject the null hypothesis or accept the alternate hypothesis We are testing groups to see if there s a difference between them Examples of when we might want to test different groups:


- The group of psychiatric patients are trying three different therapies: counseling medication and biofeedback We want to see if one therapy is better than the others
- The manufacturer has two different processes to make light bulbs if they want to know which one is better
- Students from the different colleges take the same exam We want to see if one college outperforms the other



**Types of ANOVA:**

- One-way ANOVA
- Two-way ANOVA

One-way ANOVA is the hypothesis test in which only one categorical variable or the single factor is taken into consideration With the help of F-distribution it enables us to compare means of three or more samples The Null hypothesis  $H_0$  is the equity in all population means while an Alternative hypothesis is the difference in at least one mean



There are two-ways ANOVA examines the effect of two independent factors on a dependent variable. It also studies the inter-relationship between independent variables influencing the values of the dependent variable if any.



### Q3. What is ANCOVA?

**Answer:**

**Analysis of Covariance ANCOVA :** It is the inclusion of the continuous variable in addition to the variables of interest the dependent and independent variable as means for the control. Because the ANCOVA is the extension of the ANOVA the researcher can still assess main effects and the interactions to answer their research hypotheses. The difference between ANCOVA and an ANOVA is that an ANCOVA model includes the covariate that is correlated with dependent variable and means on dependent variable are adjusted due to effects the covariate has on it. Covariates can also

be used in many ANOVA based designs: such as between-subjects within-subjects repeated measures mixed between and within designs etc Thus this technique answers the question

In simple terms The difference between ANOVA and the ANCOVA is the letter "C" which stands for 'covariance' Like ANOVA "Analysis of Covariance" ANCOVA has the single continuous response variable Unlike ANOVA ANCOVA compares the response variable by both the factor and a continuous independent variable example comparing test score by both 'level of education' and the 'number of hours spent in studying' The terms for the continuous independent variable IV used in the ANCOVA is "covariate"

Example of ANCOVA

## ANCOVA EXAMPLE

### Independent Variables

(Factor)

Level of Education  
(High School, College Degree,  
or Graduate Degree)


(Covariate)

Number of Hours  
Spent Studying

### Dependent Variable

(Response)

Test Score




## Q4. What is MANOVA?

Answer:


**MANOVA multivariate analysis of variance** : It is a type of multivariate analysis used to analyze data that involves more than one dependent variable at a time. MANOVA allows us to test hypotheses regarding the effect of one or more independent variables on two or more dependent variables.

The obvious difference between ANOVA and the "Multivariate Analysis of Variance" MANOVA is the M which stands for multivariate. In basic terms MANOVA is an ANOVA with two or more continuous response variables. Like ANOVA, MANOVA has both the one-way flavor and a two-way flavor. The number of factor variables involved distinguish the one-way MANOVA from a two-way MANOVA.

### ONE-WAY MANOVA EXAMPLE



### TWO-WAY MANOVA EXAMPLE



When comparing the two or more continuous response variables by the single factor a one-way MANOVA is appropriate e.g. comparing test score and annual income together by level of

education. The two-way MANOVA also entails two or more continuous response variables but compares them by at least two factors e.g. comparing test score and annual income together by both level of education and zodiac sign.

## Q5. What is MANCOVA?

**Answer:**

**Multivariate analysis of covariance MANCOVA :** It is a statistical technique that is the extension of analysis of covariance ANCOVA. It is the multivariate analysis of variance MANOVA with a covariate(s). In MANCOVA we assess for statistical differences on multiple continuous dependent variables by an independent grouping variable while controlling for a third variable called the covariate; multiple covariates can be used depending on the sample size. Covariates are added so that it can reduce error terms and so that the analysis eliminates the covariates effect on the relationship between the independent grouping variable and the continuous dependent variables.

ANOVA and ANCOVA the main difference between the MANOVA and MANCOVA is the C which again stands for the covariance. Both the MANOVA and MANCOVA feature two or more response variables but the key difference between the two is the nature of the IVs. While the MANOVA can include only factors an analysis evolves from MANOVA to MANCOVA when one or more covariates are added to the mix.

## MANCOVA EXAMPLE

### Independent Variables

(Factor)  
Level of Education  
(High School, College Degree, or Graduate Degree)

(Covariate)  
Number of Hours Spent Studying

### Dependent Variables

(Response)  
Test Score

(Response)  
Annual Income




## Q6. Explain the differences between KNN classifier and KNN regression methods.

**Answer:**

They are quite similar. Given a value for  $x_0$  and a prediction point  $x_0$ , KNN regression first identifies the  $K$  training observations that are closest to  $x_0$ , represented by  $N_0$ . It then estimates  $f(x_0)$  using the average of all the training responses in  $N_0$ . In other words,

$$\hat{f}(x_0) = \frac{1}{K} \sum_{x_i \in N_0} y_i$$

So the main difference is the fact that for the classifier approach, the algorithm assumes the outcome as the class of more presence, and on the regression approach, the response is the average value of the nearest neighbors.



## Q7. What is t-test?

**Answer:**

To understand T-Test Distribution, consider the situation you want to compare the performance of two workers of your company by checking the average sales done by each of them or to compare the performance of a worker by comparing the average sales done by him with the standard value. In such situations of daily life, t-distribution is applicable.

A t-test is the type of inferential statistic used to determine if there is a significant difference between the means of two groups which may be related in certain features. It is mostly used when the data sets like the data set recorded as the outcome from flipping a coin 100 times would follow a normal distribution and may have unknown variances. A t-test is used as a hypothesis testing tool which allows testing of an assumption applicable to a population.


**Understand t-test with Example:** Let's say you have a cold and you try a naturopathic remedy. Your cold lasts a couple of days. The next time when you have a cold, you buy an over-the-counter pharmaceutical and the cold lasts a week. You survey your friends and they all tell you that their colds were of a shorter duration, an average of 3 days, when they took the homeopathic remedy. What you want to know is, are these results repeatable? A t-test can tell you by comparing the means of the two groups and letting you know the probability of those results happening by chance.

Type	T-statistic	Degrees of freedom
One-sample t-test	$t = \frac{\bar{x} - \mu_0}{s/\sqrt{n}}$	$df = n - 1$
Paired t-test	$t = \frac{\bar{X}_D - \mu_0}{s_D/\sqrt{n}}$ .	$df = n - 1$

## OVERVIEW OF T-TESTS

### T-test

**Used to compare two samples to determine if they came from the same population.**



## Q8. What is Z-test?

**Answer:**

**Z-test:** It is a statistical test used to determine whether the two population means are different when the variances are known and the sample size is large. The test statistic is assumed to have the normal distribution and nuisance parameters such as standard deviation should be known for an accurate z-test to be performed.

Another definition of Z-test: A Z-test is a type of hypothesis test. Hypothesis testing is just the way for you to figure out if results from a test are valid or repeatable. Example: if someone said they had found the new drug that cures cancer, you would want to be sure it was probably true. Hypothesis test will tell you if it's probably true or probably not true. A Z-test is used when your data is approximately normally distributed.

### Z-Tests Working :

Tests that can be conducted as the z-tests include one-sample location test, a two-sample location test, a paired difference test, and a maximum likelihood estimate. Z-tests are related to t-tests, but t-tests are best performed when an experiment has the small sample size. Also, T-tests assumes the standard deviation is unknown, while z-tests assumes that it is known. If the standard deviation of the population is unknown, then the assumption of the sample variance equaling the population variance is made.

### When we can run the Z-test :

Different types of tests are used in the statistics, i.e., f test, chi-square test, t-test. You would use a Z test if:

- Your sample size is greater than 30. Otherwise, use a t-test.
- Data points should be independent from each other. Some other words, one data point is not related or doesn't affect another data point.
- Your data should be normally distributed. However, for large sample sizes over 30, this doesn't always matter.
- Your data should be randomly selected from a population where each item has an equal chance of being selected.
- Sample sizes should be equal if at all possible.

### Z-TEST

► Formula to find the value of Z (z-test) is:

$$Z = \frac{\bar{x} - \mu_0}{\sigma / \sqrt{n}}$$

- $\bar{x}$  = mean of sample
- $\mu_0$  = mean of population
- $\sigma$  = standard deviation of population
- $n$  = no. of observations

## Q9. What is Chi-Square test?


[Answer:](#)

**Chi-square  $\chi^2$  statistic:** It is a test that measures how expectations compare to actual observed data or model results. The data used in calculating a chi-square statistic must be random, raw, mutually exclusive, drawn from independent variables, and drawn from a large enough sample. For example, the results of tossing a coin 100 times meet these criteria.

Chi-square test is intended to test how it is that an observed distribution is due to chance. It is also called the "**goodness of fit**" statistic because it measures how well the observed distribution of the data fits with the distribution that is expected if the variables are independent.

Chi-square test is designed to analyze the **categorical** data. That means that the data has been counted and divided into categories. It will not work with parametric or continuous data such as height in inches. For example, if you want to test whether attending class influences how students perform on an exam using test scores from 0-100, as data would not be appropriate for a Chi-square test. However, arranging students into the categories "Pass" and "Fail" would. Additionally, the data in a Chi-square grid should not be in the form of percentages or anything other than frequency count data.

$$\chi^2_c = \sum \frac{(O_i - E_i)^2}{E_i}$$



## Q10. What is correlation and the covariance in the statistics?

**Answer:**

The Covariance and Correlation are two mathematical concepts; these two approaches are widely used in the statistics. Both Correlation and the Covariance establish the relationship and also measures the dependency between the two random variables. The work is similar between these two in the mathematical terms they are different from each other.

**Correlation:** It is the statistical technique that can show whether and how strongly pairs of variables are related. For example height and weight are related; taller people tend to be heavier than shorter people. The relationship isn't perfect. People of the same height vary in weight and you can easily think of two people you know where the shorter one is heavier than the taller one. Nonetheless, the average weight of people 5'5" is less than the average weight of people 5'6" and their average weight is less than that of people 5'7" etc. Correlation can tell you just how much of the variation in peoples' weights is related to their heights.

### Correlation Formula

 
$$\rho_{xy} = \frac{\text{Cov}(r_x, r_y)}{\sigma_x \sigma_y}$$
 

**Covariance:** It measures the directional relationship between the returns on two assets. The positive covariance means that asset returns move together while a negative covariance means they move inversely. Covariance is calculated by analyzing at-return surprises standard deviations from the expected return or by multiplying the correlation between the two variables by the standard deviation of each variable.



### Covariance Formula

**For Population**

$$\text{Cov}(x,y) = \frac{\sum (x_i - \bar{x}) * (y_i - \bar{y})}{N}$$

**For Sample**

$$\text{Cov}(x,y) = \frac{\sum (x_i - \bar{x}) * (y_i - \bar{y})}{(N - 1)}$$

# **DATA SCIENCE INTERVIEW PREPARATION**

**(30 Days of Interview**



**# DAY 17**

## Q1. What is ERM (Empirical Risk Minimization)?

**Answer:**

**Empirical risk minimization (ERM):** It is a principle in statistical learning theory which defines a family of learning algorithms and is used to give theoretical bounds on their performance. The idea is that we don't know exactly how well an algorithm will work in practice (the true "risk") because we don't know the true distribution of data that the algorithm will work on but as an alternative we can measure its performance on a known set of training data.


We assumed that our samples come from this distribution and use our dataset as an approximation. If we compute the loss using the data points in our dataset it's called empirical risk. It is empirical and not true because we are using a dataset that's a subset of the whole population.

When our learning model is built we have to pick a function that minimizes the empirical risk that is the delta between predicted output and actual output for data points in the dataset. This process of finding this function is called empirical risk minimization (ERM). We want to minimize the true risk. We don't have information that allows us to achieve that so we hope that this empirical risk will almost be the same as the true empirical risk.

**Let's get a better understanding by Example**

We would want to build a model that can differentiate between a male and a female based on specific features. If we select 100 random people where women are really short and men are really tall then the model might incorrectly assume that height is the differentiating feature. For building a truly accurate model we have to gather all the women and men in the world to extract differentiating features. Unfortunately that is not possible! So we select a small number of people and hope that this sample is representative of the whole population.

$$\begin{aligned}
 R_{emp}[f] &= \sum_{x \in X} \sum_{j=1}^2 c(x, y_j, f(x)) p_{emp}(y_j, x) \\
 &= \frac{1}{n} \sum_{i=1}^n c(x_i, y_i, f(x_i))
 \end{aligned}$$






## Q2. What is PAC (Probably Approximately Correct)?

**Answer:**

PAC: In computational learning theory probably approximately correct (PAC) learning is a framework for mathematical analysis of machine learning.

The learner receives samples and must have to pick a generalization function (called the *hypothesis*) from a specific class of possible functions. Our goal is that with high probability the selected function will have low generalization error. The learner must be able to learn the concept given any arbitrary approximation ratio probability of success or distribution of the samples.

Hypothesis class is PAC(Probably Approximately Correct) learnable if there exists a function  $m \geq m(H)$  and algorithm that for any labeling function  $f$  distribution  $D$  over the domain of inputs  $\Delta$  and  $\epsilon$  that with  $m \geq m(H)$  produces a hypothesis  $h$  like that with probability  $1 - \delta$  it returns a **true error** lower than  $\epsilon$ . Labeling function is nothing other than saying that we have a specific function  $f$  that labels the data in the domain.




### Q3. What is ELMo?

**Answer:**

ELMo is a novel way to represent words in vectors or embeddings. These word embeddings help achieve state-of-the-art (SOTA) results in several NLP tasks:

Task	Previous SOTA	ELMo + Baseline
SQuAD	SAN	84.4
SNLI	Chen et al (2017)	88.6
SRL	Ho et al (2017)	81.7
Coref	Lee et al (2017)	67.2
NER	Peters et al (2017)	91.93 +/- 0.19
Sentiment (5-class)	McCann et al (2017)	53.7
		54.7 +/- 0.5

It is a deep contextualized word representation that models both complex characteristics of word use (e.g. syntax and semantics) and how these uses vary across linguistic contexts. These word vectors are learned functions of internal states of a deep biLM(bidirectional language model) which is pre-trained on large text corpus. They could be easily added to existing models and significantly improve state of the art across a broad range of challenging NLP problems including question answering, textual entailment and sentiment analysis.



## Q4. What is Pragmatic Analysis in NLP?

**Answer:**

**Pragmatic Analysis(PA):** It deals with outside word knowledge which means understanding i.e external to documents and queries. PA that focuses on what was described is reinterpreted by what it actually meant deriving the various aspects of language that require real-world knowledge.

It deals with overall communicative and social content and its effect on interpretation. It means abstracting the meaningful use of language in situations. In this analysis the main focus always on what was said in reinterpreted on what is intended.

It helps users to discover this intended effect by applying a set of rules that characterize cooperative dialogues.

E.g. "close the window?" should be interpreted as a request instead of an order.


Personal	Organizational devices (Calls/Vocatives)
Request	Questions
Action	Answers/Responses
Permission	Repetition/Imitation
Offering/showing	Elicited identification
Descriptions	Routines
Statements (Internal reports)	Exclamations
Acknowledgements	Unclassified
Performatives	Double coded

## Q5. What is Syntactic Parsing?

**Answer:**

**Syntactic Parsing or Dependency Parsing:** It is a task of recognizing a sentence and assigning a syntactic structure to it. Most Widely we used syntactic structure is the parse tree which can be generated using some parsing algorithms. These parse trees are useful in various applications like grammar checking or more importantly it plays a critical role in the semantic analysis stage. For example to answer the question *Who is the point guard for the LA Laker in the next game ?* we need to figure out its subject objects attributes to help us figure out that the user wants the point guard of the LA Lakers specifically for the next game.

Example:



## Q6. What is ULMFiT?

**Answer:**


Transfer Learning in **NLP(Natural language Processing)** is an area that had not been explored with great success. But in May 2017 Jeremy Howard and Sebastian Raschka came up with the paper **Universal Language Model Fine-tuning for Text Classification(ULMFiT)** which explores the benefits of using a pre-trained model on text classification. It proposes **ULMFiT(Universal Language Model Fine-tuning for Text Classification)** a transfer learning method that could be applied to any task in NLP. In this method outperforms the state-of-the-art on six text classification tasks.

ULMFiT uses a **regular LSTM** which is the state-of-the-art language model architecture (**AWD-LSTM**). The LSTM network has three layers. Single architecture is used throughout for pre-training as well as for fine-tuning.

ULMFiT achieves the state-of-the-art result using novel techniques like:


- Discriminative fine-tuning
- Slanted triangular learning rates
- Gradual unfreezing

### Discriminative Fine-Tuning



Different layers of a neural network capture different types of information so they should be fine-tuned to varying extents. Instead of using the same learning rates for all layers of the model discriminative fine-tuning allows us to tune each layer with different learning rates.

### Slanted triangular learning



The model should quickly converge to a suitable region of the parameter space in the beginning of training and then later refine its parameters. Using a constant learning rate throughout training is not the best way to achieve this behaviour. Instead Slanted Triangular Learning  $\square$ ates (STL $\square$ ) linearly increases the learning rate at first and then linearly decays it.

### Gradual Unfreezing

Gradual unfreezing is the concept of unfreezing the layers gradually which avoids the catastrophic loss of knowledge possessed by the model. It first unfreezes the top layer and fine-tunes all the unfrozen layers for 1 epoch. It then unfreezes the next lower frozen layer and repeats until all the layers have been fine-tuned until convergence at the last iteration.

## Q7. What is BERT?


**Answer:**

**BE $\square$ T (Bidirectional Encoder  $\square$ epresentations from Transformers)** is an open-sourced NLP pre-training model developed by researchers at Google in 201 $\square$ . A direct descendant to GPT (Generalized Language Models) BE $\square$ T has outperformed several models in NLP and provided top results in  $\square$ uestion Answering Natural Language Inference (MNLI) and other frameworks.

What makes it s unique from the rest of the model is that it is the first deeply bidirectional unsupervised language representation pre-trained using only a plain text corpus. Since it s open-sourced anyone with machine learning knowledge can easily build an NLP model without the need for sourcing massive datasets for training the model thus saving time energy knowledge and resources.

## How does it work?

Traditional context-free models (like word2vec or GloVe) generate a single word embedding representation for each word in the vocabulary which means the word **right** would have the same context-free representation in **I m sure I m right** and **Take a right turn**. However BERT would represent based on both previous and next context making it bidirectional. While the concept of bidirectional was around for a long time BERT was first on its kind to successfully pre-train bidirectional in a deep neural network.




## Q8.What is XLNet?

Answer:


- XLNet is a BERT-like model instead of a totally different one. But it is an auspicious and potential one. In one word **XLNet is a generalized autoregressive pretraining method.**

**Autoregressive (A) language model:** It is a kind of model that uses the context word to predict the next word. But here the context word is constrained to two directions either forward or backwards.



The advantages of A language model are good at generative Natural Language Processing (NLP) tasks. Because when generating context usually is the forward direction. A language model naturally works well on such NLP tasks.

But Autoregressive language model has some disadvantages and it only can use forward context or backward context which means it can't use forward and backward context at the same time.



*The conceptual difference between BERT and XLNet. Transparent words are masked out so the model cannot rely on them. XLNet learns to predict the words in an arbitrary order but in an autoregressive, sequential manner (not necessarily left-to-right). BERT predicts all masked words simultaneously.*

## Q9. What is the transformer?

[Answer:](#)

**Transformer:** It is a deep machine learning model introduced in 2017 used primarily in the field of natural language processing (NLP). Like recurrent neural networks (RNN) It is designed to handle ordered sequences of data such as natural language for various tasks like machine translation and text summarization. However Unlike recurrent neural networks (RNN) Transformers do not require that the sequence be processed in the order. So if the data in question is a natural language the Transformer does not need to process the beginning of a sentence before it processes the end. Due to this feature the Transformer allows for much more parallelization than RNNs during training.

Transformers are developed to solve the problem of sequence transduction current neural networks. It means any task that transforms an input sequence to an output sequence. This includes speech recognition text-to-speech transformation etc.

For models to perform a sequence transduction it is necessary to have some sort of memory. example let us say that we are translating the following sentence to another language (French):

The Transformers is a Japanese band. That band was formed in 1960 during the height of the Japanese music history.

In the above example the word the band in the second sentence refers to the band The Transformers introduced in the first sentence. When you read about the band in the second sentence you know that it is referencing to the The Transformers band. That may be important for translation.

For translating other sentences like that a model needs to figure out these sort of dependencies and connections. Recurrent Neural Networks (RNNs) and Convolutional Neural Networks (CNNs) have been used to deal with this problem because of their properties.




Figure 1: The Transformer - model architecture.


## Q10. What is Text summarization?

**Answer:**

**Text summarization:** It is the process of shortening a text document to create a summary of the significant points of the original document.

**Types of Text Summarization Methods :**

Text summarization methods can be classified into different types.




Example:

Source Text: Peter and Elizabeth took a taxi to attend the night party in the city.

While in the party, Elizabeth collapsed and was rushed to the hospital.

Summary: Elizabeth was hospitalized after attending a party with Peter.



**DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview  
Preparation)  
# Day-18**

## Q1. What is Levenshtein Algorithm?

**Answer:**

Levenshtein distance is a string metric for measuring the difference between two sequences. The Levenshtein distance between two words is the minimum number of single-character edits (i.e. insertions, deletions or substitutions) required to change one word into the other.

Mathematically the Levenshtein distance between the two strings  $a$  and  $b$  (of length  $|a|$  and  $|b|$  respectively) is given by the formula  $\text{lev}_a b(|a| |b|)$  where :

$$\text{lev}_{a,b}(i,j) = \begin{cases} \max(i,j) & \text{if } \min(i,j) = 0, \\ \min \begin{cases} \text{lev}_{a,b}(i-1, j) + 1 \\ \text{lev}_{a,b}(i, j-1) + 1 \\ \text{lev}_{a,b}(i-1, j-1) + 1_{(a_i \neq b_j)} \end{cases} & \text{otherwise.} \end{cases}$$

Where  $1_{(a_i \neq b_j)}$ : This is the indicator function equal to zero when  $a_i \neq b_j$  and equal to 1 otherwise and  $\text{lev}_a b(i, j)$  is the distance between the first  $i$  characters of  $a$  and the first  $j$  characters of  $b$ .

**Example:**

The Levenshtein distance between "HONDA" and "HYUNDAI" is 3 since the following three edits change one into the other and there is no way to do it with fewer than three edits:

insertion
substitution
deletion

H		O	N	D	A	
H	Y	U	N	D	A	I

H	O		N	D	A	
H	Y	U	N	D	A	I

## Q2. What is Soundex?

Answer:

Soundex attempts to find similar names or homophones using phonetic notation. The program retains letters according to detailed equations to match individual titles for purposes of ample volume research.

**Soundex phonetic algorithm:** Its indexes strings depend on their English pronunciation. The algorithm is used to describe homophones words that are pronounced the same but spelt differently.

Suppose we have the following sourceDF.

```
+----+----+
|word1|word2|
+----+----+
|  to|  two|
|brake|break|
| here| hear|
| tree| free|
+----+----+
```

Let's run below code and see how the soundex algorithm encodes the above words.

```
val actualDF = sourceDF.withColumn(
  "w1_soundex",
  soundex(col("word1")))
  .withColumn(
  "w2_soundex",
  soundex(col("word2")))
)

actualDF.show()
```

```
+----+----+----+----+
|word1|word2|w1_soundex|w2_soundex|
+----+----+----+----+
|  to|  two|      T000|      T000|
|brake|break|      B620|      B620|
| here| hear|      H600|      H600|
| tree| free|      T600|      F600|
+----+----+----+----+
```

Let's summarize the above results:


- "two" and "to" both are encoded as T000
- "break" and "brake" both are encoded as B620
- "hear" and "here" both are encoded as H600
- "free" is encoded as F600 and "tree" is encoded as T600: Encodings are similar but word is different

The Soundex algorithm was often used to compare first names that were spelt differently.

### Q3. What is Constituency parse?

[Answer:](#)

A constituency parse tree breaks a text into sub-phrases. Non-terminals in the tree are types of phrases the terminals are the words in the sentence and the edges are unlabeled. For a simple sentence "John sees Bill" a constituency parse would be:



Above approaches convert the parse tree into a sequence following a depth-first traversal to be able to apply sequence-to-sequence models to it. The linearized version of the above parse tree looks as follows: (S (N) (VP V N)).

### Q4. What is LDA(Latent Dirichlet Allocation)?

[Answer:](#)

LDA: It is used to classify text in the document to a specific topic. LDA builds a topic per document model and words per topic model modelled as Dirichlet distributions.

- Each document is modeled as a distribution of topics and each topic is modelled as multinomial distribution of words.
- LDA assumes that every chunk of text we feed into it will contain words that are somehow related. Therefore choosing the right corpus of data is crucial.

- It also assumes documents are produced from a mixture of topics. Those topics then generate words based on their probability distribution.


The Bayesian version of PLSA is LDA. It uses Dirichlet priors for the word-topic and document-topic distributions lending itself to better generalization.

### What LDA give us?

It is a probabilistic method. For every document the results give us a mixture of topics that make up the document. To be precise we can get probability distribution over the k topics for every document. Every word in the document is attributed to the particular topic with probability given by distribution.

These topics themselves were defined as probability distributions over vocabulary. Our results are two sets of probability distributions:

- The collection of distributions of topics for each document
- The collection of distributions of words for each topic.



## Q5.What is LSA?

Answer:

**Latent Semantic Analysis (LSA):** It is a theory and the method for extract and represents the contextual usage meaning of words by statistical computation applied to large corpus of texts.


It is an information retrieval technique which analyzes and identifies the pattern in an unstructured collection of text and relationship between them.

Latent Semantic Analysis itself is an unsupervised way of uncovering synonyms in a collection of documents.

**Why LSA(Latent Semantic Analysis)?**

LSA is a technique for creating vector representation of the document. Having a vector representation of the document gives us a way to compare documents for their similarity by calculating the distance between vectors. In turn means we can do handy things such as classify documents to find out which of a set knows topics they most likely reside to.

Classification implies we have some known topics that we want to group documents into and that you have some labelled training data. If you're going to identify natural groupings of the documents without any labelled data you can use clustering




## Q6. What is PLSA?

**Answer:**

PLSA stands for Probabilistic Latent Semantic Analysis uses a probabilistic method instead of SVD to tackle problem. The main idea is to find the probabilistic model with latent topics that we can *generate* data we observe in our document term matrix. Specifically we want a model  $P(D|W)$  such that for any document  $d$  and word  $w$   $P(d|w)$  corresponds to that entry in document-term matrix.

Each document is found in the mixture of topics and each topic consists of the collection of words. PLSA adds the probabilistic spin to these assumptions:

- Given document  $d$  topic  $z$  is available in that document with the probability  $P(z|d)$
- Given the topic  $z$  word  $w$  is drawn from  $z$  with probability  $P(w|z)$



In the above case  $P(D)$ ,  $P(Z|D)$  and  $P(W|Z)$  are the parameters of our models.  $P(D)$  can be determined directly from corpus.  $P(Z|D)$  and the  $P(W|Z)$  are modelled as multinomial distributions and can be trained using the expectation-maximisation algorithm (EM).

## Q7. What is LDA2Vec?

**Answer:**

It is inspired by LDA word2vec model is expanded to simultaneously learn word document topic and paragraph topic vectors.

Lda2vec is obtained by modifying the skip-gram word2vec variant. In the original skip-gram method the model is trained to predict context words based on a pivot word. In lda2vec the pivot word vector and a document vector are added to obtain a context vector. This context vector is then used to predict context words.

At the document level we know how to represent the text as mixtures of topics. At the word-level we typically used something like word2vec to obtain vector representations. It is an extension of word2vec and LDA that jointly learns word document and topic vectors.

### How does it work?


It correctly builds on top of the skip-gram model of word2vec to generate word vectors. Neural net that learns word embedding by trying to use input word to predict enclosing context words.

With Lda2vec other than using the word vector directly to predict context words you leverage a context vector to make the predictions. Context vector is created as the sum of two other vectors: the word vector and the document vector.

The same skip-gram word2vec model generates the word vector. The document vector is most impressive. It is a really weighted combination of two other components:

- the document weight vector representing the weights of each topic in a document
- Topic matrix represents each topic and its corresponding vector embedding.

Together a document vector and word vector generate context vectors for each word in a document. Lda2vec power lies in the fact that it not only learns word embeddings for words; it simultaneously learns topic representations and document representations as well.



## Q8. What is Expectation-Maximization Algorithm(EM)?

### Answer:

The Expectation-Maximization Algorithm in short EM algorithm is an approach for maximum likelihood estimation in the presence of latent variables.


This algorithm is an iterative approach that cycles between two modes. The first mode attempts to predict the missing or latent variables called the estimation-step or E-step. The second mode attempts to optimise the parameters of the model to explain the data best called the maximization-step or M-step.

- **E-Step.** Estimate the missing variables in the dataset.
- **M-Step.** Maximize the parameters of the model in the presence of the data.

The EM algorithm can be applied quite widely although it is perhaps most well known in machine learning for use in unsupervised learning problems such as density estimation and clustering.

For detail explanation of EM let us first consider this example. Say that we are in a school and interested to learn the height distribution of female and male students in the school. The most sensible thing to do as we probably would agree with me is to randomly take a sample of N students of both genders collect their height information and estimate the mean and standard deviation for male and female separately by way of maximum likelihood method.

Now say that you are not able to know the gender of student while we collect their height information and so there are two things you have to guess/estimate: (1) whether the individual sample of height information belongs to a male or a female and (2) the parameters ( ) for each gender which is now unobservable. This is tricky because only with the knowledge of who belongs to which group can we make reasonable estimates of the group parameters separately. Similarly only if we know the parameters that define the groups can we assign a subject properly. How do you break out of this infinite loop? Well EM algorithm just says to start with initial random guesses.



## Q9.What is Text classification in NLP?


**Answer:**

Text classification is also known as text tagging or text categorization is a process of categorizing text into organized groups. By using NLP text classification can automatically analyze text and then assign a set of pre-defined tags or categories based on content.

Unstructured text is everywhere on the internet such as emails chat conversations websites and the social media but it's hard to extract value from given data unless it's organized in a certain way. Doing so used to be a difficult and expensive process since it required spending time and resources to manually sort the data or creating handcrafted rules that are difficult to maintain. Text classifiers with NLP have proven to be a great alternative to structure textual data in a fast cost-effective and scalable way.

Text classification is becoming an increasingly important part of businesses as it allows us to get insights from data and automate business processes quickly. Some of the most common examples and the use cases for automatic text classification include the following:

- **Sentiment Analysis:** It is the process of understanding if a given text is talking positively or negatively about a given subject (e.g. for brand monitoring purposes).
- **Topic Detection:** In this the task of identifying the theme or topic of a piece of text (e.g. know if a product review is about Ease of Use Customer Support or Pricing when analysing customer feedback).
- **Language Detection:** the procedure of detecting the language of a given text (e.g. know if an incoming support ticket is written in English or Spanish for automatically routing tickets to the appropriate team).



## Q10. What is Word Sense Disambiguation (WSD)?

**Answer:**

WSD (Word Sense Disambiguation) is a solution to the ambiguity which arises due to different meaning of words in a different context.

In natural language processing **word sense disambiguation** (WSD) is the problem of determining which "sense" (meaning) of a word is activated by the use of the word in a particular context a process which appears to be mostly unconscious in people. WSD is the natural classification problem: Given a word and its possible senses as defined by the dictionary classify an occurrence of the word in the context into one or more of its sense classes. The features of the context (such as the neighbouring words) provide the evidence for classification.

For example consider these two below sentences.


The **bank** will not be accepting the cash on Saturdays.

The river overflowed the **bank**.

The word **bank** in the given sentence refers to commercial (finance) banks while in the second sentence it refers to a riverbank. The uncertainty that arises due to this is tough for the machine to detect and resolve. Detection of change is the first issue and fixing it and displaying the correct output is the second issue.

### Word Sense disambiguation

I need new batteries for my **mouse**.



**DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview  
Preparation)**

**# DAY 19**

## Q1. What is LSI(Latent Semantic Indexing)?

**Answer:**


**Latent Semantic Indexing (LSI):** It is an indexing and retrieval method that uses a mathematical technique called S $\square$ D(Singular value decomposition) to find patterns in relationships between terms and concepts contained in an unstructured collection of text. It is based on the principle that words that are used in the same contexts tend to have similar meanings.


For example Tiger and Woods are associated with men instead of an animal and a Wood Parris and Hilton are associated with the singer

**Example:**

If you use LSI to index a collection of articles and the words fan and regulator appear together frequently enough the search algorithm would notice that the two terms are semantically close. A search for fan will therefore return a set of items containing that phrase but also items that contain just the word regulator. It doesn't understand word distance but by examining a sufficient number of documents it only knows the two terms are interrelated. It then uses that information to provide an expanded set of results with better recall than an understandable keyword search.

The diagram below describes the effect between LSI and keyword searches. W stands for a document.





## Q2. What is Named Entity Recognition? And tell some use cases of NER?

### Answer:

**Named-entity recognition (NER):** It is also known as entity extraction and entity identification is a subtask of information extraction that explores to locate and classify atomic elements in text into predefined categories like the names of persons organizations places expressions of times quantities monetary values percentages and more

In each text document particular terms represent specific entities that are more informative and have a different context. These entities are called named entities which more accurately refer to conditions that represent real-world objects like people places organizations or institutions and so on which are often expressed by proper names. The naive approach could be to find these by having a look at the noun phrases in text documents. It also is known as entity chunking extraction which is a popular technique used in information extraction to analyze and segment the named entities and categorize or classify them under various predefined classes

### Named Entity Recognition use-case

- **Classifying content for news providers-**

NER can automatically scan entire articles and reveal which are the significant people organizations and places discussed in them. Assigning the relevant tags for each item helps in automatically categorizing the articles in defined hierarchies and enable smooth content discovery

- **Customer Support:**

Let's say we are handling the customer support department of an electronics store with multiple branches worldwide; we go through a number of mentions in our customers' feedback. Such as this for instance

Now if we pass it through the Named Entity Recognition API it pulls out the entities Bangalore (location) and Fitbit (Product). This can be then used to categorize the complaint and assign it to the relevant department within the organization that should be handling this.



Figure 1: An example of NER application on an example text

### Q3. What is perplexity?

**Answer:**

Perplexity: It is a measurement of how well a probability model predicts a sample. In the context of NLP, perplexity (Confusion) is one way to evaluate language models.

The term perplexity has three closely related meanings. It is a measure of how easy a probability distribution is to predict. It is a measure of how variable a prediction model is. And it is a measure of prediction error. The third meaning of perplexity is calculated slightly differently, but all three have the same fundamental idea.

Dan Jurafsky

## Perplexity

The best language model is one that best predicts an unseen test set

- Gives the highest  $P(\text{sentence})$

Perplexity is the inverse probability of the test set, normalized by the number of words:

$$PP(W) = P(w_1 w_2 \dots w_N)^{\frac{1}{N}}$$

$$= \sqrt[N]{\frac{1}{P(w_1 w_2 \dots w_N)}}$$

Chain rule:

$$PP(W) = \sqrt[N]{\prod_{i=1}^N \frac{1}{P(w_i | w_1 \dots w_{i-1})}}$$

For bigrams:

$$PP(W) = \sqrt[N]{\prod_{i=1}^N \frac{1}{P(w_i | w_{i-1})}}$$

Minimizing perplexity is the same as maximizing probability

## Q4. What is the language model?

### Answer:

Language Modelling (LM): It is one of the essential parts of modern NLP. There are many sorts of applications for Language Modelling like Machine Translation, Spell Correction, Speech Recognition, Summarization, Question Answering, Sentiment analysis, etc. Each of those tasks requires the use of the language model. The language model is needed to represent the text to a form understandable from the machine point of view.

The statistical language model is a probability distribution over a series of words. Given such a series say of length  $m$ , it assigns a probability to the whole series.

It provides context to distinguish between phrases and words that sound similar. For example, in American English, the phrases "wreck a nice beach" and "recognize speech" sound alike but mean different things.

Data sparsity is a significant problem in building language models. Most possible word sequences are not noticed in training. One solution is to make the inference that the probability of a word only depends on the previous  $n$  words. This is called as an  $n$ -gram model or unigram model when  $n = 1$ . The unigram model is also known as the bag of words model.

### How does this Language Model help in NLP Tasks?

The probabilities restoration by a language model is most useful to compare the likelihood that different sentences are "good sentences". This was useful in many practical tasks, for example:

**Spell checking:** You observe a word that is not identified as a known word as part of a sentence. Using the edit distance algorithm, we find the closest known words to the unknown words. These are the candidate corrections. For example, we observe the word "wurd" in the context of the sentence "I like to write this wurd". The candidate corrections are ["word", "weird", "wind"]. How can we select among these candidates the most likely correction for the suspected error "weird"? □

**Automatic Speech Recognition:** we receive as input a string of phonemes; a first model predicts for sub-sequences of the stream of phonemes candidate words; the language model helps in ranking the most likely sequence of words compatible with the candidate words produced by the acoustic model.

**Machine Translation:** each word from the source language is mapped to multiple candidate words in the target language; the language model in the target language can rank the most likely sequence of candidate target words.


## Q5. What is Word Embedding?

**Answer:**

A word embedding is a learned representation for text where words that have the same meaning have a similar observation

It is basically a form of word representation that bridges the human understanding of language to that of a machine. Word embeddings divide representations of text in an n-dimensional space. These are essential for solving most NLP problems.

And the other point worth considering is how we obtain word embeddings as no two sets of word embeddings are similar. Word embeddings aren't random; they're developed by training the neural network. A recent powerful word embedding usage comes from Google named Word2Vec which is trained by predicting several words that appear next to other words in a language. For example, the word "cat" the neural network would predict the words like "kitten" and "feline". This intuition of words comes out "near" each other allows us to place them in vector space.



## Q6. Do you have an idea about fastText?

**Answer:**


**fastText:** It is another word embedding method that is an extension of the word2vec model. Alternatively learning vectors for words directly. It represents each word as an n-gram of characters. So for example take the word artificial with n=3 the fastText representation of this word is <math>\langle a, r, t, i, f, i, c, i, a \rangle</math> where the angular brackets indicate the beginning and end of the word.

This helps to capture the meaning of shorter words and grant the embeddings to understand prefixes and suffixes. Once the word has been showed using character skip-grams a n-gram model is trained to learn the embeddings. This model is acknowledged to be a bag of words model with a sliding

window over a word because no internal structure of the word is taken into account. As long as the characters are within this window, the order of the n-grams doesn't matter.

fastText works well with rare words. So even if a word wasn't seen during training, it can be broken down into n-grams to get its embeddings.

Word2vec and Glove both fail to provide any vector representation for words that are not in the model dictionary. This is a huge advantage of this method.



## Q7. What is GloVe?

## Answer:

GloVe (global vectors) is for word representation. GloVe is an unsupervised learning algorithm developed by Stanford for achieving word embeddings by aggregating a global word-word co-occurrence matrix from a corpus. The resulting embeddings show interesting linear substructures of the word in vector space.

The GloVe model produces a vector space with meaningful substructure as evidenced by its performance of 80% on a new word analogy task. It also outperforms related models on similarity tasks and named entity recognition.

## How GloVe find meaning in statistics?

Produces a vector space with meaningful substructure as evidenced by its performance of 80% on a new word analogy task. It also outperforms related models on similarity tasks and named entity recognition.


GloVe aims to achieve two goals:

- (1) Create word vectors that **capture meaning in vector space**
- (2) Takes advantage of **global count statistics** instead of only local information

Unlike word2vec which learns by streaming sentences GloVe determines based on a **co-occurrence matrix** and trains word vectors so their differences predict **co-occurrence ratios**

GloVe weights the loss based on word frequency

Somewhat surprisingly word2vec and GloVe turn out to be remarkably similar despite starting off from entirely different starting points



## Q8. Explain Gensim?

**Answer:**


Gensim: It is billed as a Natural Language Processing package that does Topic Modeling for Humans But its practically much more than that

If you are unfamiliar with topic modeling it is a technique to extract the underlying topics from large volumes of text Gensim provides algorithms like LDA and LSI (which we already seen in previous interview questions) and the necessary sophistication to built high-quality topic models

It is an excellent library package for processing texts working with word vector models (such as FastText Word2Vec etc) and for building the topic models. Another significant advantage with gensim is: it lets us handle large text files without having to load the entire file in memory.


We can also tell as It is an open-source library for unsupervised topic modeling and natural language processing using modern statistical machine learning.

Gensim is implemented in Python and Cython. Gensim is designed to handle extensive text collections using data streaming and incremental online algorithms which differentiates it from most other machine learning software packages that target only in-memory processing.



## Q9. What is Encoder-Decoder Architecture?

**Answer:**



The encoder-decoder architecture consists of two main parts :

- **Encoder:**

Encoder simply takes the input data and trains on it then it passes the final state of its recurrent layer as an initial state to the first recurrent layer of the decoder part

```
Encoder input : English sentences
```

```
Encoder initial state : It depends on the initializer we use
```


- **Decoder :**


The decoder takes the final state of encoder s final recurrent layer and uses it as an initial state to its initial recurrent layer the input of the decoder is sequences that we want to get French sentences

```
Decoder input : French sentences
```

```
Decoder initial state : The last state of encoder's last recurrent layer
```

Some more example for better understanding:






## Q10. What is Context2Vec?

### Answer:

Assume a case where you have a sentence like I can't find May. Word May maybe refers to a month's name or a person's name. You use the words surround it (context) to help yourself to determine the best suitable option. Actually this problem refers to the Word Sense Disambiguation task on which you investigate the actual semantics of the word based on several semantic and linguistic techniques. The Context2Vec idea is taken from the original CBOW Word2Vec model but instead of relying on averaging the embedding of the words it relies on a much more complex parametric model that is based on one layer of Bi-LSTM. Figure 1 shows the architecture of the CBOW model.

**Figure 1**



Context2vec applied the same concept of windowing but instead of using a simple average function it uses 3 stages to learn complex parametric networks

- A Bi-LSTM layer that takes left-to-right and right-to-left representations
- A feedforward network that takes the concatenated hidden representation and produces a hidden representation through learning the network parameters
- Finally we apply the objective function to the network output




Figure 1: *word2vec* and *context2vec* architectures.

We used the *Word2vec* negative sampling idea to get better performance while calculating the loss value

The following are some samples of the closest words to a given context

Sentential Context	Closest target words
This [ ] is due	item, fact-sheet, offer, pack, card
This [ ] is due not just to mere luck	offer, suggestion, announcement, item, prize
This [ ] is due not just to mere luck, but to outstanding work and dedication	award, prize, turnabout, offer, gift
[ ] is due not just to mere luck, but to outstanding work and dedication	it, success, this, victory, prize-money

Table 1: Closest target words to various sentential contexts, illustrating *context2vec*'s sensitivity to long range dependencies, and both sides of the target word.

# **DATA SCIENCE INTERVIEW PREPARATION**

**(30 Days of Interview  
Preparation)**

**# DAY 20**

## Q1. Do you have any idea about Event2Mind in NLP?


An**sw**er**?**

Yes it is based on NLP research paper to understand the common-sense inference from sentences

### **Event2Mind: Common-sense Inference on Events, Intents, and Reactions**

The study of Commonsense Reasoning in NLP deals with teaching computers how to gain and employ common sense knowledge NLP systems require common sense to adapt quickly and understand humans as we talk to each other in a natural environment

This paper proposes a new task to teach systems commonsense reasoning: given an event described in a short event phrase (e.g PersonX drinks coffee in the morning) the researchers teach a system to reason about the likely intents (PersonX wants to stay awake) and reactions (PersonX feels alert) of the event's participants



Understanding a narrative requires common-sense reasoning about the mental states of people in relation to events. For example if Robert is dragging his feet at work pragmatic implications about Robert's *intent* are that Robert wants to avoid doing things (Above Fig) You can also infer that Robert's *emotional reaction* might be feeling bored or lazy Furthermore while not explicitly mentioned you can assume that people other than Robert are affected by the situation and these people are likely to feel impatient or frustrated

---

This type of pragmatic inference can likely be useful for a wide range of NLP applications that require accurate anticipation of people's intents and emotional reactions even when they are not expressly mentioned. For example an ideal dialogue system should react in empathetic ways by reasoning about the human user's mental state based on the events the user has experienced without the user explicitly stating how they are feeling. Furthermore advertisement systems on social media should be able to reason about the emotional reactions of people after events such as mass shootings and remove ads for guns which might increase social distress. Also the pragmatic inference is a necessary step toward automatic narrative understanding and generation. However this type of commonsense social reasoning goes far beyond the widely studied entailment tasks and thus falls outside the scope of existing benchmarks.

## Q2. What is SWAG in NLP?

### Answer:

SWAG stands for **Situations with Adversarial Generations** is a dataset consisting of 113k multiple-choice questions about a rich spectrum of grounded situations

Swag: A Large Scale Adversarial Dataset for Grounded Commonsense Inference

According to NLP research paper on SWAG is Given a partial description like he opened the hood of the car humans can reason about the situation and anticipate what might come next ( then he examined the engine ) In this paper you introduce the task of grounded commonsense inference unifying natural language inference(NLI) and common-sense reasoning

We present SWAG a dataset with 113k multiple-choice questions about the rich spectrum of grounded positions To address recurring challenges of annotation artifacts and human biases found in many existing datasets we propose AF(Adversarial Filtering) a novel procedure that constructs a de-biased dataset by iteratively training an ensemble of stylistic classifiers and using them to filter the data To account for the aggressive adversarial filtering we use state-of-the-art language models to oversample a diverse set of potential counterfactuals massively Empirical results present that while humans can solve the resulting inference problems with high accuracy (88%) various competitive models make an effort on our task We provide a comprehensive analysis that indicates significant opportunities for future research

When we read a tale we bring to it a large body of implied knowledge about the physical world For instance given the context on stage a man takes a seat at the piano we can easily infer what the situation might look like: a man is giving a piano performance with a crowd watching him We can furthermore infer his likely next action: he will most likely set his fingers on the piano key and start playing

This type of natural language inference(NLI) requires common-sense reasoning substantially broadening the scope of prior work that focused primarily on linguistic entailment Whereas the dominant entailment paradigm asks if 2 natural language sentences (the premise and the hypothesis ) describe the same set of possible worlds here we focus on whether a (multiple-choice) ending represents a possible (*future*) world that can a from the situation described in the premise even when it is not strictly entailed Making such inference necessitates a rich understanding of everyday physical conditions including object affordances and frame semantics

On stage, a woman takes a seat  at the piano. She

- a) sits on a bench as her sister plays with the doll.
- b) smiles with someone as the music plays.
- c) is in the crowd, watching the dancers.
- d) nervously sets her fingers on the keys.**



A girl is going across a set of monkey bars. She

- a) jumps up across the monkey bars.
- b) struggles onto the monkey bars to grab her head.
- c) gets to the end and stands on a wooden plank.**
- d) jumps up and does a back flip.

The woman is now blow drying the dog. The dog

- a) is placed in the kennel next to a woman's feet.**
- b) washes her face with the shampoo.
- c) walks into frame and walks towards the dog.
- d) tried to cut her face, so she is trying to do something very close to her face.

Table 1: Examples from Swag; the correct answer is **bolded**. Adversarial Filtering ensures that stylistic models find all options equally appealing.

### Q3. What is the Pix2Pix network?

**Answer:**

Pix2Pix network: It is a Conditional GANs (cGAN) that learn the mapping from an input image to output an image





Image-To-Image Translation is the process for translating one representation of the image into another representation

The image-to-image translation is another example of a task that GANs (Generative Adversarial Networks) are ideally suited for. These are tasks in which it is nearly impossible to hard-code a loss function. Studies on GANs are concerned with novel image synthesis translating from a random vector  $z$  into an image. Image-to-Image translation converts one image to another like the edges of the bag below to the photo image. Another exciting example of this is shown below:



#### In Pix2Pix Dual Objective Function with an Adversarial and L1 Loss

A naive way to do Image-to-Image translation would be to discard the adversarial framework altogether. A source image would just be passed through a parametric function and the difference in the resulting image and the ground truth output would be used to update the weights of the network. However, designing this loss function with standard distance measures such as L1 and L2 will fail to capture many of the essential distinctive characteristics between these images. However,

---

authors do find some value to the L1 loss function as a weighted sidekick to the adversarial loss function

The Conditional-Adversarial Loss (Generator versus Discriminator) is very popularly formatted as follows:

$$\begin{aligned}\mathcal{L}_{cGAN}(G, D) = & \mathbb{E}_{x,y}[\log D(x, y)] + \\ & \mathbb{E}_{x,z}[\log(1 - D(x, G(x, z)))]\end{aligned}$$

The L1 loss function previously mentioned is shown below:

$$\mathcal{L}_{L1}(G) = \mathbb{E}_{x,y,z}[\|y - G(x, z)\|_1].$$

Combining these functions results in:

$$G^* = \arg \min_G \max_D \mathcal{L}_{cGAN}(G, D) + \lambda \mathcal{L}_{L1}(G).$$


In the experiments the authors report that they found the most success with the lambda parameter equal to 100

## Q4. Explain UNet Architecture?

### Answer:


□ **-Net architecture:** It is built upon the Fully Convolutional Network and modified in a way that it yields better segmentation in medical imaging. Compared to FCN-8 the two main differences are (a) U-net is symmetric and (b) the skip connections between the downsampling path and upsampling path apply a concatenation operator instead of a sum. These skip connections intend to provide local information to the global information while upsampling. Because of its symmetry the network has a large number of feature maps in the upsampling path which allows transferring information. By comparison the underlying FCN architecture only had the *number of classes* feature maps in its upsampling way.

## How does it work?



The UNet architecture looks like a U which justifies its name. This UNet architecture consists of 3 sections: The contraction, the bottleneck and the expansion section. The contraction section is made of many contraction blocks. Each block takes an input that applies two 3X3 convolution layers followed by a 2X2 max pooling. The number of features or kernel maps after each block doubles so that UNet architecture can learn complex structures. Bottommost layer mediates between the contraction layer and the expansion layer. It uses two 3X3 CNN layers followed by 2X2 up convolution layer.

But the heart of this architecture lies in the expansion section. Similar to the contraction layer, it also has several expansion blocks. Each block passes input to two 3X3 CNN layers followed by a 2X2 upsampling layer. After each block, the number of feature maps used by the convolutional layer get halved to maintain symmetry. However, every time input is also appended by feature maps of the corresponding contraction layer. This action would ensure that features that are learned while contracting the image will be used to reconstruct it. The number of expansion blocks is as same as the number of contraction blocks. After that, the resultant mapping passes through another 3X3 CNN layer with the number of feature maps equal to the number of segments desired.



## Q5. What is pair2vec?

### Answer:


This paper pre trains *word pair representations* by maximizing pointwise mutual information of pairs of words with their context. This encourages a model to learn more meaningful representations of word pairs than with more general objectives like modeling. The pre-trained representations are useful in tasks like SQuAD and MultiNLI that require cross-sentence inference. You can expect to see more pretraining tasks that capture properties particularly suited to specific downstream tasks and are complementary to more general-purpose tasks like language modeling.

Reasoning about implied relationships between pairs of words is crucial for cross sentences inference problems like question answering (QA) and natural language inference (NLI). In NLI e.g. given a premise such as *golf is prohibitively expensive* inferring that the hypothesis *golf is a cheap pastime* is a contradiction requires one to know that *expensive* and *cheap* are antonyms. Recent work has shown that current models which rely heavily on unsupervised single-word embeddings struggle to grasp such relationships. In this pair2vec paper we show that they can be learned with word pair2vec(pair vector) which are trained unsupervised at a huge scale and which significantly improve performance when added to existing cross-sentence attention mechanisms.

X	Y	Contexts
		with X and Y baths
hot	cold	too X or too Y neither X nor Y in X, Y
Portland	Oregon	the X metropolitan area in Y X International Airport in Y
crop	wheat	food X are maize, Y, etc dry X, such as Y, more X circles appeared in Y fields
Android	Google	X OS comes with Y play the X team at Y X is developed by Y

Table 1: Example word pairs (italicized) and their contexts (Wikipedia).

Unlike single word representations which are typically trained by modeling the co-occurrence of a target word  $x$  with its context  $c$  our word-pair representations are learned by modeling the three-way co-occurrence between two words ( $x$   $y$ ) and the context  $c$  that ties them together as illustrated in above Table While similar training signal has been used to learn models for ontology construction and knowledge base completion this paper shows for the first time that considerable scale learning of pairwise embeddings can be used to improve the performance of neural cross-sentence inference models directly



## Q6. What is Meta-Learning?

**Answer:**


Meta-learning: It is an exciting area of research that tackles the problem of learning to learn. The goal is to design models that can learn new skills or fastly to adapt to new environments with minimum training examples. Not only does this dramatically speed up and improve the design of ML(Machine Learning) pipelines or neural architectures but it also allows us to replace hand-engineered algorithms with novel approaches learned in a data-driven way.

The goal of meta-learning is to train the model on a variety of learning tasks such that it can solve new learning tasks with only a small number of training samples. It tends to focus on finding **model agnostic** solutions whereas multi-task learning remains deeply tied to model architecture.

Thus meta-level AI algorithms make AI systems:

- Learn faster
- Generalizable to many tasks
- Adaptable to environmental changes like in Reinforcement Learning

One can solve any problem with a single model but meta-learning should not be confused with one-shot learning.



## Q7. What is ALiPy(Active Learning in Python)?


**Answer:**

Supervised ML methods usually require a large set of labeled examples for model training. However in many real applications there are ample unlabeled data but limited labeled data; and acquisition of labels is costly. Active learning (AL) reduces labeling costs by iteratively selecting the most valuable data to query their labels from the annotator.

Active learning is the leading approach to learning with limited labeled data. It tries to reduce human efforts on data annotation by actively querying the most prominent examples.

ALiPy is a Python toolbox for active learning(AL) which is suitable for various users. On the one hand the entire process of active learning has been well implemented. Users can efficiently perform experiments by many lines of codes to finish the entire process from data pre-processes to

result in visualization More than 20 commonly used active learning(AL) methods have been implemented in the toolbox providing users many choices




## Q8.What is the Lingvo model?

### Answer:

Lingvo: It is a Tensorflow framework offering a complete solution for collaborative deep learning research with a particular focus towards sequence-to-sequence models. These models are composed of modular building blocks that are flexible and easily extensible and experiment configurations are centralized and highly customizable. Distributed training and quantized inference are supported directly within a framework and it contains existing implementations of an ample number of utilities helper functions and newest research ideas. This model has been used in collaboration by dozens of researchers in more than 20 papers over the last two years.

#### ▫ why does this Lingvo research matter▫

The process of establishing a new deep learning(DL) system is quite complicated. It involves exploring an ample space of design choices involving training data, data processing logic, the size and type of model components, the optimization procedures and the path to deployment. This complexity requires the framework that quickly facilitates the production of new combinations and the modifications from existing documents and experiments and shares these new results. It is a workspace ready to be used by deep learning researchers or developers. Nguyen Says: We have researchers working on state-of-the-art(SOTA) products and research algorithms basing their research off of the same codebase. This ensures that code is battle-tested. Our collective experience is encoded in means of good defaults and primitives that we have found useful over these tasks.



## Q9. What is Dropout Neural Networks?

**Answer:**



The term **dropout** refers to dropping out units (both hidden and visible) in a neural network

At each training stage individual nodes are either dropped out of the net with probability  $1-p$  or kept with probability  $p$  so that a reduced network is left; incoming and outgoing edges to a dropped-out node are also removed

□ **Why do we need dropout?**

The answer to these questions is to prevent over-fitting

A fully connected layer occupies most of the parameters and hence neurons develop co-dependency amongst each other during training which curbs the individual power of each neuron leading to over-fitting of training data




## Q10. What is GAN?

### Answer:

**A generative adversarial network (GAN):** It is a class of machine learning systems invented by Ian Goodfellow and his colleagues in 2014. Two neural networks are contesting with each other in a game (in the idea of game theory often but not always in the form of a zero-sum game). Given a training set this technique learns to generate new data with the same statistics as the training set. E.g. a GAN trained on photographs can produce original pictures that look at least superficially authentic to human observers having many realistic characteristics. Though initially proposed as a form of a generative model for unsupervised learning GANs have also proven useful for semi-supervised learning [2] fully supervised learning and reinforcement learning.

Example of GAN



- Given an image of a face the network can construct an image that represents how that person could look when they are old

Generative Adversarial Networks takes up a game-theoretic approach unlike a conventional neural network. The network learns to generate from a training distribution through a 2-player game. The two entities are Generator and Discriminator. These two adversaries are in constant battle throughout the training process.

**DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview  
Preparation)**

**# Day21**


## Q1. Explain Grad-CAM architecture?

### Answer:

According to the research paper We propose a technique for making Convolutional Neural Network CNN -based models more transparent by visualizing input regions that are important for predictions producing *visual explanations* Our approach is called Gradient-weighted Class Activation Mapping Grad-CAM which uses class-specific gradient information to localize the crucial regions These localizations are combined with the existing pixel-space visualizations to create a new high-resolution and class-discriminative display called the Guided Grad-CAM These methods help better to understand CNN-based models including image captioning and the apparent question answering VQA models We evaluate our visual explanations by measuring the ability to discriminate between the classes and to inspire trust in humans and their correlation with the occlusion maps Grad-CAM provides a new way to understand the CNN-based models

A technique for making CNN Convolutional Neural Network -based models more transparent by visualizing the regions of input that are important for predictions from these models or visual explanations


Guided Grad-CAM for "Cat"



Guided Grad-CAM for "Dog"



This visualization is both high-resolution when the class of interest is tiger cat it identifies crucial tiger cat features like stripes pointy ears and eyes and class-discriminative it shows the tiger cat but not the boxer dog




## Q2.Explain squeeze-net architecture?

### Answer:


Nowadays technology is at its peak Self-driving cars and IoT is going to be household talks in the next few years to come Therefore everything is controlled remotely say e g in self-driving cars we will need our system to communicate with the servers regularly So accordingly if we have a model that has a small size then we can quickly deploy it in the cloud So that's why we needed an architecture that is less in size and also achieves the same level of accuracy that other architecture achieves

### It's Architecture

- **Replace 3x3 filters with 1x1 filter-** We plan to use the maximum number of  $x$  filters as using a  $X$  filter rather than a 3X3 filter can reduce the number of parameters by  $9X$  We may think that replacing 3X3 filters with  $X$  filters may perform badly as it has less information to work on But this is not a case Typically 3X3 filter may capture the spatial information of pixels close to each other while the  $X$  filter zeros in on pixel and captures features amongst its channels
- **Decrease number of input channels to 3x3 filters-** to maintain a small total number of parameters in a CNN and it is crucial not only to decrease the number of 3x3 filters but also to decrease the number of input channels to 3x3 filters We reduce the number of input channels to 3x3 filters using *squeeze layers*. The author of this paper has used a term called the *fire module*, in which there is a squeeze layer and an expanded layer In the squeeze layer we are using  $X$  filters while in the expanded layer we are using a combo of 3X3 filters and  $X$  filters The author is trying to limit the number of inputs to 3X3 filters to reduce the number of parameters in the layer



- **Downsample late in a network so that convolution layers have a large activation map-** Having got an intuition about contracting the sheer number of parameters we are working with how the model is getting most out of the remaining set of parameters The author in this paper has downsampled the feature map in later layers and this increases the accuracy But this is an excellent contrast to networks like VGG where a large feature map is taken and then it gets smaller as network approach towards the end This different approach is too interesting and they cite the [paper by K He and H Sun](#) that similarly applies delayed downsampling that leads to higher classification accuracy  
This architecture consists of the fire module which enables it to bring down the number of parameters




And other thing that surprises me is the lack of fully connected layers or dense layers at the end which one will see in a typical CNN architecture The dense layers in the end learn all the relationships between the high-level features and the classes it is trying to identify The fully connected layers are designed to learn that noses and ears make up a face and wheels and lights indicate cars However in this architecture that extra learning step seems to be embedded within the transformations between various fire modules

CNN architecture	Compression Approach	Data Type	Original → Compressed Model Size	Reduction in Model Size vs. AlexNet	Top-1 ImageNet Accuracy	Top-5 ImageNet Accuracy
AlexNet	None (baseline)	32 bit	240MB	1x	57.2%	80.3%
AlexNet	SVD [3]	32 bit	240MB → 48MB	5x	56.0%	79.4%
AlexNet	Network Pruning [11]	32 bit	240MB → 27MB	9x	57.2%	80.3%
AlexNet	Deep Compression [10]	5-8 bit	240MB → 6.9MB	35x	57.2%	80.3%
SqueezeNet (ours)	None	32 bit	4.8MB	50x	57.5%	80.3%
SqueezeNet (ours)	Deep Compression	8 bit	4.8MB → 0.66MB	363x	57.5%	80.3%
SqueezeNet (ours)	Deep Compression	6 bit	4.8MB → 0.47MB	510x	57.5%	80.3%


The squeeze-net can accomplish an accuracy nearly equal to AlexNet with 50X less number of parameters. The most impressive part is that if we apply Deep compression to the already smaller model then it can reduce the size of the squeeze-net model to 500x times that of AlexNet.

### Q3.ZFNet architecture

**Answer:**



The architecture of the network is an optimized version of the last year's winner - AlexNet. The authors spent some time to find out the bottlenecks of AlexNet and removing them achieving superior performance.



a : First layer ZFNET features without feature scale clipping b : the First layer features from AlexNet Note that there are lot of dead features - ones where the network did not learn any patterns c : the First layer features for ZFNet Note that there are only a few dead features d : Second layer features from AlexNet The grid-like patterns are so-called aliasing artifacts They appear when

receptive fields of convolutional neurons overlap and neighboring neurons learn similar structures  
e : 2nd layer features for ZFNet Note that there are no aliasing artifacts Source: original paper

In particular they reduced the filter size in the <sup>st</sup> convolutional layer from  $5 \times 5$  to  $7 \times 7$  which resulted in fewer dead features learned in the first layer see the image below for an example of that A dead feature is a situation where a convolutional kernel fails to learn any significant representation Visually it looks like a monotonic single-color image where all the values are close to each other

In addition to changing the filter size the authors of FZNet have doubled the number of filters in all convolutional layers and the number of neurons in the fully connected layers as compared to the AlexNet In the AlexNet there were 48- 28- 92- 92- 28-2048-2048 kernels-neurons and in the ZFNet all these doubled to 96-256-384-384-256-4096-4096 This modification allowed the network to increase the complexity of internal representations and as a result decrease the error rate from 5.4% for last year's winner to 4.8% to become the winner in 2013

## Q4. What is NAS (Neural Architecture Search)?

### Answer:

Developing the neural network models often requires significant architecture engineering We can sometimes get by with transfer learning but if we want the best possible performance it's usually best to design your network This requires specialized skills and is challenging in general; we may not even know the limits of the current state-of-the-art SOTA techniques Its a lot of trial and error and experimentation itself is time-consuming and expensive

This is the NAS Neural Architecture Search comes in NAS Neural Architecture Search is an algorithm that searches for the best neural network architecture Most of the algorithms work in the following way Start off by defining the set of building blocks that can be used for our network E.g. the state-of-the-art SOTA NASNet paper proposes these commonly used blocks for an image recognition network-

- identity
- $1 \times 7$  then  $7 \times 1$  convolution
- $3 \times 3$  average pooling
- $5 \times 5$  max pooling
- $1 \times 1$  convolution
- $3 \times 3$  depthwise-separable conv
- $7 \times 7$  depthwise-separable conv
- $1 \times 3$  then  $3 \times 1$  convolution
- $3 \times 3$  dilated convolution
- $3 \times 3$  max pooling
- $7 \times 7$  max pooling
- $3 \times 3$  convolution
- $5 \times 5$  depthwise-separable conv

In the NAS algorithm the controller Recurrent Neural Network RNN samples the building blocks putting them together to create some end to end architecture Architecture generally combines the same style as state-of-the-art SOTA networks such as DenseNets or ResNets but uses a much different combination and the configuration of blocks

This new network architecture is then trained to convergence to obtain the least accuracy on the held-out validation set The resulting efficiencies are used to update the controller so that the controller will generate better architectures over time perhaps by selecting better blocks or making better connections The controller weights are updated with a policy gradient The whole end-to-end setup is shown below





Figure 1. Overview of Neural Architecture Search [71]. A controller RNN predicts architecture  $A$  from a search space with probability  $p$ . A child network with architecture  $A$  is trained to convergence achieving accuracy  $R$ . Scale the gradients of  $p$  by  $R$  to update the RNN controller.

It's a reasonably intuitive approach! In simple means: have an algorithm grab different blocks and put those blocks together to make the network Train and test out that network Based on our results adjust the blocks we used to make the network and how you put them together!

## Q5. What is SENets?

**Answer:**



SENet stands for Squeeze-and-Excitation Networks introduces a building block for CNNs that improves channel interdependencies at almost no computational cost They have used in the 2017 ImageNet competition and helped to improve the result from last year by 25% Besides this large performance boost they can be easily added to existing architectures The idea is this:

Let's add parameters to each channel of the convolutional block so that the network can adaptively adjust the weighting of each feature map

As simple as it may sound this is it So let's take a closer look at why this works so well

### Why it works too well?

CNNs uses its convolutional filters to extract hierarchical information from the images Lower layers find little pieces of context like high frequencies or edges while upper layers can detect faces text or other complex geometrical shapes They extract whatever is necessary to solve the task precisely


All of this works by fusing spatial and channel information of an image The different filters will first find the spatial features in each input channel before adding the information across all available output channels

All we need to understand for now is that the network weights each of its channels equally when creating output feature maps It is all about changing this by adding a content-aware mechanism to weight each channel adaptively In its too basic form this could mean adding a single parameter to each channel and giving it linear scalar how relevant each one is

However the authors push it a little further First they get the global understanding of each channel by squeezing feature maps to a single numeric value This results in the vector of size  $n$  where  $n$  is equal to the number of convolutional channels Afterward it is fed through a two-layer neural network which outputs a vector of the same size These  $n$  values can now be used as weights on the original features maps scaling each channel based on its importance

## Q6. Feature Pyramid Network (FPN)

**Answer:**



### The Bottom-Up Pathway

The bottom-up pathway is feedforward computation of backbone ConvNet. It is known as one pyramid level is for each stage. The output of last layer of each step will be used as the reference set of feature maps for enriching the top-down pathway by lateral connection.

### Top-Down Pathway and Lateral Connection

- The higher resolution features are upsampled spatially coarser but semantically stronger feature maps from higher pyramid levels. More particularly the spatial resolution is upsampled by a factor of 2 using nearest neighbor for simplicity.
- Each lateral connection adds feature maps of the same spatial size from the bottom-up pathway and top-down pathway.
- Specifically **the feature maps from the bottom-up pathway undergo  $1 \times 1$  convolutions to reduce channel dimensions.**
- And **feature maps from the bottom-up pathway and top-down pathway are merged by element-wise addition.**


### Prediction in FPN

- Finally **the  $3 \times 3$  convolution is appended on each merged map to generate a final feature map, which is to reduce the aliasing effect of upsampling.** This last set of feature maps is called  $\square P_2 \ P_3 \ P_4 \ P_5 \square$  corresponding to  $\square C_2 \ C_3 \ C_4 \ C_5 \square$  that are respectively of same spatial sizes
- Because all levels of pyramid use shared classifiers/regressors as in a traditional featured image pyramid feature dimension at output  $d$  is fixed with  $d = 256$ . Thus all extra convolutional layers have 256 channel outputs

## Q7. DeepID-Net( Def-Pooling Layer)


### Answer:

A new def-pooling deformable constrained pooling layer is used to model the deformation of the object parts with geometric constraints and penalties. That means except detecting the whole object directly it is also important to identify object parts which can then assist in detecting the whole object.



The steps in **black** color are the **old stuff** that existed in R-CNN. The stages in **red** color do not appear in R-CNN.

### Selective Search



- First color similarities, texture similarities, regions size and region filling are used as **non-object-based segmentation**. Therefore you obtain **many small segmented areas** as shown at the bottom left of the image above.
- Then the bottom-up approach is used that **small segmented areas are merged to form the larger segment areas**.
- Thus **about 2K regions, proposals (bounding box candidates) are generated**, as shown in the above image.

### 2. Box Rejection

R-CNN is used to reject bounding boxes that are most likely to be the background


### 3. Pre train Using Object-Level Annotations


	Pretrained on object-level annoation	Pretrained on image-level annotation
Image		
Visualized model		

Usually pretraining is on **image-level annotation**. It is **not good when an object is too small within the image** because the object should occupy a large area within the bounding box created by the selective search.

Thus **pretraining is on object-level annotation**. And the deep learning(DL) model can be any models such as ZFNet VGGNet and GoogLeNet

### 4. Def-Pooling Layer





$$b_c^{(x,y)} = \max_{\delta_x, \delta_y \in \{-R, \dots, R\}} \{ m_c^{\mathbf{z}_{\delta_x, \delta_y}} - \sum_{n=1}^N a_{c,n} d_{c,n}^{\delta_x, \delta_y} \}$$

where  $\mathbf{z}_{\delta_x, \delta_y} = (s_x \cdot x + \delta_x, s_y \cdot y + \delta_y)$ .

For the def-pooling path output from conv5 goes through the Conv layer then goes through the def-pooling layer and then has a max-pooling layer

In simple terms the summation of ac multiplied by dc n is the  $5 \times 5$  deformation penalty in the figure above The penalty of placing object part from assumed the central position

By training the DeepID-Net object parts of the object to be detected will give a high activation value after the def-pooling layer if they are closed to their anchor places And this output will connect to 200-class scores for improvement

## 5. Context Modeling

In object detection tasks in ILSVRC there are 200 classes And there is also the classification competition task in ILSVRC for classifying and localizing 1000-class objects The contents are more diverse compared with the object detection task Hence **1000-class scores, obtained by classification network, are used to refine 200-class scores.**

## 6. The Model Averaging-

**Multiple models are used** to increase the accuracy and **the results from all models are averaged** This technique has been used since AlexNet LeNet and so on

## 7. Bounding Box Regression


Bounding box regression is to **fine-tune the bounding box location** which has been used in R-CNN

## Q8. What is FractalNet Architecture?

**Answer:**

In 2015 after the invention of ResNet with numerous champion won there are plenty of researchers working on how to improve the ResNet such as Pre-Activation ResNet, RiR, RoR, Stochastic Depth and WRN. In this story conversely a non-residual-network approach FractalNet is shortly reviewed. When VGGNet is starting to degrade when it goes from 6 layers VGG-6 to 9 layers VGG-9, FractalNet can go up to 40 layers or even 80 layers.

### Architecture



In the above picture: A Simple Fractal Expansion on Left Recursively Stacking of Fractal Expansion as One Block in the Middle 5 Blocks Cascaded as FractalNet on the Right

For the base case  $f_C(z)$  is the convolutional layer:

$$f_1(z) = \text{conv}(z)$$

After that recursive fractals are:

$$f_{C+1}(z) = [(f_C \circ f_C)(z)] \oplus [\text{conv}(z)]$$

Where  $C$  is a number of columns as in the middle of the above figure. The number of the convolutional layers at the deepest path within the block will have  $2 \times C - 1$ . In this case  $C=4$  thereby a number of convolutional layers are  $2 \times 8 = 16$  layers.

For the **join layer** green the **element-wise mean** is computed. It is not concatenation or addition.


With five blocks  $B=5$  cascaded as FractalNet at the right of the figure then the number of convolutional layers at the most profound path within the whole network is  $B \times 2 \times C - 1$  i.e.  $5 \times 2 \times 4 = 40$  layers.

In between 2 blocks  $2 \times 2$  max pooling is done to reduce the size of feature maps. Batch Norm and ReLU are used after each convolution.

## Q9. What is the SSPNet architecture?

**Answer:**

SPPNet has introduced the new technique in CNN called **Spatial Pyramid Pooling (SPP)** at the transition of the convolutional layer and fully connected layer. This is a work from **Microsoft**.



Conventionally at the transformation of the Conv layer and FC layer there is one single pooling layer or even no pooling layer. In SPPNet it suggests having **multiple pooling layers with different scales**.

In the figure **3-level SPP** is used. Suppose conv5 layer has 256 feature maps. Then at the SPP layer

first each feature map is **pooled to become one value (which is grey)** Thus **256-d vector is formed**

- 2 Then each feature map is **pooled to have four values (which is green)** and form the **4×256-d vector**
- 3 Similarly each feature map is **pooled to have 16 values (in blue)** and form the **16×256-d vector**
- 4 The **above three vectors are concatenated to form a 1-d vector**
- 5 Finally this **1-d vector is going into FC layers** as usual

With SPP you don't need to crop the image to a fixed size like AlexNet before going into CNN **Any image sizes can be inputted.**


DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview Preparation)

# Day22

## Q1. Explain V-Net (Volumetric Convolution) Architecture with related to Biomedical Image Segmentation?

### Answer:


There were several medical data used in clinical practice consists of 3D volumes such as MRI volumes illustrate prostate while most approaches are only able to process 2D images A 3D image segmentation based on a volumetric fully convolutional neural network is proposed in this work



Slices from MRI volumes depicting prostate

Prostate segmentation nevertheless is the crucial task having clinical relevance both during diagnosis where the volume of the prostate needs to be assessed and during treatment planning where the estimate of the anatomical boundary needs to be accurate

### Architecture




- V-Net justifies by its name it is shown as V-shape The left part of the network consists of a compression path while on the right part decompresses signal until its original size is reached
- This is the same as U-Net but with some difference

## On left

- The left side of the network is divided into different stages that operate at various resolutions Each stage comprises one to 3 convolutional layers
- At each stage, a residual function is learned The input of each stage is used in convolutional layers and processed through non-linearities and added to the output of the last convolutional layer of that stage to enable learning a residual function This V-net architecture ensures convergence compared with non-residual learning networks such as U-Net
- The convolutions performed in each stage use volumetric kernels having the size of 3x3x3 voxels A voxel represents a value on a regular grid in 3D-space The term voxel is commonly used in 3D much 3D space just like voxelization in a point cloud
- Along the compression path the resolution is reduced by convolution with 2x2x2 voxels full kernels applied with stride 2 Thus the size of the resulting feature maps is halved with a similar purpose as pooling layers And number of feature channels doubles at each stage of the compression path of V-Net
- Replacing pooling operations with convolutional ones helps to have a smaller memory footprint during training because no switches mapping the output of pooling layers back to their inputs are needed for back-propagation
- Downsampling helps to increase the receptive field
- ReLU is used as a non-linearity activation function

## On right part

- The network extracts features and expands spatial support of the lower resolution feature maps to gather and assemble the necessary information to output a two-channel volumetric segmentation



- At each stage a **deconvolution** operation is employed to **increase the size of the inputs followed by one to three convolutional layers**, involving **half the number of kernels** applied in the previous layer
- **The residual function** is learned similar to left part of the network
- The 2 features maps computed by a **very last convolutional layer** having **1x1x1 kernel size** and producing **outputs of the same size as input volume**
- These two output feature maps are **the probabilistic segmentation of the foreground and background regions by applying soft-max voxelwise**

## Q2. Highway Networks- Gating Function to highway

### Answer:

It is found that difficulties are optimizing a very deep neural network. However it's still an open problem with why it is difficult to optimize a deep network. It is due to gradient vanishing problem. Inspired by LSTM Long Short-Term Memory authors thereby **make use of gating function to adaptively bypass or transform the signal so that the network can go deeper**. The deep network with more than 1000 layers can also be optimized.

### Plain Network

Before going into Highway Networks Let us start with plain network which consists of  $L$  layers where the  $l$ -th layer with omitting the symbol for the layer :


$$\mathbf{y} = H(\mathbf{x}, \mathbf{W}_H).$$

Where  $x$  is input  $WH$  is the weight  $H$  is the transform function followed by an activation function and  $y$  is the output. And for  $i$ -th unit:

$$y_i = H_i(\mathbf{x})$$

We compute the  $y_i$  and pass it to the next layer

### Highway Network



In a highway network 2 non-linear transforms  $T$  and  $H$  are introduced:

$$\mathbf{y} = H(\mathbf{x}, \mathbf{W}_H) \cdot T(\mathbf{x}, \mathbf{W}_T) + \mathbf{x} \cdot C(\mathbf{x}, \mathbf{W}_C).$$

where  $T$  is Transform Gate and  $H$  is the Carry Gate

In particular  $C = 1 - T$ :

$$\mathbf{y} = H(\mathbf{x}, \mathbf{W}_H) \cdot T(\mathbf{x}, \mathbf{W}_T) + \mathbf{x} \cdot (1 - T(\mathbf{x}, \mathbf{W}_T)).$$

We can have below conditions for specific  $T$  values:

$$\mathbf{y} = \begin{cases} \mathbf{x}, & \text{if } T(\mathbf{x}, \mathbf{W}_T) = 0, \\ H(\mathbf{x}, \mathbf{W}_H), & \text{if } T(\mathbf{x}, \mathbf{W}_T) = 1. \end{cases}$$

When  $T=0$ , we pass input as output directly, which creates an information highway That's why it is called the Carry Highway Network

When  $T=1$  we use non-linear activated transformed input as output


Here in contrast to the  $i$ -th unit in plain network the authors introduce the concept. For  $i$ -th block there is a block state  $\mathbf{c}(i)$  and transform gate output  $T_i(i)$ . And the corresponding block output  $\mathbf{o}(i)$

$$y_i = H_i(\mathbf{x}) * T_i(\mathbf{x}) + x_i * (1 - T_i(\mathbf{x}))$$

which is connected to the next layer

- Formally  $T(i)$  is the sigmoid function:

$$f_{C+1}(z) = [(f_C \circ f_C)(z)] \oplus [\text{conv}(z)]$$



Sigmoid function caps the output between 0 to 1. When the input has a too-small value it becomes 0. When the input has a too-large amount it becomes 1. Therefore, by learning  $w$  and  $b$ , a network can adaptively pass 0 or 1 to the next layer.

And the author claims that this helps to have the simple initialization scheme for  $WT$  which is independent of nature of  $H$ .

$bT$  can be initialized with the negative value e.g. -3 etc such that the network is initially biased towards carrying behaviour.

LSTM inspires the above idea as the authors mentioned

And SGD (Stochastic Gradient Descent) did not stall for networks with more than 10 layers. However the exact results have not been provided.


### Q3. What is DetNAS: Neural Architecture Search(NAS) on Object Detection?

#### Answer:

Object detection is one of the most fundamental computer vision OpenCV tasks and has been widely used in real-world applications. The performance of object detectors highly relies on features extracted by backbones. However most works on object detection directly use networks designed for classification as a backbone the feature extractors e.g. ResNet. The architectures optimized on image classification can not guarantee performance on object detection. It is known that there is an essential gap between these two different tasks. Image classification basically focuses on "What main object of the image is" while object detection aims at finding "Where and What each object

instance in an image. There have been little works focusing on backbone design for object detector except the hand-craft network DetNet.

Neural architecture search (NAS) has achieved significant progress in image classification and semantic segmentation. The networks produced by search have reached or even surpassed the performance of the hand-crafted ones on this task. But object detection has never been supported by NAS before. Some NAS Neural architecture search work directly applies architecture searched on CIFAR-10 classification on object detection.




In this work we present the first effort towards learning a backbone network for object detection tasks. Unlike previous NAS works our method does not involve any architecture-level transfer. We propose DetNAS to conduct neural architecture search directly on the target tasks. The quests are even performed with precisely the same settings to the target task. Training an object detector usually needs several days and GPUs no matter using a pre-train-finetune scheme or training from scratch. Thus it is not affordable to directly use reinforcement learning (RL) or evolution algorithm (EA) to search the architectures independently. To overcome this obstacle we formulate this problem into searching the optimal path in the large graph or supernet. In simple terms DetNAS consists of three steps: 1. training a supernet that includes all sub-networks in search space; 2. searching for the sub-network with the highest performance on the validation set with EA; 3. retraining the resulting network and evaluating it on the test set.

#### **Q4. You have any idea about ECE (Emotion cause extraction).**

##### **Answer:**

Emotion cause extraction (ECE) aims at extracting potential causes that lead to emotion expressions in the text. The ECE task was first proposed and defined as a word-level sequence labeling problem in Lee et al. To solve the shortcoming of extracting causes at the word level Gui et al. 2016 released a new corpus which has received much attention in the following study and becomes a benchmark dataset for ECE research.

Below Fig Displays an example from this corpus there are five clauses in a document The emotion happy is contained in fourth clause We denote this clause as an *emotion clause* which refers to a term that includes emotions It has two corresponding causes: a policeman visited the old man with the lost money in the second clause and told him that the thief was caught in the third clause We name them as *cause clause* which refers to a term that contains causes



In this work we propose a new task: emotion-cause pair extraction ECPE which aims to extract all potential pairs of emotions and corresponding causes in the document In Above Fig we show the difference between the traditional ECE task and our new ECPE task The goal of ECE is to extract the corresponding cause clause of the given emotion In addition to a document as the input ECE needs to provide annotated feeling at first before cause extraction


In contrast the output of our ECPE task is a pair of emotion-cause without the need of providing emotion annotation in advance From Above fig e g given the annotation of feeling: happy the goal of ECE is to track the two corresponding cause clauses: a policeman visited the old man with the lost money and and told him that the thief was caught While in the ECPE task the goal is to directly extract all pairs of emotion clause and cause clause including The old man was delighted a policeman visited the old man with the lost money and The old man was pleased and told him that the thief was caught without providing the emotion annotation happy

To address this new ECPE task we propose a two-step framework Step converts the emotion-cause pair extraction task to two individual sub-tasks emotion extraction and cause extraction respectively via two kinds of multi-task learning networks intending to extract a set of emotion clauses and a set of cause clauses Step 2 performs emotion-cause pairing and filtering We combine all the elements of the two sets into pairs and finally train a filter to eliminate the couples that do not contain a causal relationship

## Q5.What is DST (Dialogue state tracking)?

**Answer:**

Dialogue state tracking DST is a core component in task-oriented dialogue systems such as restaurant reservations or ticket bookings. The goal of DST is to extract user goals expressed during conversation and to encode them as a compact set of the dialogue states i.e. a set of slots and their corresponding values. E.g. as shown in below fig *(slot, value)* pairs such as *(price, cheap)* and *(area, centre)* are extracted from the conversation. Accurate DST performance is important for appropriate dialogue management where user intention determines the next system action and the content to query from the databases.



State tracking approaches are based on the assumption that ontology is defined in advance where all slots and their values are known. Having a predefined ontology can simplify DST into a classification problem and improve performance. Henderson et al [20 4b](#); Mrkšić et al [20 7](#); Zhong et al [20 8](#). However, there are two significant drawbacks to this approach: A full ontology is hard to obtain in advance. Xu and Hu [20 8](#). In the industry, databases are usually exposed through an external API only which is owned and maintained by others. It is not feasible to gain access to enumerate all the possible values for each slot. Even if a full ontology exists, the number of possible slot values could be significant and variable. For example, a restaurant name or a train departure time can contain a large number of possible values. Therefore, many of the previous works that are based on neural classification models may not be applicable in real scenarios.

## Q6.What is NMT(Neural machine translation)?


**Answer:**

NMT stands for Neural machine translation which is the use of neural network models to learn the statistical model for machine translation.

The key benefit to the approach is that the single system can be trained directly on the source and target text no longer requiring the pipeline of specialized methods used in statistical ML machine learning

Unlike the traditional phrase-based translation system which consists of many sub-components that are tuned separately neural machine translation attempts to build and train a single large neural network that reads a sentence and outputs a correct translation

As such neural machine translation NMT systems are said to be end-to-end systems as only one model is required for the translation



#### **■■ Encoder**

The task of the encoder is to provide the representation of a input sentence. The input sentence is a sequence of words for which we first consult embedding matrix. Then as in the primary language model described previously we process these words with a recurrent neural network RNN. This results in hidden states that encode each word with its left context i.e. all the preceding words. To also get the right context we also build a recurrent neural network RNN that runs right-to-left or from the end of the sentence to beginning. Having two recurrent neural networks RNN running in two directions is known as the bidirectional recurrent neural network RNN.

#### **■■ Decoder**

The decoder is the recurrent neural network RNN. It takes some representation of input context more on that in the next section on the attention mechanism and previous hidden state and the output word prediction and generates a new hidden decoder state and the new output word prediction.


If you use LSTMs for the encoder then you also use LSTMs for the decoder. From hidden state You now predict the output word. This prediction takes the form of the probability distribution over entire output vocabulary. If you have a vocabulary of say 50 000 words then the prediction is a 50 000 dimensional vector each element corresponding to the probability predicted for one word in the vocabulary.

## **Q7. What is Character-Level models (CLM)?**

#### **Answer:**

In English there is strong empirical evidence that the character sequence that create up proper nouns tend to be distinctive. Even divorced of context human reader can predict that hoekstenberger is an entity but abstractually is not. Some NER research explores use of character-level features.

including capitalization prefixes and suffixes Cucerzan and Yarowsky; Ratinov and Roth [2009](#) and character-level models CLMs Klein et al [2003](#) to improve the performance of NER but to date there has been no systematic study isolating utility of CLMs in capturing the distinctions between name and non-name tokens in English or across other languages



We conduct the experimental assessment of the discriminative power of CLMs for a range of languages: English Arabic Amharic Bengali Farsi Hindi Somali and Tagalog These languages use the variety of scripts and orthographic conventions e g only three use capitalization come from different language families and vary in their morphological complexity We represent the effectiveness of CLMs character-level models in distinguishing name tokens from non-name tokens as illustrated by the above Figure which shows confusion in histograms from a CLM trained on entity tokens Our models use individual tokens but perform extremely well in spite of taking no account of the word context

We then assess the utility of directly adding simple features based on this CLM character-level model implementation to an existing NER system and show that they have the significant positive impact on performance across many of the languages we tried By adding very simple CLM-based features to the system our scores approach those of a state-of-the-art SOTA NER system Lample et al [2016](#) across multiple languages representing both the unique importance and broad utility of this approach

## Q8.What is LexNLP package?

### Answer:

Over the last 2 decades many high-quality open-source packages for natural language processing NLP and machine learning ML have been released Developers and researchers can quickly write applications in languages such as Python Java and R that stand on shoulders of

comprehensive well-tested libraries such as Stanford NLP Manning et al [20 4](#) OpenNLP ApacheOpenNLP [20 8](#) NLTK Bird et al [2009](#) spaCy Honnibal and Montani [20 7](#) scikit-learn library Buitinck et al [20 3](#) Pedregosa et al [20](#) and Gensim Řehák and Sojka [20 0](#) Consequently for most of the domains rate of research has increased and cost of the application development has decreased

For some specialized areas like marketing and medicines there are focused libraries and organizations like BioMedICUS Consortium [20 8](#) RadLex Langlotz [2006](#) and the Open Health Natural Language Processing NLP Consortium Law however has received substantially less attention than others despite its ubiquity societal importance and the specialized form LexNLP is designed to fill this gap by providing both tools and data for developers and researchers to work with real legal and regulatory text including statutes regulations the court opinions briefs contracts and the other legal work products


Law is the domain driven by language logic and the conceptual relationships ripe for computation and analysis Ruhl et al [20 7](#) However in our experience natural language processing NLP and machine learning ML have not been applied as fruitfully or widely in legal as one might hope We believe that the key impediment to academic and commercial application has been lack of tools that allow users to turn the real unstructured legal document into structured data objects The Goal of LexNLP is to make this task simple whether for the analysis of statutes regulations court opinions briefs or the migration of legacy contracts to smart contract or distributed ledger systems

## Q9.Explain The Architecture of LeNet-5.

### Answer:

Yann LeCun Leon Bottou Yoshua Bengio and Patrick Haffner proposed the neural network architecture for the handwritten and machine-printed character recognition in the 990 s which they called them LeNet-5 The architecture is straightforward and too simple to understand that's why it is mostly used as a first step for teaching CNN Convolutional Neural Network


### Architecture



This architecture consists of two sets of convolutional and average pooling layers followed by the flattening convolutional layer then 2 fully-connected layers and finally the softmax classifier


#### **On the First Layer:**

The input for LeNet-5 is the  $32 \times 32$  grayscale image which passes through first convolutional layer with 6 feature maps or filters having size  $5 \times 5$  and the stride of one. Image dimensions changes from  $32 \times 32 \times 1$  to  $28 \times 28 \times 6$



#### **On Second Layer:**

Then it applies average pooling layer or sub-sampling layer with the filter size  $2 \times 2$  and stride of two. The resulting image dimension will be reduced to  $4 \times 4 \times 6$



#### **Third Layer:**


Next there is the second convolutional layer with 6 feature maps having size  $5 \times 5$  and the stride of one. In this layer only ten out of sixteen feature maps are connected to 6 feature maps of previous layer as shown below

	0	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15
0	X			X	X	X			X	X	X	X		X	X	
1	X	X			X	X	X			X	X	X	X		X	
2	X	X	X			X	X	X		X		X	X	X		
3		X	X	X		X	X	X	X		X		X	X	X	
4			X	X	X		X	X	X	X		X	X		X	
5				X	X	X		X	X	X	X		X	X	X	

TABLE I


EACH COLUMN INDICATES WHICH FEATURE MAP IN S2 ARE COMBINED BY THE UNITS IN A PARTICULAR FEATURE MAP OF C3.

The main reason is to break symmetry in the network and keeps a number of connections within reasonable bounds That is why the number of training parameters in this layers are 5 6 instead of 2400 and similarly number of connections are 5 600 instead of 240000




#### Fourth layer:

In the fourth layer S4 is an average pooling layer with filter size  $2 \times 2$  and stride of 2 This layer is same as second layer S2 except it has 6 feature maps so output will be reduced to  $5 \times 5 \times 6$



### **Fifth Layer:**


The fifth layer C5 is the fully connected convolutional layer with 20 feature maps each of the size  $5 \times 5 \times 16$ .  
 × Each of 20 units in C5 is connected to all the 400 nodes  $5 \times 5 \times 6$  in the fourth layer S4



### **Sixth Layer:**

The sixth layer is also fully connected layer F6 with 84 units

C5: Fully Connected Layer



F6: Fully Connected Layer



$$\begin{aligned}\text{Trainable parameters} &= \text{Weight} + \text{Bias} \\ &= (400 \times 120) + 120 = 48120\end{aligned}$$

$$\begin{aligned}\text{Trainable parameters} &= \text{Weight} + \text{Bias} \\ &= (120 \times 84) + 84 = 10164\end{aligned}$$

### Output Layer:

Finally there is fully connected softmax output layer with 10 possible values corresponding to digits from 0 to 9

F6: Fully Connected Layer



Output

0  
1  
2  
3  
4  
5  
6  
7  
8  
9



$$\begin{aligned}\text{Trainable parameters} &= \text{Weight} + \text{Bias} \\ &= (120 \times 84) + 84 = 10164\end{aligned}$$

# **DATA SCIENCE INTERVIEW PREPARATION (30 Days of Interview Preparation)**


## **# DAY 23**

## Q1.Explain Overfeat in Object detection.

### Answer:

Overfeat: It is a typical model of integrating object detection localization and classification tasks whole into one convolutional neural network CNN. The main idea is to do image classification at different locations on regions of multiple scales of the image in a sliding window fashion and second predict bounding box locations with the regressor trained on top of the same convolution layers.

This model architecture is too similar to AlexNet. This model is trained as follows:



- 1 Train a CNN model identical to AlexNet on image classification tasks
- 2 Then we replace top classifier layers by the regression network and trained it to predict object bounding boxes at each spatial location and scale. Regressor is class-specific each generated for one class image
  - Input: Images with classification and bounding box
  - Output:  $x_{left}$   $x_{right}$   $y_{top}$   $y_{bottom}$     $x_{left}$   $x_{right}$   $y_{top}$   $y_{bottom}$    4 values in total representing the coordinates of the bounding box edges
  - Loss: The regressor is trained to minimize  $L_2$  norm between the generated bounding box and truth for each training example

At the detection time

- 1 It Performs classification at each location using the pretrained CNN model
- 2 It Predicts object bounding boxes on all classified regions generated by the classifier
  - Merge bounding boxes with sufficient overlap from localization and sufficient confidence of being the same object from the classifier

## Q2. What is Multipath: Multiple Probabilistic Anchor Trajectory Hypotheses for Behavior Prediction?

**Answer:**

In this paper we focus on problem of predicting future agent states which is the crucial task for robot planning in real-world environments. We are specifically interested in addressing this problem for self-driving vehicles application with a potentially enormous societal impact. Mainly predicting the future of other agents in this domain is vital for safe, comfortable and efficient operation. E.g. it is important to know whether to yield to the vehicle if they are going to cut in front of our robot or when would be the best time to add into traffic. Such future prediction requires an understanding of a static and dynamic world context: road semantics *like* lane connectivity, stop lines, traffic light informations and past observations of other agents as in below Fig.


A fundamental aspect of the future state prediction is that it is inherently *stochastic* as agents can't know each other's motivations. When we are driving we can never really be sure what other drivers will do next and it is essential to consider multiple outcomes and their likelihood.

We seek the model of the future that can provide both i) a weighted parsimonious set of discrete trajectories that covers space of likely outcomes and ii) a closed-form evaluation of the likelihood of any trajectory. These two attributes enable efficient reasoning in relevant planning use-cases e.g. human-like reactions to discrete trajectory hypotheses *e.g.* yielding, following and probabilistic queries such as the expected risk of collision in a space-time region.

This model addresses these issues with critical insight: it employs a fixed set of *trajectory anchors* as the basis of our modeling. This lets us factor stochastic uncertainty hierarchically: First *intent uncertainty* captures the uncertainty of *what* an agent intends to do and is encoded as a distribution over the set of anchor trajectories. Second given an intent *control uncertainty* represents our uncertainty over *how* they might achieve it. We assume control uncertainty is normally distributed at each future time step [Thrun05] parameterized such that the mean corresponds to a context-specific offset from the anchor state with the associated covariance capturing the unimodal aleatoric uncertainty [Kendall17]. In Fig. Illustrates a typical scenario where there are three likely intents given the scene context with control mean offset refinements respecting road geometry and control uncertainty intuitively growing over time.

Our trajectory anchors are modes found in our training data in state-sequence space via unsupervised learning. These anchors provide templates for coarse-granularity futures for an agent and might correspond to semantic concepts like change lanes or slow down although to be clear we don't use any semantic concepts in our modeling.


Our complete model predicts a Gaussian mixture model GMM at each time step with the mixture weights intent distribution fixed over time Given such a parametric distribution model we can directly evaluate the likelihood of any future trajectory and have a simple way to obtain a compact diverse weighted set of trajectory samples: the MAP sample from each anchor-intent



### Q3. An Object detection approach using MR-CNN

**Answer:**

**Multi-Region CNN (MR-CNN):** Object representation using multiple regions to capture several different aspects of one object




## Network Architecture of MR-CNN


- First the input image goes through Activation Maps Module as shown above and outputs the activation map
- Bounding box** or Region proposals candidates are generated using Selective Search
- For each bounding box candidate a set of regions  $i$  with  $i \in 1$  to  $n$  are generated that is why it is known as multi-region. More details about the choices of multiple areas are described in next sub-section
- ROI pooling is performed for each region  $i$  cropped or pooled area goes through fully connected FC layers at each Region Adaptation Module
- Finally the output from all FC layers are added together to form a 1D feature vector which is an object representation of the bounding box.
- Here VGG-16 ImageNet pre-trained model is used. The max-pooling layer after the last conv layer is removed

## Q4. Object detection using Segmentation-aware CNN

**Answer:**



- There are close connections between segmentation and detection And segmentation related ques are empirically known to help object detection often
- Two modules are added: **Activation maps module for semantic segmentation-aware features** and **regions adaptation module for grammarly segmentation-aware feature.**
- There is no additional annotation used for training here
- FCN is used for an activation map module
- The last FC7 layer channels number is changed from 4096 to 512



- The **weakly supervised training** strategy is used **Artificial foreground class-specific segmentation mask is created using bounding box annotations**


- More particularly the ground truth bounding boxes of an image are projected on the spatial domain of the last hidden layer of the [FCN](#) and the pixels that lay inside the projected boxes are labelled as foreground while the rest are labelled as background
- After training the FCN using the mask the last classification layer is dropped Only the rest of FCN is used
- Though it is weakly supervised training the foreground probabilities shown as above still carry some information as shown above
- The bounding box used is 1.5 times larger than the original bounding box

## Q5. What is CRAFT (Object detection)?

**Answer:**

**CRAFT stands for** Cascade Region-proposal-network And **FasT R-CNN** It is reviewed by the Chinese Academy of Sciences **and** Tsinghua University In Faster R-CNN region proposal network is used to generate proposals These proposals after ROI pooling are going through network for classification However CRAFT is found that there is a core problem in Faster R-CNN:

- In proposal generation there is still a large proportion of background regions The existence of many background sample causes many false positives



In CRAFT Cascade Region-proposal-network), as shown above another CNN Convolutional neural network is added after RPN to generate fewer proposals i e 200 here . Then classification is performed on 200 proposals and outputs about 20 first detection results For each primitive result, refined object detection is performed using one-vs-rest classification

### Cascade Proposal Generation

#### Baseline RPN


- An ideal proposal generator should generate as few proposal as possible while covering almost all object instances Due to resolution loss caused by CNN pooling operation and the fixed aspect ratio of the sliding window RPN is weak at covering objects with extreme shapes or scales

aero	bike	<b>bird</b>	<b>boat</b>	<b>bottle</b>
95.44	98.81	<b>93.90</b>	<b>92.78</b>	<b>80.38</b>
bus	car	cat	<b>chair</b>	cow
98.12	96.00	99.16	<b>91.80</b>	99.18
table	dog	horse	mbike	persn
95.15	99.59	97.70	96.31	95.49
plant	sheep	sofa	train	<b>tv</b>
<b>86.87</b>	98.76	98.74	97.52	<b>90.58</b>

Recall Rates (is in %), Overall is 94.87%, lower than 94.87% is bold in the text.

- The above results are baseline RPN based on VGG-M trained using PASCAL VOC 2007 train-val and tested on the test set
- The recall rate on each object category varies a lot Object with extreme aspect ratio and scale are hard to be detected such as boat and bottle

### Proposed Cascade Structure




The concatenation classification network after RPN is denoted as FRCN Net here

- An additional classification network that comes after RPN
- The additional network is the 2- class detection network denoted as FRCN net in above figure. It uses output of RPN as training data
- After RPN net is trained the 2000 first proposals of each training image are used as training data for the FRCN net
- During training +ve and -ve sampling are based on 0.7 IoU for negatives and below 0.3 IoU for negatives respectively
- **There are 2 advantages:**
  - 1 First additional FRCN net further **improves quality of the object proposals** and **shrinks more background regions** making proposals fit better with task requirement
  - 2 **Proposals from multiple sources can be merged** as the input of the FRCN net so that complementary information can be used

## Q6. Explain YOLOv1 for Object Detection.


**Answer:**

- OLOv1 stands for One Look Only Once it is reviewed by FAIR Facebook AI Research The network only looks at the image once to detect multiple objects



By just looking image once the detection speed is in real-time 45 fps . Fast □ OLOv1 achieves 155 fps

- OLO suggests having a unified network to perform all at once Also an end-to-end training network can be achieved




The input image is divided into the  $S \times S$  grid  $S=7$  . If the center of the object falls into the grid cell that grid cell is responsible for detecting that object

Each grid cell predict  $B$  bounding boxes  $B=2$  and confidence scores for those boxes. These confidence score reflect how confident model is that the box contains an object i.e any objects in the box  $P$  Objects

Each bounding box consists of five predictions:  $x$   $y$   $w$   $h$  and confidence


- The  $x$   $y$  coordinates represent center of the box relative to the bound of the grid cell
- The height  $h$  and width  $w$  are predicted relative to whole image
- The confidence represents the IOU Intersection Over Union between the predicted box and any ground truth box

Each grid cell also predicts conditional class probabilities  $P(\text{Class} | \text{Object}) / \text{Total number of classes}$   $\approx 20$




The output size becomes:  $7 \times 7 \times 2 \times 5 \times 20 = 1470$

## Network Architecture of YOLOv1



The model consists of 24 convolutional layers followed by two fully connected layers. Alternating 1x1 convolutional layers reduce features space from preceding layers. 1x1 Conv has been used in GoogLeNet for reducing the number of parameters.

Fast OLO fewer convolutional layers 9 instead of 24 and fewer filters in those layers. The network pipeline is summarized like below:



Therefore we can see that the input image goes through network once and then objects can be detected. And we can have end-to-end learning.

## Q7. Adversarial Examples Improve Image Recognition

### Answer:

Adversarial examples crafted by adding imperceptible perturbations to images can lead to ConvNets Convolutional Neural Networks to make wrong predictions. The existence of adversarial examples not only reveal limited generalization ability of ConvNets but also poses security threats on the real-world deployment of these models. Since the first discovery of the vulnerability of ConvNets to adversarial attacks many efforts have been made to improve network robustness.



Above Fig : AdvProp improves image recognition By training model on ImageNet AdvProp helps EfficientNet-B7 to achieve 52.9% accuracy on ImageNet 52.9% mCE mean corruption error lower is better on ImageNet-C 44.7% accuracy on ImageNet-A and 26.6% accuracy on Stylized-ImageNet beating its vanilla counterpart by 0.7%, 6.5%, 7.0% and 4.0% respectively Theses sample images are randomly selected from category goldfinch

In this paper rather than focusing on defending against adversarial examples we shift our attention to leveraging adversarial examples to improve accuracy Previous works show that training with adversarial examples can enhance model generalization but are restricted to certain situations the improvement is only observed either on small datasets e.g. MNIST in the fully-supervised setting [5] or on larger datasets but in the semi-supervised setting [21, 22]. Meanwhile recent works [15, 16, 17] also suggest that training with adversarial examples on large datasets e.g. ImageNet [20] with supervised learning results in performance degradation on clean images To summarize it remains an open question of how adversarial examples can be used effectively to help vision models

We observe all previous methods jointly train over clean images and adversarial examples without distinction even though they should be drawn from different underlying distributions We hypothesize this distribution mismatch between fresh examples and adversarial examples is a key factor that causes performance degradation in previous works

## Q8. Advancing NLP with Cognitive Language Processing Signals


### Answer:

When reading humans process language automatically without reflecting on each step Humans string words together into sentences understand the meaning of spoken and written ideas and process language without overthinking about how the underlying cognitive process happens This process generates cognitive signals that could potentially facilitate natural language processing tasks

In recent years collecting these signals has become increasingly accessible and less expensive Papoutsaki et al 2016 ; as a result using cognitive features to improve NLP tasks has become more popular For example researchers have proposed a range of work that uses eye-tracking or gaze signals to improve part-of-speech tagging Barrett et al 2016 sentiment analysis Mishra et al 2017 named entity recognition Hollenstein andhang 2019 among other tasks Moreover these signals have been used successfully to regularize attention in neural networks for NLP Barrett et al 2010

However most previous work leverages only eye-tracking data presumably because it is the most accessible form of cognitive language processing signal Also most state-of-the-artwork SOTA focused on improving a single task with a single type of cognitive signal But can cognitive processing signals bring consistent improvements across modality e.g. eye-tracking and EEG and across various NLP

tasks. And if so does the combination of different sources of cognitive signals bring incremental improvements.



## Q8. Do you have any idea how can we use NLP on News headlines to predict index trends?

**Answer:**

Traders generally look up information about the company they are looking to buy shares into for long and short trading. A frequent source of information is news media which provides updates about the company's activities such as expansion better or worse revenues than expected new products and much more. Depending on the news trader can determine a bearish or bullish trend and decide to invest in it.

We may be able to correlate overall public sentiments towards the company and its stock price: Apple is generally well-liked by the public receives daily news coverage of its new product and financial stability and its stock has been growing steadily. These facts may be correlated but first may not cause the second; we will analyze if news coverage can be used to predict the market trend. To do so we will examine the top 25 news headlines of each open-market day from 200□ to late 2015 and try to predict

---

the end-of-day value of DJIA index for the same day. The theory behind predicting same day value is that traders will respond to news quickly and thus the market will adjust within an hour of release. Therefore in the single business day if the news is spread during business hours its effect may be measured before closing bell of the market.

The motivation behind this analysis is that humans take decision using most of the available information. This usually takes several minutes to discover new information and take the decision. An algorithm is capable of processing gigabytes of texts from multi-source streams in second. We could potentially exploit this difference in order to create a trading strategy.

NLP Natural Language Processing techniques can be used to extract different information from headlines such as sentiment subjectivity context and named entities. We obtain an indicator vector using each of these techniques which allows us to train different algorithms to predict a trend. To predict these values we can use several methods that should be well suited for this type of information: Linear regression Support Vector Machine SVM Long Short-Term Memory LSTM recurrent neural network and a dense feed-forward MLP neural network. We included techniques used by Bollen et al 2010 which resulted in state-of-the-art SOTA results. We will also analyze the method used in other studies with a similar context.

### **Information in headlines**

Latent Sentiment Analysis is done by building up a corpus of labeled words which usually connote a degree of +ve or -ve sentiment. We can extend the corpus to include emoticons i.e. :- and expression which often correlates to strong emotions. Naive sentiment analysis consists of a lookup of each word in sentence to be analyzed and evaluation of a score for sentence overall. This approach is limited by its known vocabulary which can be mitigated by context analysis and introduction of synonyms. Second limitation is sarcasm which is prevalent in twitter feed analysis. The sentiment inferred by words is opposed to the sentiment assumed by the user. This is mitigated by technique detecting sarcasm which

lead to a polarity flip of such tweets.

Sentiment analysis gives insight on how favorable the media is and maybe the bias traders may have towards buying or selling.

Another NLP technique which gave promising results was context analysis. This is a recent deep learning approach where you rely on a large corpus of text in order to learn and predict the words around a target. You can then deduce in what context it usually appears. The result is a vector representing each word. Other vectors with little distance are usually synonyms. The representation also allows us to do algebra such as the famous king - man woman = queen.

---

Learning this representation offers the possibility of associating a specific context with a bullish or bearish market


DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview Preparation)

# Day2?

## Q1.What is STN?


Answer:

STN stands for Spatial Transformer Network for image classification. Google Deepmind briefly reviews it. STN helps to crop out and scale-normalizes appropriate region which can simplify the subsequent classification task and lead to better classification performance as below:



(a) Input Image with Random Translation, Scale, Rotation, and Clutter, (b) STN Applied to Input Image, (c) Output of STN, (d) Classification Prediction

## Spatial Transformer Network (STN)



**Source**



$$\begin{pmatrix} x_i^s \\ y_i^s \end{pmatrix} = T_\theta(G_i) = A_\theta \begin{pmatrix} x_i^t \\ y_i^t \\ 1 \end{pmatrix} = \begin{bmatrix} \theta_{11} & \theta_{12} & \theta_{13} \\ \theta_{21} & \theta_{22} & \theta_{23} \end{bmatrix} \begin{pmatrix} x_i^t \\ y_i^t \\ 1 \end{pmatrix}$$

**Target**



- STN is composed of **Localisation Net** **Grid Generator** and **Sampler**

## Localization Net


- With **input feature map  $U$**  with width  $W$  height  $H$  and  $C$  channels **outputs** are  $\theta$  parameters of transformation  $T\theta$ . It can be learned as affine transform as above. Or to be more constrained such as the used for attention which only contains scaling and translation as below:

$$A_\theta = \begin{bmatrix} s & 0 & t_x \\ 0 & s & t_y \end{bmatrix}$$

### Grid Generator

- Suppose we have a regular grid  $G$  this  $G$  is a set of points with **source coordinates**  $(x_i^s, y_i^s)$  which act as **input**
- Then we **apply transformation**  $T\vartheta$  on  $G$  i.e.  $T\vartheta G$
- After  $T\vartheta G$  a set of points with **destination coordinates**  $(x_i^t, y_i^t)$  is **outputted** These points have been altered based on the transformation parameters It can be Translation Scale Rotation or More Generic Warping depending on how we set  $\vartheta$  as mentioned above

### Sampler



- Based on the new set of coordinates  $(x_i^t, y_i^t)$  we generate a **transformed output feature map**  $V$  This  $V$  is translated scaled rotated warped projective transformed or affined whatever
- It is noted that STN can be applied to not only input image but also intermediate feature maps

## Q2.What is decaNLP?

**Answer:**

We introduced the Natural Language Decathlon decaNLP to explore models that generalize to many different kinds of Natural Language Processing NLP tasks decaNLP encourages single model to

simultaneously optimize for 10 tasks: question answering machine translation document summarization semantic parsing sentiment analysis natural language inference NLI semantic role labeling relation extraction goal-oriented dialogue and pronoun resolution

We frame all the tasks as question answering [Kumar et al 2016] by allowing task specification to take the form of a natural language question  $q$ : all inputs have a context question and answer Fig 1 Traditionally NLP examples have inputs  $x$  and output  $y$  and the underlying task  $t$  is provided through explicit modeling constraints Meta-learning approaches include  $t$  as additional input Our approach does not use the single representation for any  $t$  but instead uses natural language questions that describe underlying tasks This allows single models to multitask effectively and makes them more suitable as pre-trained models for transfer learning and meta-learning: natural language questions allow a model to generalize to entirely new tasks through different but related task descriptions

The MQAN multitask question answering network is designed for decaNLP and makes use of a novel dual attention and multi-pointer-generator decoder to multitask across all tasks in decaNLP Our results represent that training the MQAN jointly on all tasks with the right anti-curriculum strategy can achieve performance comparable to that of ten separate MQANs each trained separately An MQAN pretrained on decaNLP shows improvements in transfer learning for machine translation and named entity recognition NER domain adaptation for sentiment analysis and natural language inference NLI and zero-shot capabilities for text classification Though not explicitly designed for any one job MQAN proves to be a robust model in a single-task setting as well achieving state-of-the-art results on the semantic parsing component of decaNLP

### Examples

Question	Context	Answer	Question	Context	Answer
What is a major importance of Southern California in relation to California and the US?	...Southern California is a major economic center for the state of California and the US....	major economic center	What has something experienced?	Areas of the Baltic that have experienced <a href="#">eutrophication</a> .	eutrophication
What is the translation from English to German?	Most of the planet is ocean water.	Der Großteil der Erde ist Meerwasser.	Who is the illustrator of Cycle of the Werewolf?	Cycle of the Werewolf is a short novel by Stephen King, featuring illustrations by comic book artist <a href="#">Bernie Wrightson</a> .	Bernie Wrightson
What is the summary?	Harry Potter star Daniel Radcliffe gains access to a reported £320 million fortune....	Harry Potter star Daniel radcliffe gets £320M fortune....	What is the change in dialogue state?	Are there any Eritrean restaurants in town?	food-Eritrean
Hypothesis: Product and geography are what make cream skimming work. Entailment, neutral, or contradiction?	Premise: Conceptually cream skimming has two basic dimensions – product and geography.	Entailment.	What is the translation from English to SQL?	The <a href="#">table</a> has column names... Tell me what the <a href="#">notes</a> are for South Australia.	SELECT notes from table WHERE 'Current Slogan' = 'South Australia'
Is this sentence positive or negative?	A stirring, funny and finally transporting re-imaging of Beauty and the Beast and 1930s horror film.	positive	Who had given help? Susan or Joan?	Joan made sure to thank Susan for all the help she had given.	Susan

In the above figure: Overview of the decaNLP dataset with one example from each decaNLP task in the order presented in Section 2 They show how the datasets were pre-processed to become question


answering problems Answer words in red are generated by pointing to the context in green from the issue and in blue if they are made from a classifier over the output vocabulary

### Q3.Universal Transformers

#### Answer:

Convolutional and fully-attentional feed-forward architectures such as the Transformer model have recently emerged as viable alternatives to RNNs Recurrent neural networks for the range of sequence modeling tasks notably machine translation [JonasFaceNet2017](#); [transformer](#). These architectures address the significant shortcoming of RNNs namely their inherently sequential computation which prevents parallelization across elements of input sequence while still addressing vanishing gradients problem [vanishing-exploding-gradient](#). Transformer model in particular achieves this by relying entirely on the self-attention mechanism [decomposableAttnModel](#); [lin2017structured](#) to compute series of context-informed vector-space representations of symbols in its input and output which are then used to predict distributions over subsequent symbols as the model predicts output sequence symbol-by-symbol. Not only is this mechanism straightforward to parallelize but as each symbol's representation is also directly informed by all other symbols' representations this results in an active global receptive field. This stands in contrast to e.g. convolutional architecture which typically has limited receptive field.

Notably however Transformer foregoes the Recurrent Neural Network RNN's inductive bias towards learning recursive or iterative transformations. Our experiments indicate that this inductive bias may be important for several algorithmic and language understanding tasks of varying complexity: in contrast to models such as the Neural Turing Machine the Neural GPU or Stack RNNs the Transformer does not generalize well to input lengths not encountered during training.



In this paper we propose a *Universal Transformer*. It combines the parallelizability and global receptive field of a Transformer model with the recurrent inductive bias of RNNs which seems to be better suited to range of algorithmic and natural language understanding NLU sequence-to-sequence problems. As the name implies in contrast to standard Transformer under certain assumptions a Universal Transformer can be shown to be computationally universal.

In each step the Universal Transformer iteratively refine its representations for all positions in sequence in parallel with self-attention mechanism decomposableAttnModel ; lin2017structured followed by the recurrent transformation consisting of a depth-wise separable convolution xception2016 or a position-wise fully-connected layer see above Fig. We also extended the Universal Transformer by employing an adaptive computation time mechanism at each position in sequence graves2016adaptive allowing model to choose the required number of refinement steps for each symbol dynamically.

When running for fixed number of steps the Universal Transformer is equivalent to a multi-layer Transformer with a tied parameter across its layers. However another and possibly more informative way of characterizing Universal Transformer is as recurrent function evolving per-symbol hidden states in parallel based at each step on a sequence of the previous unknown state. In this way it is similar to architectures such as Neural GPU and the Neural Turing Machine. The Universal Transformer thereby retains the attractive computational efficiency of original feed-forward Transformer model but with an added recurrent inductive bias of RNNs. In its adaptive form we show that the Universal Transformer can effectively interpolate between the feed-forward fixed-depth Transformer and a gated recurrent architecture running for several steps depending on the input data.

Our experimental results show that its recurrence improve results in machine translation where Universal Transformer outperforms the standard Transformer with a same no of parameters. In experiments on several algorithmic tasks Universal Transformer consistently improves significantly over LSTM Long Short Term Memory RNNs and the standard Transformer. Furthermore on bAbI and LAMBADA text understanding data sets the Universal Transformer achieves a new state of the art.

## **Q4. What is StarSpace in NLP?**

**Answer:**

We introduce StarSpace the neural embedding model that is general enough to solve a wide variety of problems:

- Other labeling tasks or Text classification e.g sentiment classification

- Ranking of the set of entities e.g. a classification of web documents given a query
- Collaborative filtering-based recommendation e.g. recommending documents, videos or music
- Content-based recommendation where content is defined with discrete features e.g. words of documents
- Embedding graphs e.g. multi-relational graphs such as Freebase
- Learning word, sentence or document embeddings

It can be viewed as a straight-forward and efficient strong baseline for any of these tasks. In experiment it is shown to be on par with or outperforming several competing methods while being generally applicable to cases where many of that method are not.

The method works by learning entity embeddings with discrete feature representation from relations among collections of those entities directly for the task of ranking or classification of interest. In the general case StarSpace embeds objects of different types into a vectorial embedding space; hence the star meaning all types and space in a name and in that familiar space compares them against each other. It learns to rank the set of entities, documents or objects given a query entity, document or object where the query is not necessarily of the same type as the items in the set.

## Q5. TransferTransfo in NLP

### Answer:

Non-goal-oriented dialogue systems chatbots are interesting test-bed for interactive Natural Language Processing NLP systems and are also directly useful in wide range of applications ranging from technical support services to entertainment. However building intelligent conversational agent remains an unsolved problem in artificial intelligence AI research. Recently recurrent neural network RNN based models with sufficient capacity and access to large datasets attracted large interest when first attempted. It showed that they were capable of generating meaningful responses in some chit-chat settings. Still further inquiries in the capabilities of these neural network

architectures and developments indicated that they were limited which made communicating with them a rather unsatisfying experience for human beings

The main issues with these architectures can be summarized as:

- i the wildly inconsistent outputs and the lack of a consistent personality Li and Jurafsky [2016](#)
- ii the absence of long-term memory as these models have difficulties in taking into account more than the last dialogue utterance; and
- iii a tendency to produce consensual and generic responses that are vague and not engaging for humans Li Monroe and Jurafsky [2016](#)

In this work we take a step toward more consistent and relevant data-driven conversational agents by proposing a model architecture associated training and generation algorithms which are able to significantly improve over the traditional seq-2-seq and information-retrieval baselines in terms of i relevance of the answer ii coherence with a predefined personality and dialog history and iii grammatical and fluency as evaluated by auto


## **Q6. Wizard of Wikipedia: Knowledge-Powered Conversational Agents**

Answer:

Arguably one of the critical goals of AI and the ultimate goal of natural language research is for the human to be able to talk to the machine In order to get close to this goal machines must master the no of skills: to be able to comprehend language employ memory to retain and recall knowledge to reason about these concept together and finally output a response that both fulfills functional goals in conversation while simultaneously being captivating to their human speaking partner The current state-of-the-art SOTA approaches sequence to sequence seq2seq models of various kinds Sutskever et al [2014](#); Vinyals & Le [2015](#); Serban et al [2016](#); Vaswani et al [2017](#) attempt to address some of these skills but generally suffer from inability to bring memory and knowledge to bear; as indicated by their name they involve encoding input sequence providing limited reasoning by transforming their hidden state given input and then decoding to the output To converse intelligently on the given topic the speaker needs knowledge of that subject and it is our contention here that more direct knowledge memory mechanisms need to be employed In this work we consider setups where this can be naturally measured and built

We consider the task of open-domain dialogue where two speakers conduct open-ended chit-chat given an initial starting topic and during the conversation the topic can broaden or focus on related themes During such conversations an interlocutor can glean new information and personal points of view from

their speaking partner while providing themselves similarly. This is a challenging task as it requires several components not found in many standard models. We design a set of architectures specifically for this goal that combine elements of Memory Network architectures Sukhbaatar et al 2015 to retrieve knowledge and read and condition on it and Transformer architectures Vaswani et al 2017 to provide state-of-the-art text representations and sequence models for generating outputs which we term Transformer Memory Networks.



## Q7. ERASER: A Benchmark to Evaluate Rationalized NLP Models

**Answer:**

### Movie Reviews

In this movie, ... Plots to take over the world. The acting is ...  
The soundtrack is run-of-the-mill, but the action more than makes up for it.

- (a) Positive (b) Negative

### e-SNLI

H A man in an orange vest runs over a pickup truck.  
P A man is touching a truck.

- (a) Entailment (b) Contradiction (c) Neutral

### Commonsense Explanations (CoS-E)

Where do you find the most amount of leaves?

- (a) Compost pile (b) Flowers (c) Forest (d) Field (e) Ground

### Evidence Inference

**Article** Patients for this trial were recruited ... Comparing with 0.9% saline, 120 mg of inhaled nebivolol Turasemide had no effect on breathlessness during exertion.

**Prompt** With respect to breathlessness, what is the reported difference between patients receiving placebo and those receiving furosemide?

- (a) Sig. decreased (b) No sig. difference (c) Sig. increased

Interest has recently grown in interpretable Natural Language Processing NLP systems that can reveal **how** and **why** model make their predictions. But work in this direction has been conducted on the

different dataset with correspondingly different metrics and inherent subjectivity in defining what constitute interpretability has translated into researcher using different metrics to quantify performance We aimed to facilitate measurable progress on designing interpretable NLP Natural Language Processing models by releasing the standardized benchmark of datasets augmented and repurposed from pre-existing corpora and spanning the range of NLP tasks and associated metrics for measuring the quality of rationales We refer to this as ERASER Evaluating Rationales And Simple English Reasoning benchmark

In curating and releasing ERASER we take inspiration from stickiness of GLUE Wang et al 2019b and SuperGLUE Wang et al 2019a benchmarks for evaluating progress in natural language understanding NLU tasks These have enabled rapid growth in models for inclusive language representation learning We believe still somewhat nascent subfield of interpretable NLP Natural Language Processing stands to similarly benefit from the analogous collection of standardized datasets or tasks and metric

Interpretability is the broad topic with many possible realizations Doshi-Velez and Kim [2017](#) ; Lipton [2016](#) In ERASER we focuses specifically on *rationales* i e snippets of text from the source document that support a specific categorization All datasets contained in ERASER include such rational explicitly marked by annotators as supporting specific classifications By definition rationales should be *sufficient* to categorize document but they may not be comprehensive Therefore for some dataset we have collected *complete* rationales i e in which *all* evidence supporting the classification has been marked

How one measures quality of extracted rationales will invariably depend on their intended use With this in mind we propose the suite of metrics to evaluate rationales that might be appropriate for different scenarios Widely this includes measures of agreement with human-provided rationales and assessment of *faithfulness* The latter aim to capture extent to which rationales provided by the model in fact informed its prediction

While we propose metrics that we think are reasonable we view a problem of designing metrics for evaluating rationales-especially for capturing faithfulness as a topic for further research that we hope that ERASER will help facilitate We plan to revisit metrics proposed here in future iterations of benchmark ideally with input from community Notably while we provide a leaderboard this is perhaps better viewed as the results board ; we do not privilege any particular metric Instead we hope that ERASER permits comparison between models that provide rationales wrt different criteria of interest


## Q8. End to End memory networks

**Answer:**


Two grand challenges in artificial intelligence(AI) research have been to build a model that can make multiple computational step in the service of answering the question or completing the task, and models that can describe long term dependencies in sequential data.

Recently there has been the resurgence in models of computation using explicit storage and a notion of attention; manipulating such storage offers an approach to both of these challenges. In, the storage is endowed with continuous representation; reads from and writes to storage, as well as other processing steps, are modeled by actions of neural networks.

In this work, we present the new recurrent neural network (RNN) architecture where recurrence reads from possibly large external memory multiple times before outputting symbol. Our model can be considered the continuous form of the Memory Network implemented in. The model in that work was not easy to train via back-propagation and required supervision at each layer of a network. The continuity of model we present here means that it can be trained end-to-end from input-output pairs, and so applies to more tasks, i.e., tasks where such supervision is not available, like in language modeling or realistically supervised question answering tasks. Our model can also be seen as version of RNNsearch with multiple computational steps per output symbol. We will show experimentally that various hops over the long-term memory are crucial to excellent performance of our model on these tasks, and that training the memory representation can be integrated in a scalable manner into our end-to-end neural network model.



## Multiple Memory Lookups: Multiple Hops




## Q9. What is LinkNet?

### Answer:

From my experience LinkNet is lightning fast which is one of the main improvements the authors site in their summary LinkNet is a relatively lightweight network with around 11.5 million parameters; networks like VGG have more than 10x that amount

The structure of LinkNet is to use a series of encoder and decoder blocks to break down the image and build it back up before passing it through a few final convolutional layers. The structure of the network was designed to minimize the number of parameters so that segmentation could be done in real-time.

I performed some tests of the LinkNet architecture but did not spend too much time iterating to improving the models




**DATA SCIENCE  
INTERVIEW PREPARATION  
(30 Days of Interview  
Preparation)  
# Day-25**

## Q1. What is WRN?

**Answer:**

**WRN:** It stands for Wide Residual Networks is presented By widening Residual Network (ResNet) the network can be more superficial or shallow with same accuracy or improved accuracy More external network means:

- the number of layers can be reduced
- Training time can be shorter as well



Problems on Residual Network (ResNet)

Circuit Complexity Theory

The authors of residual networks(ResNet) tried to make them as thin as possible in favor of increasing their depth and having less parameters and even introduced a «bottleneck» block which makes ResNet blocks even thinner

Diminishing Feature Reuse

However As gradient flows through network there is nothing to force it to go through residual block weights and it can avoid learning anything during training so there may be either only few blocks that learn useful representations or many blocks share very little information with a small contribution to the final goal This problem was formulated as a diminishing feature reuse

### WRNs (Wide Residual Networks)

In WRNs plenty of parameters are tested like the design of ResNet block how deep (deepening factor  $J$ ) and how extensive (widening factor  $k$ ) within the ResNet block

When  $k=1$  it has the same width as the *ResNet* While  $k>1$  it is  $k$  time wider than *ResNet*

**WRN- $d\cdot k$** : means the WRN has a depth of  $d$  and with widening factor  $k$

- *Pre-Activation ResNet* is used in CIFAR-10 CIFAR-100 and SVHN datasets Original *ResNet* is used in the ImageNet dataset
- The significant difference is that *Pre-Activation ResNet* has the structure of performing batch norm and ReLU before convolution (i.e BN-ReLU-Conv while original *ResNet* has the structure of Conv-BN-ReLU And *Pre-Activation ResNet* is generally better than the original one but it has no visible improvement in ImageNet when layers are only around 100

The design of the ResNet block

block type	depth	# params	time,s	CIFAR-10
$B(1,3,1)$	40	1.4M	85.8	6.06
$B(3,1)$	40	1.2M	67.5	5.78
$B(1,3)$	40	1.3M	72.2	6.42
$B(3,1,1)$	40	1.3M	82.2	5.86
$B(3,3)$	28	1.5M	67.5	5.73
$B(3,1,3)$	22	1.1M	59.9	5.78

•

- **B(3;3)** : Original «basic» block in the above figure a
- **B(3;1;3)** : With one extra ( $1\times 1$  layer in between the two  $3\times 3$  layers
- **B(1;3;1)** : With the same dimensionality of all convolutions bottleneck
- **B(1;3)** : The network has the alternating ( $1\times 1$   $3\times 3$  convolutions
- **B(3;1)** : The network has the alternating ( $3\times 3$   $1\times 1$  convolutions
- **B(3;1;1)** : This is Network in Network style block

**B(3;3)** has the smallest error rate (5.73%)

Note: The Number of depths (layers) is different is to keep the number of parameters close to each other

## Q2.What is SIMCO: SIMilarity-based object Counting?

**Answer:**

Most approaches for counting similar objects in images assume a single object class; when is not ad-hoc learning is necessary. None of them are genuinely agnostic and multi-class i.e. able to capture repeated patterns of different types without any tuning. Counting approaches are based on density or regression estimation; here we focus on counting by detection so the counted objects are individually detected first.

Research on agnostic counting is vital in many fields. It serves for obvious question answering where counting questions could be made on too-specific entities outside the semantic span of the available classes (e.g. What is the most frequent thing? in below Fig.). In representation learning unsupervised counting of visual primitives (i.e. visible things) is crucial to obtain a rich image representation. Counting is a hot topic in cognitive robotics where autonomous agents learn by separating sensory input into the finite number of classes (without a precise semantics) building the classification system that

counts on each of them.

Application-wise agnostic counting may help the manual tagging of training images providing a starting guess for the annotator on single- or multi-spectral images. Inpainting filters may benefit from a magic wand capturing repeated instances to remove.



**Figure: SIMCO on obvious question answering: the most frequent object? SIMCO finds 47 LEGO heads**

In this paper we present the SIMCO (SIMilarity-based object COnting approach which is entirely agnostic i.e. with no need for any *ad-hoc* class-specific fine-tuning and multi-class i.e. finding different types of repeated patterns. Two main ideas characterize SIMCO

First every object to be counted is considered as a specialization of a basic 2D shape: this is particularly true with many and small objects (see in above Fig: LEGO heads can be approximated as circles). SIMCO incorporates this idea building upon the novel Mask-RCNN-based classifier fine-tuned just once on a novel synthetic shape dataset *InShape*

The second idea is that leveraging on the 2D shape approximation of objects; one can naturally perform unsupervised grouping of the detected objects (grouping circles with circles etc discovering *different* types of repeated entities (without resorting to a particular set of classes). SIMCO realizes this with a head branch in the network architecture implementing triplet losses which provides a 64-dim embedding that maps objects close if they share the same shape class plus some appearance attributes. Affinity propagation clustering finds groups over this embedding.


### **Q3. What is Voice-Face Cross-modal Matching and Retrieval?**

#### **Answer:**

Studies in biology and neuroscience have shown that human's appearances are associated with their voices. Both the facial features and voice-controlling organs of individuals are affected by hormones and genetic information. Human beings can recognize this association. For example: when hearing from the phone call we can guess the gender, the approximate age of the person on the other end of the line. When watching an unvoiced TV show We can imagine an approximate voice by observing the face movement of the protagonist. With the recent advances of deep learning face recognition models and speaker recognition models have achieved exceptionally high precision. Can the associations between voices and faces be discovered algorithmically by machines? The research on this problem can benefit a lot of applications such as synchronizing video faces and talking sound generating faces according to voices.

In recent years much research attention has been paid on the voice-face cross-modal learning tasks which have shown the feasibility of recognizing voice-face associations. This problem is generally formulated as a voice-face matching task and the voice-face retrieval task as shown in Figure 1. Given a set of voice audios and faces voice-face matching is to tell which look makes the voice when machine hearing voice audio. Voice-face retrieval is to present a sorted sequence of faces in the order of the

estimated match from a query of voice recording



**Matching:** Who is more likely to make this voice?

**Retrieval:** Rank face images according their relatedness with the voice query.

SVHF is the prior of voice-face cross-modal learning which studies the performance of CNN-based deep network on this problem. The human s baseline for the voice-face matching task is also proposed in the paper. Both the voice to face and the face to voice matching tasks are studied in the Pins and Horiguchi s work which exhibits similar performance on these two tasks. The curriculum learning schedule is introduced in Pins for hard negative mining. Various visualizations of the embedding vectors are presented to show the learned audio-visual associations in Kim s work. DIMNet learns the common representations for faces and voices by leveraging their relationship with some covariates such as gender and nationality. DIMNet obtains an accuracy of 84.12% on the 1:2 matching which exceeds the human level.

Research on this problem is still in the early stage. Datasets used by previous research are always tiny which can t evaluate the generalization ability of models sufficiently. Traditional test schemes based on random tuple mining tend to have low confidence. The benchmark for this problem needs to be established. This paper presents the voice-face cross-modal matching and retrieval framework a dataset from Chinese speakers and a data collection tool. In the frame cross-modal embeddings are learned with CNN-based networks and triplet loss in a voice anchored metric space with L2-Norm constraint. An identity-based example sampling method is adopted to improve the model efficiency. The proposed framework achieves state-of-the-art performance on multiple tasks. For example the result of 1:2 matching tested on 10 million triplets (thousands of people) reached 84.48% which is also higher than DIMNet tested on 189 people. We have evaluated the various modules of the CNN-based framework and provided our recommendations. Even matching and retrieval based on the average of multiple voices and multiple faces are also attempted which can further improve the performance. This task is the simplest way of analyzing video data. Large-scale datasets are used in this problem to ensure the generalization ability required in a real application. The cross-language transfer capability of the model is studied on the voice-face dataset of Chinese speakers we constructed. The series of performance

metrics are presented on the tasks by extensive experiments. The source code of the paper and the dataset collection tool will be published along with the article.

## Q4. What is CenterNet: Object Detection with Keypoint Triplets?

### Answer:

Object detection has been significantly improved and advanced with the help of deep learning especially convolutional neural networks (CNNs). In the current era one of the most popular flowcharts is anchor-based which placed the set of rectangles with pre-defined sizes and regressed them to the desired place with the help of the ground-truth objects. These approaches often need a large number of anchors to ensure the sufficiently high IoU (intersection over union) rate with the ground-truth objects and the size and aspect ratio of each anchor box needs to be manually designed. Also anchors are usually not aligned with the ground-truth boxes which is not conducive to bounding box classification tasks.

To overcome the drawbacks of anchor based approaches a keypoint-based object detection pipeline named CornerNet was proposed. It represented each object by a pair of corner key points which bypassed the need for anchor boxes and achieved the state-of-the-art one-stage object detection accuracy. Nevertheless the performance of CornerNet is still restricted by its relatively weak ability to refer to the global information of an object. That is to say since a pair of corners construct each object the algorithm is sensitive to detect the boundary of objects meanwhile not being aware of which pairs of critical points should be grouped into the objects. Consequently as shown in Figure a it often generates some incorrect bounding boxes most of which could be easily filtered out with complementary information e.g. the aspect ratio.



To address this issue we equip CornerNet with an ability to perceive the visual patterns within each proposed region so that it can identify the correctness of each bounding box by itself. In this paper we present the low-cost yet effective solution named **CenterNet** which explores the central part of the proposal *i.e.* the region that is close to the geometric center with one extra keypoint. Our intuition is that if the predicted bounding box has a high IoU with the ground-truth box then the probability that the center key point in its central region is predicted as the same class is high and vice versa. Thus during inference after the proposal is generated as a pair of corner keypoints we determine if the plan is indeed an object by checking if there is a crucial central point of the same class falling within its central

region. The idea as shown in Figure a is to use a triplet instead of a pair of key points to represent each object.

Accordingly for better detecting the center keypoints and corners we propose two strategies to enrich center and corner information respectively. The first strategy is named as **center pooling** which is used in the branch for predicting the center keypoints. Center pooling helps the center keypoints obtain more recognizable visual patterns within objects which makes the central part of the proposal be better perceived. We achieve this by getting out the max summed response in both horizontal and vertical directions of the center key point on a feature map for predicting center keypoints. The second strategy is named **cascade corner pooling** which equips the original corner pooling module with the ability to perceive internal information. We achieve this by getting out the max summed response in both boundary and inner directions of objects on a feature map for predicting corners. Empirically we verify that such the two-directional pooling method is more stable *i.e.* being more robust to the feature-level noises which contributes to the improvement of both precision and recall.

We evaluate the proposed CenterNet on the MS-COCO dataset one of the most popular benchmarks for large scale object detection. CenterNet with both center pooling and the cascade corner pooling incorporated reports an AP of 47.0% on the test-dev set which outperforms all existing one-stage detectors by the extensive margin. With an average inference time of 270ms using a 52-layer hourglass backbone and 340ms using a 104-layer hourglass backbone per image CenterNet is quite efficient yet closely matches the state-of-the-art performance of the other two-stage detectors.

## Q5. What is Task2Vec: Task Embedding for Meta-Learning?


**Answer:**

The success of Deep Learning hinges in part on the fact that models learned for one task can be used on the other related tasks. Yet no general framework exists to describe and learn relations between tasks. We introduce task2vec embedding the technique to represent tasks as elements of the vector space is based on the Fisher Information Matrix. The norms of the embedding correlates with the complexity of the task while the distance between embeddings captures the semantic similarities between tasks (Fig 1). When other natural distances are available such as taxonomical distance in the biological classification we find that the embedding distance correlates positively with it (Fig 2). Moreover we introduce an asymmetric distance on tasks that correlates with the transferability between tasks.

Computation of the embedding leverages the duality between network parameters (weights and outputs) (activations in a deep neural network (DNN) : Just as the activations of a DNN trained on the complex visual recognition task are the rich representation of the input images we show that the gradients of the weights relative to a task-specific loss are the rich representation of the task itself. Specifically given a task defined by the dataset  $D = \{(x_i, y_i)\}_{i=1}^N$  of labeled samples we feed the data through a pre-trained

reference convolutional neural network which we call *probe network* and compute the diagonal Fisher Information Matrix (FIM) of the network filter parameters to capture the structure of task. Since the architecture and weights of the probe network are fixed the FIM provides the fixed-dimensional representation of the tasks. We show this embedding encodes the difficulty of the tasks characteristics of the input domain and features of the probe network are useful to solve it.

Our task embedding can be used to reason about the space of the tasks and solve meta-tasks. As a motivating example we study the problem of selecting the best pre-trained feature extractor to solve a new task. This can be particularly valuable when there is insufficient data to train or fine-tune a generic model and the transfer of knowledge is essential. task2vec depends solely on the task and ignores interactions with the model which may however play an essential role. To address this we learn about the joint task and model embedding called model2vec in such a way that models whose embeddings are close to a task exhibit excellent performance on the task. We use this to select an expert from the given collection improving performance relative to fine-tuning a generic model trained on ImageNet and obtaining close to the ground-truth optimal selection.



## Q6. What is GLMNet: Graph Learning-Matching Networks for Feature Matching?

**Answer:**

Many problems of interest in computer vision and pattern recognition area can be formulated as a problem of finding consistent correspondences between two sets of features which are known as feature matching problem. Feature set that incorporates the pairwise constraint can be represented via an attribute

---

graph whose nodes represent the unary descriptors of feature points and edges encode the pairwise relationships among different feature points. Based on this graph representation, feature matching can then be reformulated as a graph node matching problem.

Graph matching generally first operates with both node and edge affinities that encode similarities between the node and edge descriptors in two graphs. Then it can be formulated mathematically as an Integral Quadratic Programming (IQP) problem with permutation constraint on related solutions to encode the one-to-one matching constraints. It is known to be NP-hard. Thus many methods usually solve it approximately by relaxing the discrete permutation constraint and finding locally optimal solutions. Also to obtain better node/edge affinities, learning methods have been investigated to determine the more optimal parameters in node/edge affinity computation. Recently, deep learning methods have also been developed for matching problems. The main benefit of deep learning matching methods is that they can conduct visual feature representation, node/edge affinity learning, and matching optimization together in an end-to-end manner. Zanfir et al. propose an end-to-end graph matching model which makes it possible to learn all the parameters of the graph matching process. Wang et al. recently aim to explore graph convolutional networks (GCNs) for graph matching which conducts graph node embedding and matching simultaneously in a unified system.

Inspired by recent deep graph matching methods, in this paper we propose a novel Graph Learning-Matching Network (GLMNet) for graph matching problems. Overall, the main contributions of this paper are three aspects:


First, a critical aspect of (feature) graph matching is the construction of two matching graphs. Existing deep graph matching models generally use fixed structure graphs such as k-NN, Delaunay graph, etc., which thus are not guaranteed to serve the parallel task best. To address this issue, we propose to adaptively learn a pair of optimal graphs for the matching task and integrate *graph learning* and *graph matching* simultaneously in a unified end-to-end network architecture.

Second, the existing GCN based graph matching model adopts the general smoothing based graph convolution operation for graph node embedding, which may encourage the feature embedding of each node becoming more similar to those of its neighboring nodes. This is desirable for graph node labeling or classification tasks, but undesirable for the matching task because extensive smoothing convolution may dilute the discriminatory information. To alleviate this effect, we propose to incorporate a Laplacian sharpening based graph convolution operation for graph node embedding and matching tasks. Laplacian sharpening process can be regarded as the counterpart of Laplacian smoothing which encourages the embedding of each node farther away from its neighbors.

Third, existing deep graph matching methods generally utilize a doubly stochastic normalization for the final matching prediction. This usually ignores the discrete one-to-one matching constraints in matching.

optimization/prediction To overcome this issue we develop a novel constraint regularized loss to further incorporate the one-to-one matching constraints in matching prediction

Experimental results including ablation studies demonstrate the effectiveness of our GLMNet and advantages of devised components including graph learning-matching architecture Laplacian sharpening convolution for discriminative embedding and constraint regularized loss to encode one-to-one matching constraints




## Q7. What is SSAP: Single-Shot Instance Segmentation With Affinity Pyramid?

**Answer:**

The rapid development of Convolutional networks has revolutionized various vision tasks enabling us to move towards a more fine-grained understanding of images Instead of classic bounding-box level object detection or class-level semantic segmentation instance segmentation provides in-depth knowledge by segmenting all the objects and distinguish different object instances Researchers are showing increasing interests in instance segmentation recently

Current state-of-the-art solutions to this challenging problem can be classified into the *proposal-based* and *proposal-free* approaches The proposal-based methods regard it as an extension to the classic object detection task After localizing each object with a bounding box the foreground mask is predicted within each bounding box proposal However the performances of the scheme based methods are highly limited by the quality of the bounding box predictions and the two-stage pipeline also limits the speed of systems By contrast the proposal-free approach has the advantage of its efficient and straightforward design This work also focuses on the proposal-free paradigm



The proposal-free methods mostly start by producing instance-agnostic pixel-level semantic class labels followed by clustering them into the different object instances with particularly designed instance-aware features. However, previous methods mainly treat the two sub-processes as the two separate stages and employ multiple modules which is suboptimal. The mutual benefits between the two sub-tasks can be exploited which will further improve the performance of the instance segmentation. Moreover, employing multiple modules may result in additional computational costs for real-world applications.

To cope with the above issues, this work proposes a single-shot proposal-free instance segmentation method which jointly learns the pixel-level semantic class segmentation and object instance differentiation in a unified model with a single backbone network as shown in Fig. 1. Specifically, for distinguishing different object instances, an affinity pyramid is proposed which can be jointly learned with the labeling of semantic classes. The pixel-pair affinity computes the probability that two pixels belong to the same instance. In this work, the short-range relationships for pixels close to each other are derived with dense small learning windows. Simultaneously, the long-range connections for pixels distant from each other are also required to group objects with large scales or nonadjacent parts. Instead of enlarging the windows, the multi-range relationships are decoupled and long-range connections are sparsely derived from the instance maps with lower resolutions. After that, we propose learning the affinity pyramid at multiple scales along the hierarchy of a U-shape network where the short-range and long-range affinities are effectively learned from the feature levels with the higher and lower resolutions respectively. Experiments in Table 3 show that the pixel-level semantic segmentation and the pixel-pair affinity pyramid based grouping are indeed mutually benefited from the proposed joint learning scheme. The overall instance of segmentation is thus further improved.

Then, to utilize the cues about global context reasoning, this work employs a graph partition method to derive instances from the learned affinities. Unlike previous time-consuming methods, the cascaded graph partition module is presented to incorporate the graph partition process with the hierarchical manner of the affinity pyramid and finally provides both acceleration and performance improvements. Concretely, with the learned pixel-pair affinity pyramid, the graph is constructed by regarding each pixel

as the node and transforming affinities into the edge scores Graph partition is then employed from higher-level lower-resolution layers to the lower-level higher-resolution layers progressively Instance segmentation predictions from the lower resolutions produce confident proposals which significantly reduce node numbers at higher resolutions Thus the whole process is accelerated

## Q8. What is TENER: Adapting Transformer Encoder for Name Entity Recognition?

### Answer:

The named entity recognition (NER) is the task of finding the start and end of an entity in the sentence and assigning a class for this entity NER has been widely studied in the field of natural language processing (NLP) because of its potential assistance in question generation Zhou et al (2017) relation extraction Miwa and Bansal (2016) and coreference resolution Fragkou (2017) Since Collobert et al (2011) various neural models have been introduced to avoid the hand-crafted features Huang et al (2015) ; Ma and Hovy (2016) ; Lample et al

NER is usually viewed as a sequence labeling task the neural models typically contain three components: word embedding layer context encoder layer and decoder layer Huang et al (2015) ; Ma and Hovy (2016) ; Lample et al (2016) ; Chiu and Nichols (2016) ; Chen et al Zhang et al (2018) ; Gui et al (2019b) The difference between various NER models mainly lies in the variance in these components

Recurrent Neural Networks (RNNs) are widely employed in NLP tasks due to its sequential characteristic which is aligned well with the language Specifically bidirectional extended short-term memory networks (BiLSTM) Hochreiter and Schmidhuber (1997) is one of the most widely used RNN structures (Huang et al 2015) was the first one to apply the BiLSTM and the Conditional Random Fields (CRF) Lafferty et al (2001) to sequence the labeling tasks Owing to BiLSTM's high power to learn the contextual representation of words it has been adopted by the majority of the NER models as the encoder Ma and Hovy (2016) ; Lample et al (2016) ; Zhang et al (2018) ; Gui et al

Recently Transformer Vaswani et al (2017) began to prevail in the various NLP tasks like machine translation Vaswani et al (2017) language modeling Radford et al (2018) and pretraining models Devlin et al (2018) The Transformer encoder adopts the fully-connected self-attention structure to model the long-range context which is the weakness of RNNs Moreover the Transformer has better parallelism ability than RNNs However in the NER task Transformer encoder has been reported to perform poorly Guo et al (2019) our experiments also confirm this result Therefore it is intriguing to explore the reason why the Transformer does not work well in the NER task




Figure 1: An example for NER. The relative direction is important in the NER task, because words before “Inc.” are mostly to be an organization, words after “in” are more likely to be time or location. Besides, the relative distance between words is also important, since only continuous words can form an entity, the former “Louis Vuitton” can not form an entity with the “Inc.”.

The first is that the sinusoidal position embedding used in the vanilla Transformer is relative distance sensitive and direction-agnostic but this property will lose when used in the vanilla Transformer. However both the direction and relative distance information are essential in the NER task. For example words after `in` are more likely to be a location or time than words before it and words before `Inc` is most likely to be of the entity type `ORG`. Besides an entity is a continuous span of words. Therefore the awareness of relative distance might help the word better recognizes its neighbor. To endow the Transformer with the ability of directionality and relative distance awareness we adopt direction-aware attention with the relative positional encoding Shaw et al (2018) ; Huang et al (2019) ; Dai et al (2019). We propose a revised relative positional encoding that uses fewer parameters and performs better.

The second is an empirical finding. The attention distribution of the vanilla Transformer is scaled and smooth. But for NER sparse attention is suitable since not all words are necessary to be attended. Given the current word a few contextual words are enough to judge its label. The smooth attention could include some noisy information. Therefore we abandon the scale factor of dot-production consideration and the use of un-scaled and sharp attention.

With the above improvements we can significantly boost the performance of the Transformer encoder for NER.

## Q9. What is Subword ELMo?

**Answer:**


Recently pre-trained language representation has shown to be useful for improving many NLP tasks. Embeddings from Language Models is one of the most outstanding works which uses the character-aware language model to augment word representation.

An essential challenge in training word-based language models is how to control the vocabulary size for better rare word representation. No matter how large the vocabulary is unique words are always insufficiently trained. Besides an extensive vocabulary takes too much time and computational resources for the model to converge. Whereas if the dictionary is too small the out-of-vocabulary (OOV) issue will harm the model performance slowly. To obtain effective word representation Jozefowicz et al (2016) introduce character-driven word embedding using the convolutional neural network (CNN).

However potential insufficiency when modeling word from characters which hold little linguistic sense especially the morphological source Only 86 roles are adopted in English writing making the input too coarse for embedding learning As we argue that for the better representation from a refined granularity the word is too large and character is too small it is natural for us to consider subword units between character and the word levels

Splitting the word into subwords and using them to augment the word representation may recover the latent syntactic or semantic information For example *uselessness* could be divided into the following subwords: Previous work usually considers linguistic knowledge-based methods to tokenize each word into the subwords (namely morphemes) However such treatment may encounter the three main inconveniences First the subwords from linguistic knowledge typically including the morphological suffix prefix and stem may not be suitable for the targeted NLP task Banerjee and Bhattacharyya or mislead the representation of some words like the meaning of *understanding* cannot be formed by *under* and *stand* Second linguistic knowledge including related annotated lexicons or corpora may not even be available for the specific low-resource language Due to these limitations we focus on the computationally motivated subword tokenization approaches in this work

In this paper we propose Embedding from Subword-aware Language Models (ESuLMo which takes subword as input to augment word representation and release a sizeable pre-trained language model research communities Evaluations show that the pre-trained language models of ESuLMo outperform all RNN-based language models including ELMo in terms of PPL and ESuLMo beats state-of-the-art results in three of four downstream NLP tasks



DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview Preparation)

# Day26

## Q1.What is DCGANs (Deep Convolutional Generative Adversarial Networks)?

### Answer:


GANs stands for Generative adversarial networks which is introduced by Ian Goodfellow in 2014 GANs is entirely new way of teaching computers how they do complex tasks through a generative process

### GANs have two components

- A **Generator** (An artist) neural network
- A **Discriminator** (An art critic) neural network

**Generator** (An artist) generates an image **Generator** does not know anything about the real images and learns by interacting with the **Discriminator** The **Discriminator** (An art critic) determines whether an object is “*real*” and “*fake*” usually represented by a value close to 1 or 0

### High-Level DCGAN Architecture Diagram



Original DCGAN architecture Unsupervised Representation Learning with Deep Convolutional Generative Adversarial Networks have four convolutional layers for **Discriminator** and “four fractionally-strided convolutions layers for **Generator**.




Figure 1: DCGAN generator used for LSUN scene modeling. A 100 dimensional uniform distribution  $Z$  is projected to a small spatial extent convolutional representation with many feature maps. A series of four fractionally-strided convolutions (in some recent papers, these are wrongly called deconvolutions) then convert this high level representation into a  $64 \times 64$  pixel image. Notably, no fully connected or pooling layers are used.

## The Discriminator Network

The **Discriminator** is a “*art critic*” who tries to distinguish between “real” and “fake” images. This is a convolutional neural network (CNN) for image classification.

The **Discriminator** is 4 layers of strided convolutions with batch normalization except its input layer and leaky ReLU activations. **Leaky ReLU** helps the gradients flow easier through the architecture.

## The Generator Network

The **Generator** is “An artist” who tries to create an image that looks as “*real*” as possible to fool **Discriminator**.

The **Generator** is four layers of fractional-strided convolutions with batch normalization except its input layer and uses **Hyperbolic Tangent (*tanh*)** activation in the final output layer and **Leaky ReLU** in rest of the layers.

## Training of DCGANs

**The following steps are repeated in training**

- First **Generator** creates some new examples
- And the **Discriminator** is trained using real data and generated data

- After **Discriminator** has been trained models are trained together
- The **Discriminator**'s weights are frozen but its gradients are used in **Generator** model so that **Generator** can update its weights

## Q2. Explain EnAET.

**Answer:**

### **EnAET: Self-Trained Ensemble AutoEncoding Transformations for Semi-Supervised Learning**

Deep neural network has shown its sweeping successes in learning from large-scale labeled datasets like ImageNet. However such successes hinge on the availability of large amount of labeled examples that are expensive to collect. Moreover deep neural networks usually have large number of parameters that are prone to over-fitting. Thus we hope that semi-supervised learning can not only deal with limited labels but also alleviate the over-fitting problem by exploring unlabeled data. In this paper we successfully prove that both goals can be achieved by training the semi-supervised model built upon self-supervised representations.

Semi-Supervised Learning (SSL) has been extensively studied due to its great potential for addressing the challenge with limited labels. Most state-of-the-art approaches can be divided into two categories. One is confident predictions which improves a model's confidence by encouraging low entropy prediction on unlabeled data. The other category imposes consistency regularization by minimizing discrepancy among the predictions by different models. The two approaches employ reasonable objectives since good models should make confident predictions that are consistent with each other.

On the other hand a good model should also recognize the object even if it is transformed in different ways. With deep networks this is usually achieved by training a model with augmented labeled data. However unsupervised data augmentation is preferred to explore effect of various transformations on unlabeled data. For this reason we will show that self-supervised representations learned from auto-encoding the ensemble of spatial and non-spatial transformations can play a key role in significantly enhancing semi-supervised models. To this end we will present an Ensemble of Auto-Encoding Transformations (AETs) to self-train semi-supervised classifiers with various transformations by combining the advantages of both existing semi-supervised approaches and the newly developed self-supervised representations.

Our contributions are summarized as follows:

- We propose first method that employs ensemble of both spatial and non-spatial transformations from both labeled and unlabeled data in the self-supervised fashion to train a semi-supervised network
- We apply an ensemble of AETs to learn robust features under various transformations and improve the consistency of the predictions on transformed images by minimizing their KL divergence
- We demonstrate EnAET outperforms the state-of-the-art models on all benchmark datasets in both semi-supervised and fully-supervised tasks
- We show in the ablation study that exploring an ensemble of transformations plays a key role in achieving new record performances rather than simply applying AET as a regularizer

### Q3. What is Data Embedding Learning?

#### Answer:


Unsupervised word embeddings have become basis for word representation in NLP tasks. Models such as skip-gram and Glove capture statistics of large corpus and have good properties that corresponds to semantics of word. However there are certain problems with unsupervised word embeddings such as difficulty in modeling some fine-grained word semantics. For e.g. words in the same category but with different polarities are often confused because those words share common statistics in the corpus.

In supervised NLP Natural Language Processing tasks these unsupervised word embeddings are often used in one of 2 ways: keeping fixed or using as initialization fine-tuning. The decision is made based on amount of available training data in order to avoid overfitting. Nonetheless underfitting with keeping fixed and certain degree of overfitting with fine-tuning is inevitable. Because this all are none optimization of word embeddings lacks control over the learning process embeddings are not trained to an optimal point which can result in suboptimal task performance.

In this paper we propose delta embedding learning the novel method that aims to address above problems together: using regularization to find optimal fine-tuning of word embeddings. Better task performance can be reached with properly optimized embeddings. At the same time regularized fine-tuning effectively combines semantics from supervised learning and unsupervised learning which addresses some limitations in unsupervised embeddings and improves quality of embeddings.

Unlike retrofitting which learns directly from lexical resources our method provides the way to learn word semantics from supervised NLP Natural Language Processing tasks. Embeddings usually become task-specific and lose its generality when trained along with the model to maximize a task objective. Some approach tried to learn reusable embeddings from NLP Natural Language Processing tasks include multi-task learning where one predict context words and external labels at the same time and

specially designed gradient descent algorithms for fine-tuning. Our method learns reusable supervised embeddings by fine-tuning unsupervised embeddings on supervised task with a simple modification. The method also makes it possible to examine and interpret the learned semantics.



The aim of a method is to combine the benefits of unsupervised learning and supervised learning to learn better word embeddings. Unsupervised word embeddings like skip-gram trained on large corpus like Wikipedia gives good-quality word representations. We use such embedding  $\mathbf{w}_{unsup}$  as the starting point and learn a delta embedding  $\mathbf{w}_\Delta$  on top of it:

$$\mathbf{w} = \mathbf{w}_{unsup} + \mathbf{w}_\Delta \quad (1)$$

The unsupervised embedding  $\mathbf{w}_{unsup}$  is fixed to preserve good properties of the embedding space and word semantics learned from large corpus. Delta embedding  $\mathbf{w}_\Delta$  is used to capture discriminative word semantics from supervised NLP Natural Language Processing tasks and is trained together with model for the supervised task. In order to learn useful word semantics rather than task-specific peculiarities that results from fitting or overfitting the specific task we impose L21 loss one kind of structured regularization on  $\mathbf{w}_\Delta$ :

$$loss = loss_{task} + c \sum_{i=1}^n \left( \sum_{j=1}^d w_{\Delta ij}^2 \right)^{\frac{1}{2}} \quad (2)$$

The regularization loss is added as extra term to loss of supervised task

The effect of L21 loss on  $w$  has straightforward interpretation: to minimize total moving distance of word vectors in embedding space while reaching optimal task performance. The L2 part of a regularization keeps change of word vectors small so that it does not lose its original semantics. The L1 part of regularization induces sparsity on delta embeddings that only small number of words get non-zero delta embeddings while majority of words are kept intact. The combined effect is selective fine-tuning with moderation: delta embedding capture only significant word semantics that is contained in the training data of a task while absent in the unsupervised embedding.

## Q4. Do you have any idea about Rookie?

### Answer:

#### Rookie: A unique approach for exploring news archives

News archives offer the rich historical record. But if the reader or the journalist wants to learn about new topic with a traditional search engine they must enter query and begin reading or skimming old articles one-by-one slowly piecing together intricate web of people organizations events places topics concepts and social forces that make up the news.

We propose Rookie which began as attempt to build a useful tool for journalists. With Rookie a user's query generates an interactive timeline a list of important related subjects and summary of matching articles all displayed together as a collection of interactive linked views. Users click and drag along the timeline to select certain date ranges automatically regenerating the summary and subject list at interactive speed. The cumulative effect: users can fluidly investigate complex news stories as they evolve across time. Quantitative user testing shows how this system helps users better understand complex topics from documents and finish a historical sensemaking task 37% faster than with a traditional interface. Qualitative studies with student journalists also validate the approach.

We built the final version of Rookie following eighteen months of iterative design and development in consultation with reporters and editors. Because the system aimed to help real-world journalists the software which emerged from the design process is dramatically different from similar academic efforts. Specifically, Rookie was forced to cope with limitations in the speed accuracy and interpretability of current natural language processing techniques. We think that understanding and designing around such limitations is vital to successfully using NLP in journalism applications; a topic which to our knowledge has not been explored in prior work at the intersection of two fields.

### How it works?


At any given time Rookie's state is defined with the **user selection state** the triple **Q F T** where:

- **Q** is the free text query string e.g. Bashar al-Assad
- **F** is related subject string e.g. 30 years or is null
- **T** is time-span e.g. Mar 2000 Sep 2000 ; by default this is set to span of publication dates in the corpus

Users first interact with Rookie by entering a query **Q** into a search query bar using a web browser. For example in below figure a user seeking to understand the roots of the Syrian civil war has entered **Q** = Bashar al-Assad. In response Rookie renders interactive time series visualization showing the frequency of matching documents from the corpus a list of subjects in the matching documents called subjects-sum and a textual summary of those documents called sentence-sum. In this example the corpus is the collection of *New York Times* world news articles from 1987 to 2007 that contain the string Syria. All of the country-specific examples in this study are subsets of the same *New York Times* LDC corpus.

After entering **Q** user might notice that Bashar al-Assad is mainly mentioned from 1999 onwards. To investigate they might adjust time series slider to a spike in early mentions of Bashar al-Assad **T** =Mar 2000 Sep 2000

When user adjusts **T** to Mar 2000 Sep 2000 sentence-sum and subjects-sum change to reflect the new timespan below figure c subjects-sum now shows subjects like TRANSITION IN SYRIA 2Formatting from NYT section header style President Assad eldest son and 30 years which are important to **Q** during **T** Bashar al-Assad's father ruled for 30 years



- A user enters **Q** = "Bashar al-Assad" in order to learn more about the Syrian civil war

At this point user might explore further by investigating related subject **F** = President Assad clicking to select sentence-sum now attempts to summarize the relationship between **Q**= Bashar al-Assad and **F** = President Assad during **T** =Mar 2000 Sep 2000 figure d For instance sentence-sum now shows the sentence: Bashar al-Assad was born on Sept 11 1965 in Damascus the third of President Assad s five children If a user wants to understand this sentence in context they can click sentence which opens underlying document in the modal dialog

**F** and **Q** are assigned red and blue colors throughout interface allowing user to quickly scan for information Bolding **Q** and **F** give additional clarity and helps ensure that Rookie still work for colorblind users

This example demonstrates how Rookie s visualization and summarization techniques work together to offer linked views of the underlying corpus Linked views a k a multiple coordinated views interfaces are common tools for structured information: each view displays the same selected data in a different dimension e g a geographic map of a city which also shows a histogram of housing costs when a user selects a neighborhood In Rookie s case linked views display different levels of resolution The time series visualization offers a **temporal view** of query-responsive documents subjects-sum displays a medium-level **lexical view** of important subjects within the documents and sentence-sum displays a low-level **text view** of parts of the underlying documents The documents themselves available by clicking extracted sentences offer the most detailed level of zoom Thus Rookie supports the commonly advised visualization pathway: overview first zoom and filter and details on demand Shneiderman1996

Note that we use term **summarization** to mean selecting short text or sequence of short texts to represent a body of text By this definition both subjects-sum and sentence-sum are a form of summarization as each offers a textual representation of the corpus albeit at two different levels of resolution phrases and sentences

## Q5.SECRET: Semantically Enhanced Classification of Real-world Tasks

### Answer:

Significant progress has been made in NLP natural language processing and supervised machine learning ML algorithms over the past 2 decades NLP successes include machine translation speech or emotion or sentiment recognition machine reading and social media mining Hence NLP Natural Language Processing is beginning to become widely used in real-world applications that include either text or speech Supervised Machine Learning ML algorithms excel at modeling the data-label relationship while maximizing performance and minimizing energy consumption and latency

Supervised ML algorithms train on feature-label pairs to model the application of interest and predict labels. The label involves semantic information and uses this information through vector representations of words to find novel class within the dataset. Karpathy and Fei-Fei generate figure captions based on the collective use of image datasets and word embeddings. Such studies indicate that data feature and semantic relationship correlate well. However, current supervised Machine Learning ML algorithms do not utilize such correlations in the decision-making or prediction process. Their decisions are based on the feature-label relationship while neglecting significant information hidden in labels, i.e., meaning-based semantic relationships among labels. Thus, they are not able to exploit synergies between feature and semantic space.

In this article, we show how above synergies can be exploited to improve prediction performance of Machine Learning ML algorithms. Our method, called SECRET, combines vector representations of label in semantic space with available data in feature space within various operations, e.g., ML hyperparameter optimization and confidence score computation, to make final decisions and assign labels to the datapoints. Since SECRET does not target any particular Machine Learning ML algorithm or data structure, it is widely applicable.

The main contributions of this article are as follows:

- We introduce the dual-space Machine Learning ML decision process called SECRET. It combines new dimension semantic space with traditional single-space classifiers that operate in feature space. Thus, SECRET not only utilizes available data-label pairs but also takes advantage of meaning-based semantic relationships among labels to perform classification for the given real-world task.
- We demonstrate the general applicability of SECRET on various supervised Machine Learning ML algorithms and wide range of datasets for various real-world tasks.
- We demonstrate advantages of SECRET's new dimension semantic space through detailed comparisons with traditional Machine Learning ML approaches that have same processing and information except semantic resources.
- We compare the semantic space Machine Learning ML model with traditional approaches. We shed light on how SECRET builds semantic space component and its impact on overall classification performance.

## Q6. Semantic bottleneck for computer vision tasks

**Answer:**

Image-to-text tasks have made tremendous progress since the advent of deep learning DL approaches. The work presented in this paper builds on these new types of image-to-text functions to evaluate capacity of textual representations to semantically and fully encode visual content of images for

demanding applications in order to allow prediction function to host semantic bottleneck somewhere in its processing pipeline. The main objective of semantic bottleneck is to play role of *explanation* of the prediction process since it offers opportunity to examine meaningfully on what ground will further predictions be made and potentially decide to reject them either using human common-sense knowledge and experience or automatically through dedicated algorithms. Such the explainable semantic bottleneck instantiates good tradeoff between prediction accuracy and interpretability.

Reliably evaluating the quality of explanation is not straightforward. In this work we propose to evaluate the explainability power of the semantic bottleneck by measuring its capacity to detect the failure of the prediction function either through an automated detector as or through human judgment. Our proposal to generate surrogate semantic representation is to associate the global and generic textual image description caption and visual quiz in the form of small list of questions and answers that are expected to refine contextually the generic caption. The production of this representation is adapted to vision task and learned from the annotated data.




Figure : Semantic bottleneck approach: images are replaced by purely but rich textual representations for tasks such as multi-label classification or image retrieval

## Q7. Gender Bias in Neural Natural Language Processing

### Answer:

Natural language processing (NLP) with neural networks has grown in importance over last few years. They provide state-of-the-art SOTA models for tasks like coreference resolution, language modeling and machine translation. However, since these models are trained on human language texts, natural question is whether they exhibit bias based on gender or other characteristics and if so how should this bias be mitigated. This is a question that we address in this paper.

Prior work provides evidence of bias in autocomplete suggestions and differences in accuracy of speech recognition based on gender and dialect on popular online platforms Word embeddings initial pre-processors in many Natural Language Processing NLP tasks embed words of a natural language into a vector space of limited dimension to use as their semantic representation Observed that popular word embeddings including  $\text{ord}$  exhibit gender bias mirroring stereotypical gender associations such as the eponymous "Man is to computer programmer as a Woman is to homemaker

Yet the question of how to measure bias in general way for neural Natural Language Processing NLP tasks has not been studied Our first contribution is general benchmark to quantify gender bias in variety of neural Natural Language Processing NLP tasks Our definition of bias loosely follows idea of causal testing: matched pairs of individuals that differ in only the targeted concept like gender are evaluated by the model and the difference in outcomes or scores is interpreted as causal influence of the concept in scrutinized model The definition is parametric in scoring function and the target concept Natural scoring functions exist for number of neural natural language processing NLP tasks

We instantiate definition for two important tasks coreference resolution and language modeling Coreference resolution is a task of finding words and expressions referring to the same entity in the natural language text The goal of language modeling is to model distribution of word sequences For neural coreference resolution models we measure gender coreference score disparity between gender-neutral words and gendered words like the disparity between doctor and he relative to doctor and she pictured as edge weights in below Fig For language models we measure disparities of emission log-likelihood of gender-neutral words conditioned on gendered sentence prefixes as is shown in below Fig Our empirical evaluation with state-of-the-art SOTA neural coreference resolution and textbook RNN-based language models trained on benchmark datasets finds gender bias in these models Note that these results have practical significance Both coreference resolution and language modeling are core natural language processing NLP tasks in that they form the basis of many practical systems for information extraction text generation speech recognition and machine translation

Next we turn our attention to mitigating the bias Bolukbasi et al [2016](#) introduced the technique for *debiasing* word embeddings which has been shown to mitigate unwanted associations in analogy tasks while preserving embedding's semantic properties Given their spread use a natural question is whether this technique is sufficient to eliminate bias from downstream tasks like coreference resolution and language modeling As our 2nd contribution we explore this question empirically We find that while technique does reduce bias residual bias is considerable We further discover that debiasing models that make use of embeddings that are co-trained with their other parameters exhibit a significant drop in accuracy

		$A$	$B$	$\ln \Pr[B   A]$
1 $\square$ :	The <u>doctor</u> ran because <u>he</u> is late.	<u>He</u> is a	<u>doctor</u> .	-9.72
1 $\circ$ :	The <u>doctor</u> ran because <u>she</u> is late.	<u>She</u> is a	<u>doctor</u> .	-9.77
2 $\square$ :	The <u>nurse</u> ran because <u>he</u> is late.	<u>He</u> is a	<u>nurse</u> .	-8.99
2 $\circ$ :	The <u>nurse</u> ran because <u>she</u> is late.	<u>She</u> is a	<u>nurse</u> .	-8.97
	(a) Coreference resolution			
			(b) Language modeling	

Figure 1: Examples of gender bias in coreference resolution and language modeling as measured

## Q8. DSReg: Using Distant Supervision as a Regularizer

**Answer:**

Consider the following sentences in a text classification task in which we want to identify sentences containing revenue values:

- S $\square$  *The revenue of education sector is 1 million. positive*
- S2 $\square$  *The revenue of education sector increased a lot. hard-negative*
- S $\square$  *Education is a fundamental driver of global development. easy-negative*

S1 is a positive example since it contains precise value for the revenue while both S2 and S3 are negative because they do not have the concrete information of revenue value. However since S2 is highly similar to S1 it is hard for a binary classifier to make a correct prediction on S2. As another example in reading comprehension tasks like NarrativeQA Ko isk et al 2018 or MS-MARCO Nguyen et al 2016 truth answers are human-generated ones and might not have exact matches in the original corpus. A commonly adopted strategy is to first locate similar sequences from the original corpus using a ROUGE-L threshold and then treat these sequences as a positive training examples. Sequences that are semantically similar but right below this threshold will be treated as negative examples and thus inevitably introduce massive noise in training.

This problem is ubiquitous in a wide range of NLP tasks i.e. when some of the negative examples are highly similar to the positive examples. We refer to these negative examples as *hard-negative examples* for the rest of this paper. Also we refer to those negative examples that are not similar to the positive examples as *easy-negative examples*. If hard-negative examples significantly outnumber positive ones features that they share in common will contribute significantly to the negative example category.

To tackle this issue we propose using the idea of distant supervision to regulate the training. We first harvest hard-negative examples using distant supervision. This process can be done by the method as simple as using word overlapping metrics e.g. ROUGE BLEU or whether a sentence contains a certain keyword. With the harvested hard-negative examples we transform the original binary classification task to a multi-task learning task in which we jointly optimize the original target objective of distinguishing positive examples from negative examples along with an auxiliary objective of distinguishing hard-negative examples plus positive examples from easy-negative examples. For a neural network model this goal can be easily achieved by using different softmax functions to readout the final-layer representations. In this way both the difference and the similarity between positive examples and hard-negative examples can be captured by the model. It is worth noting that there are several key differences between this work and the mainstream works in distant supervision for relation extraction at both the setup level and the model level. In traditional work on distant supervision for relation extraction there is no training data initially and the distant supervision is used to get positive training data. In our case we do have a labeled dataset from which we retrieve hard-negative examples using the distant supervision.

## **Q9. What is Multimodal Emotion Classification?**

### **Answer:**

Emotion is any experience characterized by intense mental activity and certain degree of pleasure or displeasure. It primarily reflects all aspects of our daily lives playing the vital role in our decision-making and relationships. In recent years there have been growing interest in a development of technologies to recognize emotional states of individuals. Due to escalating use of social media emotion-rich content is being generated at increasing rate encouraging research on automatic emoji classification techniques. Social media posts are mainly composed of images and captions. Each of modalities has very distinct statistical properties and fusing these modalities helps us learn useful representations of data. Emotion recognition is the process that uses low-level signal cues to predict high-level emotion labels. With rapid increase in usage of emojis researchers started using them as labels to train classification models. A survey conducted by secondary school students suggested that use of emoticons can help reinforce the meaning of the message. Researchers found that emoticons when used in conjunction with written message can help to increase the intensity of its intended meaning.




Emojis are being used for visual depictions of human emotions. Emotions help us to determine interactions among human beings. The context of emotions specifically brings out complex and bizarre social communication. These social communications are identified as judgment of other person's mood based on his emoji usage. Rajhi [2017](#). According to the study made by Rajhi et al. Rajhi [2017](#), the real-time use of emojis can detect the human emotions in different scenes, lighting conditions as well as angles in real-time. Studies have shown that emojis when embedded with text to express emotion make tone and tenor of message clearer. This further helps in reducing or eliminating the chances of misunderstanding often associated with plain text messages. A recent study proved that co-occurrence allows users to express their sentiment more effectively.

Psychological studies conducted in the early 80s provide us strong evidence that human emotion is closely related to the visual content. Images can both express and affect people's emotions. Hence it is intriguing and important to understand how emotions are conveyed and how they are implied by visual content of images. With this as the reference many computer scientists have been working to relate and learn different visual features from images to classify emotional intent. Convolutional Neural Networks (CNNs) have served as baselines for major Image processing tasks. These deep Convolutional Neural

Networks CNNs combine the high and low-level features and classify images in an end-to-end multi layer fashion

Earlier most researchers working in field of social Natural Language Processing NLP have used either textual features or visual features but there are hardly any instances where researchers have combined both these features Recent works by Barbieri et al s Illendula et al s on multimodal emoji prediction and Apostolova et al work on information extraction fusing visual and textual features have shown that combining both modalities helps in improving the accuracies While a high percentage of social media posts are composed of both images and caption researchers have not looked at multimodal aspect for emotion classification Consider post in above Firgure where a user is sad and posts the image when a person close to him leaves him The image represents the disturbed heart and has the textual description sometimes tough if your love leaves you sad hurting conveys a sad emotion Similarly emoji used conveys emotion of being depressed We hypothesize that all the modalities from the social media post including visual textual and emoji features contribute to predicting emotion of the user Consequently we seek to learn importance of different modalities towards emotion prediction task



**DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview  
Preparation)**

**# Day27**

## Q1. Learning to Caption Images with Two-Stream Attention and Sentence Auto-Encoder

### Answer:

Understanding the world around us via visual representations and communicating this extracted visual information via language is one of the fundamental skills of human intelligence. The goal of recreating a similar level of intellectual ability in artificial intelligence AI has motivated researchers from computer vision and natural language communities to introduce the problem of automatic image captioning. Image captioning which is to describe the content of an image in the natural language has been an active area of research and widely applied to video and image understanding in multiple domains. The ideal model for this challenging task must have two characteristics: understanding of an image content well and generating descriptive sentences which is coherent with the image content. Many image captioning methods propose various encoder-decoder models to satisfy these needs where encoder extracts the embedding from an image and decoder generates the text based on the embedding. These two parts are typically built with a Convolutional Neural Network CNN and a Recurrent Neural Network RNN respectively.



**Baseline:** a polar bear standing on top of a wooden surface.

**Two-Stream Attention:** a polar bear standing **in front** of a **frisbee**.

**Final model:** a polar bear **sitting** on the ground **with a frisbee**.

Fig : This Image captioning decoder with two-stream attention and the Auxillary decoder finds and localizes relevant words better than general caption-attention baselines

One of the challenging question in encoder-decoder architectures is how to design interface that controls the information flow between a CNN and RNN. While early work employs static representation for interface such that the CNN compresses an entire image into a fixed vector and an RNN decodes representation into natural language sentences this strategy is shown to perform poorly when target sentence is prolonged and the image is reasonably cluttered. Inspired from Xu *et al* propose the powerful dynamic interface namely attention mechanism that identifies relevant parts of a image embedding to estimate the next word. RNN model then predicts the word based on the context vector associated with the related image regions and the previously generated words. The attentional interface is shown to obtain significant performance improvements over static one and


since then it has become the key component in all state-of-the-art SOTA image captioning models Although this interface is substantially effective and flexible it comes with critical shortcoming

Nevertheless visual representations that are learned by Convolutional Neural Network CNNs have been rapidly improving the state-of-the-art SOTA recognition performance in various image recognition tasks in past few years They can still be inaccurate when applied to noisy images and perform poorly to describe their visual contents Such noisy representations can lead to incorrect association between words and images regions and potentially drive the language model to poor textual descriptions To address these shortcomings we propose two improvements that can be used in standard encoder-decoder based image captioning framework

First we propose the novel and powerful attention mechanism that can more accurately attend to relevant image regions and better cope with ambiguities between words and image regions It automatically identifies *latent categories* that capture high-level semantic concepts based on visual and textual cues as illustrated in the second fig The two-stream attention is modeled as a neural network where each stream specializes in orthogonal tasks: the first one soft-labels each image region with the latent categories and the second one finds the most relevant area for each group Then their predictions are combined to obtain a context vector that is passed to a decoder

Second inspired by sequence-to-sequence seq2seq machine translation methods we introduce a new regularization technique that forces the image encoder coupled with the attention block to generate a more robust context vector for the following RNN model In particular we design and train an additional seq2seq sentence auto-encoder model SAE that first reads in a whole sentence as input generates the fixed dimensional vector then the vector is further used to reconstruct input sentence SAE is trained to learn structure of the input sentence space in an offline manner Once it is trained we freeze its parameters and incorporate *only* its decoder part SAE-Dec to our captioning model

IC as the auxiliary decoder branch SAE-Dec is employed along with the original image captioning decoder IC-Dec to output target sentences during training and removed in test time We show that the proposed SAE-Dec regularizer improves the captioning performance for IC-Dec and does not bring any additional computation load in test time



## Q2.Explain PQ-NET.

**Answer:**

PQ-NET: A Generative Part Seq2Seq Network for 3D Shapes Learning generative models of 3D shapes is a crucial problem in both computer vision and computer graphics. While graphics are mainly concerned with 3D shape modeling in inverse graphics a significant line of work in computer vision one aims to infer often from a single image a disentangled representation wrt 3D shape and scene structures. Lately there has been a steady stream of works on developing deep neural networks for 3D shape generation using different shape representations e.g voxel grids point clouds meshes and most recently implicit functions. However most of these works produce *unstructured* 3D shapes even though object perception is generally believed to be a process of a *structural understanding* i.e. to infer shape parts their compositions and inter-part relations.

In this paper we introduce a deep neural network that represents and generates 3D shapes via *sequential part assembly* as shown in both Fig. In a way we regard assembly sequence as a sentence which organizes and describes the parts constituting the 3D shape. Our approach is inspired in part by the resemblance between speech and shape perception as suggested by the seminal work of Biederman on recognition-by-components RBC. Another related observation is that the phrase structure rules for language parsing first introduced by Noam Chomsky take on the view that sentence is both a linear string of words and a hierarchical structure with phrases nested in phrases. In the context of shape structure presentations our network adheres to linear part orders while other works have opted for *hierarchical* part organizations.




Fig 1: Our network PQ-NET learns 3D shape representation as a *sequential part assembly*. It can be adapted to generative tasks such as random 3D shape generation, single-view 3D reconstruction from RGB or depth images, and shape completion.




Fig 2: The architecture of PQ-NET: our part Seq2Seq generative network for 3D shapes

The input to our network is a 3D shape segmented into parts where each part is first encoded into a feature representation using a part autoencoder; see Fig 2 a. The core component of our network is a *Seq2Seq* autoencoder which encodes a sequence of part features into the latent vector of fixed size and the decoder reconstructs the 3D shape one part at the time resulting in sequential assembly; see Fig 2 b. With its part-wise Seq2Seq architecture our network is coined *PQ-NET*. The latent space formed by Seq2Seq encoder enables us to adapt the decoder to perform several generative tasks.

---

including shape autoencoding interpolation new shape generation and single-view 3D reconstruction where all generated shapes are composed of meaningful parts

As training data we take the segmented 3D shapes from PartNet which was built on ShapeNet It is important to note that we do not enforce any particular part order or consistency across input shapes The shape parts are always specified in the file following some linear order in the dataset; our network takes whatever part order that is in a shapefile We train the part and Seq2Seq autoencoders of PQ-NET separately either per shape category or across all shape categories of PartNet

Our part autoencoder adapts IM-NET to encode shape parts rather than whole shapes with the decoder producing an implicit field The part Seq2Seq autoencoder follows a similar architecture as the original Seq2Seq network developed for machine translation Specifically the encoder is a bidirectional stacked recurrent neural network RNN that inputs two sequences of part features in opposite orders and outputs a latent vector The decoder is also a stacked RNN which decodes the latent vector representing the whole shape into a sequential part assembly

PQ-NET is the first *fully generative* network that learns a 3D shape representation in the form of sequential part assembly The only prior part sequence model was 3D-PRNN which generates part boxes not their geometry our network jointly encodes and decodes part structure and geometry PQ-NET can be easily adapted to various generative tasks including shape autoencoding novel shape generation structured single-view 3D reconstruction from both RGB and depth images and shape completion Through extensive experiments we demonstrate that performance and output quality of our network is comparable or superior to state-of-the-art generative models including 3D-PRNN IM-NET and StructureNet

### Q3. What is EDIT?

#### Answer:

EDIT: Exemplar-Domain Aware Image-to-Image Translation

A scene can be expressed in various manners using sketches semantic maps photographs and painting artworks to name just a few The way that one portrays the scene and expresses his/her vision is the so-called style which can reflect the characteristic of either a class/domain or a specific case Image-to-image translation I2IT refers to the process of converting an image  $I$  of a particular style to another of the target style  $S_t$  with the content preserved Formally seeking the desired translator  $T$  can be written in the following form:

$$\min \mathcal{C}(I_t, I) + \mathcal{S}(I_t, S_t) \quad \text{With} \quad I_t := \mathcal{T}(I, S_t), \quad (1)$$

where  $\mathcal{C}(I_t, I)$  is to measure the content difference between the translated  $I_t$  and the original  $I$ , while  $\mathcal{S}(I_t, S_t)$  is to enforce the style of  $I_t$  following that indicated by  $S_t$ .



Figure 1: Several results by the proposed EDIT Our EDIT can take arbitrary exemplars as reference for translating images across multiple domains including photo-painting shoe-edge and semantic map-facade in *one* model

With the emergence of deep techniques a variety of I2IT strategies have been proposed with excellent progress made over the last decade In what follows we briefly review contemporary works along two main technical lines *i.e.* one-to-one translation and many-to-many translation

*One-to-one Translation.* Methods in this category aim at mapping images from a source domain to a target domain Benefiting from the generative adversarial networks GANs the style of translated results satisfies the distribution of the target domain  $Y$  achieved by  $S(I_t) \approx D(I_t|Y)$  where  $D(I_t|Y)$  represents a discriminator to distinguish if  $I_t$  is real with respect to  $Y$  An early attempt by Isola *et al.* uses conditional GANs to learn mappings between two domains The paired data supervise the content preservation *i.e.*  $C(I_t|I) = C(I_t|I_{gt})$  with  $I_{gt}$  the ground-truth target However in real-world situations acquiring such paired datasets if not impossible is impractical To alleviate the pressure from data inspired by the concept of cycle consistency cycleGAN in an unsupervised fashion was proposed which adopts  $C(I_t|I) = C(FY \rightarrow X, FX \rightarrow Y|I)$  with  $FX \rightarrow Y$  the generator from domain  $X$  to  $Y$  and  $FY \rightarrow X$  the reverse one Afterward StarGAN further extends the translation between two domains that cross multiple areas in a single model Though the effectiveness of the mentioned methods has been witnessed by a broad spectrum of specific applications such as photo-

caricature making up-makeup removal and face manipulation their main drawback comes from the nature of deterministic uncontrollable one-to-one mapping

*Many-to-many Translation.* The goal of approaches in this class is to transfer the style controlled by an exemplar image to a source image with content maintained Arguably the most representative work goes to which uses the pre-trained VGG16 network to extract the content and style features then transfer style information by minimizing the distance between Gram matrices constructed from the generated image and the exemplar  $E$  say  $S \leftarrow I_t S := S \text{ Gram } I_t \text{ Gram } E$  Since then numerous applications on the 3D scene face swap portrait stylization and font design have been done Furthermore several schemes have also been developed towards relieving limitations in terms of speed and flexibility For example to tackle the requirement of training for every new exemplar style Shen *et al.* built a meta-network which takes in the style image and produces a corresponding image transformation network directly Risser *et al.* proposed the histogram loss to improve the training instability Huang and Belongie designed a more suitable normalization manner *i.e.* AdaIN for style transfer Li *et al.* replaced the Gram matrices with an alternative distribution alignment manner from the perspective of domain adaption Johnson *et al.* trained the network with a specific style image and multiple content images while keeping the parameters at the inference stage Chen *et al.* introduced a style-bank layer containing several filter-banks each of which represents a specific style Gu *et al.* proposed a style loss to make parameterized and non-parameterized methods complement each other Huang *et al.*designed a new temporal loss to ensure the style consistency between frames of a video Also to mitigate the deterministic nature of one-to-one translation several works for instance advocated to separately take care of content  $c | I$  and style  $s | I$  subject to  $I \simeq c | I \circ s | I$  with  $\circ$  the combined operation They manage to control the translated results by combining the content of an image with the style of the target *i.e.*  $c | I \circ s | E$  Besides one domain pair requires one independent model their performance as observed from comparisons is inferior to our method in visual quality diversity and style preservation Please see the above Fig For example produced by our approach that handles multiple domains and arbitrary exemplars in a unified model

## Q4. What is Doctor2Vec?

**Answer:**

Doctor2Vec: Dynamic Doctor Representation Learning for Clinical Trial Recruitment

The rapid growth of electronic health record EHR data and other health data enables the training of complex deep learning models to learn patient representations for disease diagnosis risk prediction

patient subtyping and medication recommendation. However, almost all current works focus on modeling patients. Deep neural networks for doctor representation learning are lacking.

Doctors play pivotal roles in connecting patients and treatments, including recruiting patients into clinical trials for drug development and treating and caring for their patients. Thus, an effective doctor representation will better support a broader range of health analytic tasks. For example, identifying the right doctors to conduct the trial *site selection* to improve the chance of completion of the trials [hurtado2017improving] and doctor recommendation for patients.

In this work, we focus on studying the *clinical trial recruitment* problem using doctor representation learning. Current standard practice calculates the median enrollment rate. Enrollment rate of a doctor is the number of patients enrolled by a doctor to the trial, For the therapeutic area as the predicted enrollment success rate for whole participating doctors, which is often incorrect. Also, some develop a multi-step manual matching process for site selection, which is labor-intensive. Recently, deep neural networks were applied on site selection tasks via static medical concept embedding using only frequent medical codes and simple term matching to trials. Despite the success, two challenges remain open:

- 1 Existing works do not capture the time-evolving patterns of doctors' experience and expertise encoded in EHR data of patients that the doctor have seen;
- 2 Current jobs learn a static doctor representation. However, in practice, given a trial for a particular disease, the doctor's experience of relevant diseases are more important. Hence, the doctor representation should change based on the corresponding trial representation.

To fill the gap, we propose Doctor2Vec, which simultaneously learns i) doctor representations from longitudinal patient EHR data and ii) trial embedding from the multimodal trial description. In particular, Doctor2Vec leverages a dynamic memory network where the observations of patients seen by the doctor are stored as memory while trial embedding serves as queries for retrieving from the mind. Doctor2Vec has the following contributions:

- 1 **Patient embedding as a memory for dynamic doctors representation learning** We represent doctors' evolving experience based on the representations from the doctors' patients. The patient representations are stored as a memory for dynamic doctor representation extraction.
- 2 **Trial embedding as a query for improved doctors selection** We learn hierarchical clinical trial embedding where the unstructured trial descriptions were embedded using BERT [devlin2018bert]. The trial embedding serves as queries of the memory network and will attend over patient representation and dynamically assign weights based on the relevance of doctor experience and trial representation to obtain the final context vector for an optimized doctor representation for a specific test.

We evaluated Doctor2Vec using large scale real-world EHR and trial data for predicting trial enrollment rates of doctors. Doctor2Vec demonstrated improved performance in the site selection task over the best baselines by up to 8.7% in PR-AUC. We also showed that the Doctor2Vec embedding could be transferred to benefit data insufficiency settings including trial recruitment in less populated/newly explored countries or for rare diseases. Experimental results show for the country transfer Doctor2Vec achieved 13.7% relative improvement in PR-AUC over the best baseline. While for embedding transfer to unique disease trials Doctor2Vec made 8.1% relative improvements in PR-AUC over the best benchmark.

## Q5. Explain PAG-Net.

### Answer:


PAG: Progressive Attention Guided Depth Super-resolution Network

A geometric description of a scene, the high-quality depth map is useful in many computer vision applications such as 3D reconstruction, virtual reality, scene understanding, intelligent driving, and robot navigation. Literature mainly contains two classes of techniques for depth information acquisition which are passive methods and active sensors. Firstly, passive methods infer depth maps from the most widely used dense stereo matching algorithms but they are time-consuming. Despite the advances in technology, the depth information from passive methods is still inaccurate in occluded and low-texture regions. The acquisition of high-quality depth maps is more challenging to obtain than RGB images.

Depth acquisition from active sensors has become increasingly popular in our daily life and ubiquitous to many consumer applications due to their simplicity, portability, and inexpensiveness. Unlike passive methods, the depth of a scene can be acquired in real-time and they are more robust in low-textured regions by low-cost sensors such as Time-of-Flight camera and Microsoft Kinect. Current sensing techniques measure depth information of a scene by using echoed light rays from the stage. Time-of-Flight sensor (ToF) is one of the mainstream types which computes depth at each pixel between camera and subject by measuring the round trip time. Although depth-sensing technology has attracted much attention, it still suffers from several quality degradations.

Depth information captured by ToF sensors suffers from low-spatial resolutions e.g.  $176 \times 144$ ,  $200 \times 200$  or  $512 \times 424$  and noise when compared with the corresponding color images. Due to the offset between projector and sensor, depth maps captured by Microsoft Kinect sensors contain structural missing along discontinuities and random missing at homogeneous regions. These issues restrict the use of depth maps in the development of depth-dependent applications. High-quality depth is significant in many computer vision applications. Therefore, there is a need for restoration of

depth maps before using in applications In this work we consider the problem of depth map super-resolution from a given low-resolution depth map and its corresponding high-resolution color image



Existing depth super-resolution DSR methods can be roughly categorized into three groups: filter design-based optimization-based and learning-based algorithms Many of the existing techniques assumed that a corresponding high-resolution color image helps to improve the quality of depth maps and used aligned RGB image as guidance for depth SR However significant artifacts including texture copying and edge blurring may occur when the assumption violated The color texture will be transferred to the super-resolved depth maps if the smooth surface contains rich textures in the corresponding color image Secondly depth and color edges might not align in all the cases Subsequently it leads to ambiguity Hence there is a need for optimal guidance for the high-resolution depth map

Although there have been many algorithms proposed in the literature for the depth super-resolution DSR most of them still suffer from edge-blurring and texture copying artifacts In this paper we offer a novel method for attention guided depth map super-resolution It is based on dense residual networks and involves a unique attention mechanism The attention used here to suppress the texture copying problem arises due to improper guidance by RGB images and transfer only the salient features from the guidance stream The attention module mainly involves providing spatial attention to the guidance image based on the depth features The entire architecture for the example of super-resolution by the factor of 8 is shown in Above Fig

## Q6. An End-to-End Audio Classification System based on Raw Waveforms and Mix-Training Strategy

**Answer:**

Sound is the indispensable medium for information transmission of surrounding environment When some sounds happen such as baby crying glass breaking and so on we usually expect that we can hear sounds immediately even if we are not around In this case an audio classification that aims to

---

predict whether an acoustic event appears has gained significant attention in recent years. It has many practical applications in remote surveillance, home automation, and public security.

In real life, an audio clip usually contains multiple overlapping sounds, and types of sounds are various, ranging from natural soundscapes to human activities. It is challenging to predict a presence or absence of audio events in an audio clip. Audio Set is the common large-scale dataset in this task, which contains about two million multi-label audio clips covering 527 classes. Recently, some methods have been proposed to learn audio tags on this dataset. Among them, a multi-level attention model achieved state-of-the-art SOTA performance, which outperforms Google's baseline. However, the shortcoming of these models is that the input signal is the published bottleneck feature, which causes information loss. Considering that the actual length of sound events is different and the handcrafted features may throw away relevant information at a short time scale, raw waveforms containing more valuable information is a better choice for multi-label classification. In the audio tagging task of DCASE 2017-2018 challenge, some works [5-6] combined handcrafted features with raw waveforms as input signal on a small dataset consisting of 17 or 41 classes. To our knowledge, none of the works proposes an end-to-end network taking raw waveforms as input in the Audio Set classification task.

In this paper, we propose a classification system based on two variants of ResNet, which directly extracts features from raw waveforms. Firstly, we use one-dimension 1D ResNet for feature extraction. Then, two-dimension 2D ResNet with multi-level prediction and attention structure is used for classification. For obtaining better classification performance, further, a mix-training strategy is implemented in our system. In this training process, the network is trained with mixed data, which extends training distribution and then transferred to the target domain using raw data.

In this work, the main contributions are as follows:

1. The novel end-to-end Audio Set classification system is proposed. To best of our knowledge, it is first time to take raw waveforms as input on Audio Set and combine 1D ResNet with 2D ResNet for feature extraction at different time scales.
2. A mix-training strategy is introduced to improve the utilization of limited training data effectively. Experiments show that it is robust in multi-label audio classification compared to the existing data augmentation methods.




Figure 1: Architecture of the end-to-end audio classification network. The raw waveform 1D vector is the input signal. First the 1D ResNet is applied to extract audio features. Then the elements are transposed from  $C \times 1 \times T$  to  $1 \times C \times T$ . Finally a 2D ResNet with a multi-level prediction structure performs audio classification. The output of network has multiple labels and is the mean of multi-level prediction results. The Block is composed of  $n$  bottleneck blocks where  $n$  is related to a number of layers in ResNet.

## Q7. What is Cnak?: Cluster Number Assisted K-means

**Answer:**

Cnak stands for Cluster Number Assisted K-means

In cluster analysis it is required to group the set of data points in a multi-dimensional space so that data points in same group are more similar to each other than to those in other groups. These groups are called clusters. Various distance functions may be used to compute degree of dissimilarity or similarity among these data points. Typically Euclidean distance function is widely used in clustering. This unsupervised technique aims to increase homogeneity in the group and heterogeneity between groups. Several clustering methods with different characteristics have been proposed for different purposes. Some well-known methods include partition-based clustering, hierarchical clustering [Hierarchy1963], spectral clustering [onspectral2001], density-based clustering [DBSCAN]. However they require the knowledge of cluster number for a given dataset a priori [Lloyd57; onspectral2001; DBSCAN; DBCLASD; DENCLUE]

Nevertheless estimation of the number of clusters is difficult problem as the underlying data distribution is unknown Readers can find several existing techniques for determining cluster number in [survey\_cluster\_number2017; R3\_Chiang2010] We have followed the terminology used in R3\_Chiang2010 for categorizing different methods for the prediction of cluster numbers In this work we choose to focus only on three approaches: 1 variance-based approach 2 Structural approach and 3 the Resampling approach Variance-based plans are based on measuring compactness within a cluster Structural approaches include between-cluster separation as well as within-cluster variance We have chosen these approaches as they are either more suitable for handling big data or appear in a comparative study by several researchers Some well-known approaches are Calinski-Harabaz [CH] Silhouette Coefficient [sil] Davies-Bouldin [DB] Jump [jump] Gap statistic [gap] etc These approaches are not appropriate for handling big data as they are computationally intensive and require ample storage space It requires a scalable solution [kluster2018; ISI\_LL\_LML2018] for identifying the number of clusters Resampling-based approaches can be considered in such scenario Recently the concept of stability in clustering has become popular A few methods [instability2012; CV\_A] utilize the idea of clustering robustness against the randomness in the choice of sampled datasets to explore clustering stability

## Q8. What is D3S?

### Answer:

D3S A Discriminative Single Shot Segmentation Tracker Visual object tracking is one of the core computer vision problems The most common formulation considers the task of reporting the target location in each frame of the video given a single training image Currently the dominant tracking paradigm performing best in evaluations [kristan\_vot2017 kristan\_vot2018] is correlation bounding box tracking where the target represented by a multi-channel rectangular template is localized by cross-correlation between the template and a search region




Figure 1: The D3S tracker represents the target by two models with complementary geometric properties one invariant to a wide range of transformations including non-rigid deformations GIM - geometrically invariant model the other assuming a rigid object with motion well approximated by a euclidean change GEM - geometrically constrained Euclidean model The D3S exploiting the complementary strengths of GIM and GEM provides both state-of-the-art localization and accurate segmentation even in the presence of substantial deformation

State-of-the-art template-based trackers apply an efficient brute-force search for target localization Such a strategy is appropriate for low-dimensional transformations like translation and scale change but becomes inefficient for more general situations e g such that induce an aspect ratio change and rotation As a compromise modern trackers combine approximate exhaustive search with sampling and bounding box refinement/regression networks for aspect ratio estimation However these approaches are restricted to axis-aligned rectangles

Estimation of high-dimensional template-based transformation is unreliable when a bounding box is a sparse approximation of the target This is common consider e g elongated rotating deformable

objects or a person with spread out hands In these cases the most accurate and well-defined target location model is a binary per-pixel segmentation mask If such output is required tracking becomes the video object segmentation task recently popularized by DAVIS and YoutubeVOS challenges

Unlike in tracking video object segmentation challenges typically consider large target observed for less than 100 frames with low background distractor presence Top video object segmentation approaches thus fare poorly in short-term tracking scenarios where the target covers a fraction of the image substantially changes its appearance over a more extended period and moves over a cluttered background Best trackers apply visual model adaptation but in the case of segmentation errors it leads to irrecoverable tracking failure Because of this in the past segmentation has played only an auxiliary role in template-based trackers constrained DCF learning and tracking by 3D model

construction

Recently the SiamRPN tracker has been extended to produce high-quality segmentation masks in two stages SiamRPN branches first localize the target bounding box and then segmentation mask is computed only within this region by another branch The two-stage processing misses the opportunity to treat localization and segmentation jointly to increase robustness Another drawback is that a fixed template is used that cannot be discriminatively adapted to the changing scene

We propose a new single-shot discriminative segmentation tracker D3S that addresses the limitations as mentioned above Two discriminative visual models encode the target one is adaptive and highly discriminative but geometrically constrained to a euclidean motion GEM while the other is invariant to a broad range of transformation GIM geometrically invariant model see above Fig

GIM sacrifices spatial relations to allow target localization under significant deformation On the other hand GEM predicts the only position but discriminatively adapts to the target and acts as a selector between possibly multiple target segmentations inferred by GIM In contrast to related trackers [siammask\_cvpr19 siamrpn\_cvpr2019 atom\_cvpr19] the primary output of D3S is the segmentation map computed in a single pass through the network which is trained end-to-end for segmentation only

Some applications and most tracking benchmarks require reporting the target location as a bounding box As a secondary contribution we propose an effective method for interpreting the segmentation mask as a rotated rectangle This avoids an error-prone greedy search and naturally addresses changes in location scale aspect ratio and rotation

D3S outperforms all state-of-the-art trackers on most of the significant tracking benchmarks [kristan\_vot2016 kristan\_vot2018 got10k muller\_trackingnet] despite not being trained for bounding box tracking In video object segmentation benchmarks [davis16 davis17] D3S


outperforms the leading segmentation tracker [siammask\_cvpr19] and performs on par with top video object segmentation algorithms often tuned to a specific domain yet running orders of magnitude faster Note that the D3S is not re-trained for different benchmarks a single pre-trained version shows remarkable generalization ability and versatility PyTorch implementation will be made available

## Q9. What is DRNet?

### Answer:

DRNet stands for Dissect and Reconstruct the Convolutional Neural Network via Interpretable Manners Convolutional neural networks CNNs have been broadly applied on various visual tasks due to its superior performance [vgg] [resnet] [densenet] But the huge computation burden prevents convolutional neural networks from running on mobile devices Some works had been done to prune neural networks into smaller ones [slimming] [pruning1] [pruning2] Also there are too many lightweight network structures [mobilenet] [mobilenetv2] [shufflenet] were proposed to adapt convolutional neural networks to computational limited mobile devices However these methods usually require running a whole pre-trained network whatever the task is i e the first task requires the discrimination power of cats and dogs and the second task requires the discrimination power of apples and watermelons If one has a CNN which was pre-trained on ImageNet he must run the whole CNN on each task which is usually time-consuming and computation wasted

Our work focuses on an underlying problem i e can we run only parts of a CNN? To achieve this goal we need to find a method to dissect the whole network into pieces and reconstruct some of these pieces according to specific tasks The reconstructed CNN should have a smaller computation cost and better performance Meanwhile the process of generating this substructure should be quick and easy Therefore this technology can be applied on mobile devices and small robots such as cell-phones and uncrewed aerial vehicles Using these technologies these devices only need to store one complete CNN and some information about the substructure generating program When specific tasks come these devices can create a smaller substructure in an instant and run on it rather than run the whole original CNN



In this paper we proposed a novel and interpretable algorithm to generate these smaller substructures An interpretable way of CNN inspires our method As shown in Figure 1: the original CNN has many channels but not every channel is useful for the discrimination of every class What we need to do is to find the channels relevant to every type and combine them for the specific task This method looks similar to the previous work: structured network pruning [slimming] [pruning3] [pruning4] However all of these pruning methods need fine-tuning which is time-consuming and not allowed on mobile devices And these pruning methods are usually lack of interpretability which is much needed by human-beings when using CNNs Therefore we do not mean to propose a pruning method and make CNN smaller but to find the best channels for each class and combine them for specific tasks Our approach not only can be used on VGG and ResNet but also on some light structures such as MobileNetV2 Also we make this process quick and interpretable


DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview Preparation)

# Day28

## Q1. Explain StructEdit(Learning Structural Shape Variations).

### Answer:

The shapes of the 3D objects exhibit remarkable diversity, both in their compositional structure in terms of parts, as well as in geometry of the elements themselves. Yet humans are remarkably skilled at imagining meaningful shape variation even from the isolated object instances. For example, having seen a new chair, we can easily imagine its *natural* changes with the different height back, a wider seat, with or without armrests, or with a diverse base. In this article, we investigate how to learn such shape variations directly from the 3D data. Specifically, given the shape collection, we are interested in two sub-problems: first, for any given shape, we want to discover main modes of edits, which can be inferred directly from shape collection; and second, given an example edit on one shape, we want to transfer edit to another shape in the group, as a form of analogy-based edit transfer. This ability is useful in several settings, including the design of individual 3D models, the consistent modification of the 3D model families, and the fitting of CAD models to noisy and incomplete 3D scans.



Above Fig: Edit generation and transfer with StructEdit

We present the StructEdit, a method that learns the distribution of *shape differences* between structured objects that can be used to generate an ample variety of edits (in the first row); and accurately transfer edits between different purposes and across different modalities (on the second row). Edits can be both geometric and topological.

There are many challenges in capturing space of shape variations. First, individual shape can have different representations as image, surface meshes, or point clouds; second, one needs the unified setting for representing both continuous deformations as well as structural changes; third, shape edits are not directly expressed but are only implicitly contained in shape collections; and finally, learning the space of structural variations that is applicable to more than the single shape amounts to learning mappings between different shape edit distributions, since different shapes have various types and numbers of parts (like tables with or without leg bars).

In much of the existing literature on 3D machine learning (ML), 3D shapes are mapped to points in the representation space whose coordinates encode latent features of each shape. In such representation, shape edits are encoded as vectors in that same space—in other words, as differences between points representing shapes. Equivalently, we can think of forms as anchored vectors rooted at origin, while shape differences are floating vectors that can be transported around in shape space. This type of vector space arithmetic is commonly used [wu2016learning, achlioptas2017learning, wang2018global, gao2018automatic, xia2015realtime, Villegas\_2018\_CVPR], for example, in performing analogies, where the vector that is the difference of possible point A from point B is added to point C to produce an analogous point D. The challenge with this view in our setting is that while Euclidean spaces are perfectly homogeneous and vectors can be comfortably transported and added to points anywhere, shape spaces are far or less so. While for continuous variations, a vector space model has some plausibility, this is not so for structural variations: the “add arms” vector does not make sense for the point representing a chair that already has arms. We take the different approach. We consider embedding shapes differences or deltas *directly in their own latent space*, separate from general shape embedding space. Encoding and decoding such shape differences is always done through a VAE (variational autoencoder), in the context of the given source shape, itself encoded through the part hierarchy. This has the number of key advantages: (i) allows compact encodings of shape deltas, since in general, we aim to describe local variation; (ii) encourages network to abstract commonalities in shape variations across shape space; and (iii) adapts the edit to the provided source shape, suppressing the modes that are semantically implausible.

We have extensively evaluated the *Structdit* on publicly available shape data sets. We introduce the new synthetic dataset with ground truth shape edits to quantitatively evaluate our method and compare it against baseline alternative. We then provide evaluation results on PartNet dataset [mo2019partnet] and provide ablation studies. Finally, we demonstrate that extension of our method allows the handling of both images and point cloud as shape sources, can predict plausible edit modes from single shape examples, and can also transfer example shape edit on one shape to other shapes in the collection.

## Q2. EmpGAN: Multi-resolution Interactive Empathetic Dialogue Generation

### Answer:

As a vital part of human intelligence, emotional perceptivity is playing elemental role in various social communication scenarios, such as , education and healthcare systems Recently, sensitive conversation generation has received an increasing amount of attention to address emotion factors in an end-to-end framework However, as li2018syntactically revealed, that conventional emotional conversation system aims to produce more emotion-rich responses according to the specific user-input emotion, which inevitably leads to the psychological inconsistency problem

Studies on social psychology suggest that empathy is the crucial step towards a more humanized human-machine conversation, which improves emotional perceptivity in emotion-bonding social activities To design the intelligent automatic dialogue system, it is essential to make a chatbot empathetic within dialogues Therefore, in this paper, we focus on a task of *empathetic dialogue generation*, which automatically tracks and understands the user s emotion at each turn in multi-turn dialogue scenarios

Despite the achieved successes, obstacles to establishing the empathetic conversational system are still far beyond current signs of progress:

- Merely considering the sentence-level emotion while neglecting more precise token-level feelings may lead to insufficient emotion perceptivity It is challenging to capture nuances of human emotion accurately without modeling multi-granularity emotion factors in the dialogue generation
- Merely relying on the dialogue history but overlooking the potential of user feedback for the generated responses further aggravates the deficiencies above, which causes undesirable reactions


In this paper, we propose the multi-resolution adversarial empathetic dialogue generation model, named EmpGAN, to address the above challenges through generating more empathetic and appropriate responses To capture nuances of user feelings sufficiently, EmpGAN make responses by taking both coarse-grained sentence-level and fine-grained token-level emotions into account The response generator in EmpGAN dynamically understands sentiments along with a conversation to perceive a user s emotion states in multi-turn conversations Furthermore, an interactive adversarial learning framework is augmented to take user feedback into account thoughtfully, where two interactive discriminators identify whether the generated responses evoke emotion perceptivity regarding both the dialogue history and user emotions

In particular, the EmpGAN contains the empathetic generator and two interactive inverse discriminators. The empathetic generator is composed of three components: (i) A semantic understanding module based on Seq2Seq(sequence to sequence) neural networks that maintain the multi-turn semantic context (ii) A multi-resolution emotion perception model captures the fine and coarse-grained emotion factors of each dialogue turn to build the emotional framework (iii) An empathetic response decoder combines semantic and emotional context to produce appropriate responses in terms of both meaning and emotion. The two interactive inverse discriminator additionally incorporate the user feedback and corresponding emotional feedback as inverse supervised signal to induce the generator to produce a more empathetic response.

### **Q3. G-TAD: Sub-Graph Localization for Temporal Action Detection**

#### **Answer:**

Video understanding has gained much attention from both academia and industry over recent years, given the rapid growth of videos published in online platforms. Temporal action detection is one of exciting but challenging tasks in this area. It involves detecting start and the end frames of action instances, as well as predicting their class label. This is onerous, especially in long untrimmed videos.



Video context is an important cue to detect actions effectively. Here, we refer to mean as frames that are outside the target action but carry valuable indicative information of it. Using video context to infer potential actions is natural for human beings. Empirical evidence shows that human can reliably predict or guess the occurrence of the specific type of work by only looking at short video snippets where the action does not happen. Therefore, incorporating context into temporal action detection has become an important strategy to boost detection accuracy in the recent literature. Researchers have proposed various ways to take advantage of the video context, such as extending temporal action boundaries by the pre-

defined ratio, using dilated convolution to encode meaning into features, and aggregating definition feature implicitly by way of the Gaussian curve All these methods only utilize temporal context, which follows or precedes an action instance in its immediate secular neighborhood However, real-world videos vary dramatically in temporal extent, action content, and even editing preferences The use of such temporal contexts does not fully exploit precious merits of the video context, and it may also impair detection accuracy if not adequately designed for underlying videos

So, what properties characterize the desirable video context for accurate action detection? First, setting should be semantically or grammatically correlated to the target action other than merely temporally located in its vicinity Imagine a case where we manually stitch an action clip into some irrelevant frames; the abrupt scene change surrounding the action would not benefit the action detection On the other hand, snippets located at a distance from an operation but containing similar semantic content might provide indicative hints for detecting the action Second, context should be content-adaptive rather than manually pre-defined Considering the vast variation of videos, a framework that helps to identify different action instances could be changed in lengths and locations based on the video content Third, context should be based on multiple semantic levels, since using only one form/level of meaning is unlikely to generalize well


In this paper, we endow video context with all the above properties by casting action detection as a sub-graph localization problem based on a graph convolutional network (GCN We represent each video sequence as the graph, each snippet as a node, each snippet-snippet correlation as an edge, and target actions associated with context as sub-graphs, as shown in Fig 1 The meaning of a snippet is considered to be all snippets connected to it by an edge in a video graph We define two types of edges temporal corners and semantic edges, each corresponding to temporal context and grammatical context, respectively Temporal edges exist between each pair of neighboring snippets, whereas semantic edges are dynamically learned from the video features at each GCN layer Hence, the multi-level context of each snippet is gradually aggregated into the features of the snippet throughout the entire GCN ResNet inspires the structure of each GCN block, so we name this GCN-based feature extractor GCNet

The pipeline of our proposed Graph-Temporal Action Detection method, dubbed G-TAD, is analogous to faster R-CNN in object detection There are two critical designs in G-TAD First, GCNet, which generates context-enriched features, corresponds to the backbone network, analogous to a series of Convolutional Neural Network (CNN layers in faster R-CNN Second, to mimic ROI(region of interest alignment in faster R-CNN, we design the sub-graph alignment (SGAlign layer to generate a fixed-size representation for each sub-graph and embed all sub-graphs into same Euclidean space Finally, we apply a classifier on the features of each sub-graph to obtain detection results We summarize our contributions as follows

(1) We present a novel GCN-based video model to exploit video context for effective temporal action detection fully. Using this video GCN representation, we can adaptively incorporate multi-level semantic meaning into the features of each snippet.

(2) We propose G-TAD, a new sub-graph detection framework, to localize actions in video graphs. G-TAD includes two main modules: GCNet and SGAlign. GCNet performs graph convolutions on video graphs, leveraging both temporal and semantic context. SGAlign re-arranges sub-graph features in the embedded space suitable for detection.


(3) G-TAD achieves state-of-the-art (SOTA) performance on two popular action detection benchmarks. On ActivityNet-1.3, it achieves an average mAP of 34.09%. On THUMOS-14, it reaches 40.16% mAP, beating all contemporary one-stage methods.



**Fig: Overview of G-TAD architecture** The input of G-TAD is the sequence of snippet features. We first extract features using 3 GCNet blocks, which gradually aggregate both temporal and multi-level semantic context. Semantic context, encoded in semantic edges, is dynamically learned from elements at each GCNet layer. Then we feed extracted features into the SGAlign layer, where sub-graphs defined by the set of anchors are transformed to a fixed-size representation in the Euclidean space. Finally, the localization module scores and ranks the sub-graphs for detection.

## Q4. What is F3Net?

**Answer:**



F3Net is a combination of Fusion, Feedback, and Focus for Salient object detection (SOD) aims to estimate the significant visual regions of images or videos and often serves as the pre-processing step for many downstream vision tasks. Earlier SOD algorithms mainly rely on heuristic priors (*e.g.*, color, texture and contrast) to generate saliency maps. However, these hand-craft features can hardly capture high-level semantic relations and context information. Thus they are not robust enough to complex scenarios. Recently, convolutional neural networks (CNNs) have demonstrated its powerful feature extraction capability in visual feature representation. Many CNNs-based models have achieved remarkable progress and pushed the performance of SOD to a new level. These models adopt the encoder-decoder architecture, which is simple in structure and computationally efficient. The encoder usually is made up of a pre-trained classification model (*e.g.*, ResNet and VGG), which can extract multiple features of different semantic levels and resolutions. In the decoder, extracted features are combined to generate saliency maps.

However, there remain two significant challenges in accurate SOD. First, features of different levels have different distribution characteristics. High-level features have rich semantics but lack precise location information. Low-level features have rich details but full of background noises. To generate better saliency maps, multi-level features are combined. However, without delicate control of the information flow in the model, some redundant features, including noises from low-level layers and coarse boundaries from high-level layers, will pass in and possibly result in performance degradation. Second, most of the existing models use binary cross-entropy that treats all pixels equally. Intuitively, different pixels deserve different weights, *e.g.*, pixels at the boundary are more discriminative and should be attached with more importance. Various boundary losses have been proposed to enhance the boundary detection accuracy, but considering only the boundary pixels is not comprehensive enough since there are lots of pixels near the boundaries prone to wrong predictions. These pixels are also essential and should be assigned with

---

larger weights In consequence, it is essential to design a mechanism to reduce the impact of inconsistency between features of different levels and assign larger weights to those significant pixels

To address the above challenges, we proposed a novel SOD framework, named F3Net, which achieves remarkable performance in producing high-quality saliency maps First, to mitigate the discrepancy between features, we design a cross-feature module (CFM , which fuses elements of different levels by element-wise multiplication Different from addition and concatenation, CFM takes a selective fusion strategy, where redundant information will be suppressed to avoid the contamination between features, and important features will complement each other Compared with traditional fusion methods, CFM can remove background noises and sharpen boundaries, as shown in Fig 1 Second, due to downsampling, high-level features may suffer from information loss and distortion, which can not be solved by CFM Therefore, we develop the cascaded feedback decoder (CFD to refine these features iteratively CFD contains multiple sub-decoders, each of which includes both bottom-up and top-down processes For the bottom-up method, multi-level features are aggregated by CFM gradually For the top-down process, aggregated features are feedback into previous features to refine them Third, we propose the pixel position-aware loss (PPA to improve the commonly used binary cross-entropy loss, which treats all pixels equally Pixels located at boundaries or elongated areas are more complicated and discriminating Paying more attention to these hard pixels can further enhance model generalization PPA loss assigns different weights to different pixels, which extends binary cross-entropy The weight of each pixel is determined by its surrounding pixels Hard pixels will get larger weights, and easy pixels will get smaller ones

To demonstrate the performance of F3Net, we report experimental results on five popular SOD datasets and visualize some saliency maps We conduct a series of ablation studies to evaluate the effect of each module Quantitative indicators and visual results show that F3Net can obtain significantly better local details and improved saliency maps Codes have been released In short, our main contributions can be summarized as follows:

- We introduce the cross feature module to fuse features of different levels, which can extract the shared parts between features and suppress each other's background noises and complement each other's missing parts
- We propose the cascaded feedback decoder for SOD, which can feedback features of both high resolutions and high semantics to previous ones to correct and refine them for better saliency maps generation
- We design pixel position-aware loss to assign different weights to different positions It can better mine the structure information contained in the features and help the network focus more on detail regions

- Experimental results demonstrate that the proposed model F3Net achieves the state-of-the-art performance on five datasets in terms of six metrics, which proves the effectiveness and superiority of the proposed method

## **Q5.Natural Language Generation using Reinforcement Learning with External Rewards**

### **Answer:**

We aim to develop models that are capable of generating language across several genres of text, conversational texts, and restaurant reviews. After all, humans are adept at both. Extant NLG(natural language generation) models work on either conversational text (like movie dialogues) or longer text (e.g., stories, reviews but not both). Also, while the state-of-the-art(SOTA) in this field has advanced quite rapidly, current model is prone to generate language that is short, dull, off-context. More importantly, a generated language may not adequately reflect affective content of the input. Indeed, humans are already adept at this task, as well. To address these research challenges, we propose the RNN-LSTM architecture that uses an encoder-decoder network. We also use reinforcement learning(RL) that incorporates internal and external rewards. Specifically, we use emotional appropriateness as an internal reward for the NLG(Natural Language Generation) system so that the emotional tone of generated language is consistent with the emotional tone of prior context fed as input to model. We also effectively incorporate usefulness scores as external rewards in our model. Our main contribution is the use of distantly labeled data in architecture that generates coherent, affective content and we test the architecture across two different genres of text.

### **What are the problem statement and their intuition?**

Our aim is to take advantage of reinforcement learning(RL) and external rewards during the process of language generation. Complementary to this goal, we also aim to generate language that has same emotional tone as the other input. Emotions are recognized as functional in decision-making by influencing motivation and action selection. However, the external feedback and rewards are hard to come by for language generation; these would need to be provided through crowdsourcing judgment on generated responses *during* generation process, which makes process time-consuming and impractical. To overcome this problem, we look for distance labeling and use labels provided in training set as a proxy for human judgment on generated responses. Particularly, we incorporate usefulness scores in a restaurant review corpus as the proxy for external feedback.




Fig 1: Overall Architecture of the system showing internal and external rewards using reinforcement learning

## Q6. LaFl: Generative Landmark Guided Face Inpainting

### Answer:

Image inpainting (also known as image completion) refers to the process of reconstructing lost or deteriorated regions of images, which can be applied to, as a fundamental component, various tasks such as image restoration and editing. Undoubtedly, one expects the completed result to be realistic so that the reconstructed regions can be hardly perceived. Compared with natural scenes like oceans and lawns, manipulating faces, the focus of this work, is more challenging. Because the faces have much stronger topological structure and attribute consistency to preserve. Figure 1 shows three such examples. Very often, given the observed clues, human beings can easily infer what the lost parts possibly, although inexactly, look like. As a consequence, a slight violation of the topological structure and the attribute consistency in the reconstructed face highly likely leads to a significant perceptual flaw. The following defines the problem:

Definition:

Face inpainting given a face image  $I$  with corrupted regions masked by  $M$ . Let  $\bar{M}$  designate the complement of  $M$  and  $\circ$  the  $\ominus$  adamard product. The goal is to fill the target part with semantically meaningful and visually continuous information to the observed part. In other words, the completed

result should preserve the topological structure among face components such as eyes, nose, and mouth, and the attribute consistency on like pose, gender, ethnicity, and expression.




Figure 1: Three face completion results by our method. From left to right: corrupted inputs, plus landmarks predicted from the inputs, and our final results, respectively.

## Q7. Image2StyleGAN++: How to Edit the Embedded Images?

**Answer:**



From above fig: (i) and (ii) : input images; (iii) : the two-face generated by naively copying the left half from (i) and the right half from (ii) ; (iv) : the two-face created by our Image2StyleGAN++ framework

Recent GANs demonstrated that synthetic images could be generated with very high quality. This motivates research into embedding algorithms that embed a given photograph into a GAN latent space. Such embedding algorithms can be used to analyze the limitations of GANs, do image inpainting, local image editing, global image transformations such as image morphing and expression transfer, and few-shot video generation.

In this paper, we propose to extend a very recent embedding algorithm, Image2StyleGAN. In particular, we would like to improve this previous algorithm in three aspects. First, we noticed that the embedding quality could be further improved by including Noise space optimization into embedding framework. The key insight here is that stable Noise space optimization can only be conducted if optimization is done sequentially with  $W\alpha$  space and not jointly. Second, we would like to improve capabilities of the embedding algorithm to increase the local control over the embedding. One way to improve local authority is to include mask in embedding algorithm with undefined content. The goal of the embedding algorithm should be to find a plausible embedding for everything outside the mask, while filling in reasonable semantic content in the masked pixels.

Similarly, we would like to provide the option of approximate embeddings, where the specified pixel colors are only a guide for the embedding. In this way, we aim to achieve high-quality embeddings that can be controlled by user scribbles. In the third technical part of the paper, we investigate the combination of embedding algorithm and direct manipulations of the activation maps (called activation tensors in our article).

## **Q8. oops! Predicting Unintentional Action in Video**

### **Answer:**

From just a glance at the video, we can often tell whether a person's action is intentional or not. For example, the figure below shows a person attempting to jump off a raft, but unintentionally tripping into the sea. In a classic series of papers, developmental psychologist Amanda Woodward demonstrated that children learn this ability to recognize the intentionality of action during their first year. However, predicting the intention behind action has remained elusive for machine vision. Recent advances in action recognition have primarily focused on predicting the physical motions and atomic operations in the video, which captures the means of action but not the intent of action.

We believe a key limitation for perceiving visual intentionality has been the lack of realistic data with natural variation of intention. Although there are now extensive video datasets for action recognition, people are usually competent, which causes datasets to be biased towards successful outcomes. However, this bias for success makes discriminating and localizing visual intentionality challenging for both learning and quantitative evaluation.



**Fig: The oops! Dataset: Each pair of frames shows an example of intentional and unintentional action in our dataset** By crawling publicly available fail videos from the web, we can create a diverse and in-the-wild dataset of accidental action. For example, at the bottom-left corner shows a man failing to see gate arm, and at the top-right shows two children playing competitive games where it is inevitable; one person will fail to accomplish their goal.

We introduce a new annotated video dataset that is abundant with unintentional action, which we have collected by crawling publicly available fail videos from the web. From the above figure shows some examples, which cover in-the-wild situations for both intentional and unintentional action. Our video dataset, which we will publicly release, is both large (over 50 hours of video) and diverse (covering hundreds of scenes and activities). We annotated videos with the temporal location at which the video transitions from intentional to unintentional action. We define three tasks on this dataset: classifying the intentionality of action, localizing the change from intentional to unintentional, and forecasting onset of unintentional action shortly into the future.

To tackle these problems, we investigate several visual clues for learning with minimal labels to recognize intentionality. First, we propose a novel self-supervised task to learn to predict the speed of the video, which is incidental supervision available in all unlabeled videos for learning the action representation. Second, we explore the predictability of temporal context as a clue to learn features, as unintentional action often deviates from expectation. Third, we study an order of events as a clue to recognize intentionality, since intentional action usually precedes unintentional action.

Experiments and visualizations suggest that unlabeled video has intrinsic perceptual clues to recognize intentionality. Our results show that, while each self-supervised task is useful, and learning to predict the speed of video helps the most. By ablating model and design choices, our analysis also suggests that models do not rely solely on low-level motion clues to solve unintentional action prediction. Moreover, although human consistency in our dataset is high, there is still a large gap in performance between our models and human agreement, underscoring that analyzing human goals from videos remains the

fundamental challenge in computer vision(OpenCV) We hope this dataset of unintentional and unconstrained action can provide the pragmatic benchmark of progress

## Q9. FairyTED: A Fair Rating Predictor for TED Talk Data

### Answer:

In recent times, artificial intelligence is being used for inconsequential decision making Governments make use of it in the criminal justice system to predict recidivism [brennan2009evaluating, tollenaar2013method], which affects the decision about bail, sentencing, and parole Various firms are also using machine learning algorithms to examine and filter resumes of job applicants [nguyen2016hirability, chen2017automated, naim2016automated], which is crucial for the growth of a company Machine learning algorithms are also being used to evaluate human s social skills, such as presentation performance [Chen2017a, Tanveer2015], essay grading

To solve such decision-making problems, machine learning algorithms are trained on massive datasets that are usually collected in the wild Due to difficulties in the manual curation or adjustment over large datasets, the data likely capture unwanted bias towards the underrepresented group based on race, gender, or ethnicity Such bias results in unfair decision-making systems, leading to unwanted and often catastrophic consequences to human life and society For example, the recognition rates of pedestrians in autonomous vehicles are reported to be not equally accurate for all groups of people [wilson2019predictive] Matthew et al [kay2015unequal] showed that societal bias gets reflected in the machine learning algorithms through a biased dataset and causes representational harm for occupations Face recognition is not as useful for people with different skin tones Dark-skinned females have 43 times higher detection error than light-skinned males

In this work, we propose a predictive framework that tackles the issue of designing a fair prediction system from biased data As an application scenario, we choose the problem of fair rating prediction in the TED talks TED talks cover a wide variety of topics and influence the audience by educating and inspiring them Also, it consists of speakers from a diverse community with imbalances in age, gender, and ethnic attributes The ratings are provided by spontaneous visitors to the TED talk website A machine learning algorithm trained solely from the audience ratings will have a possibility of the predicted score being biased by sensitive attributes of the speakers

It is a challenging problem because numerous factors drive human behavior and hence have huge variability It is challenging to know the way these factors interact with each other Also, uncovering the true interaction model may not be feasible and often expensive Even though the sharing platforms such as YouTube, Massive Open Online Courses (MOOC , or [ted.com](https://www.ted.com)) make it possible to collect a large amount of observational data, these platforms do not correct for bias and unfair ratings

---


In this work, we utilize *causal models* [pearl2009causal] to define possible dependencies between attributes of the data. We then address the problem of not knowing true interaction model by averaging outputs of predictors across several possible causes. Further, using these causal models, we generate *counterfactual samples* of sensitive attributes. These counterfactual samples are the key components in our fair prediction framework (adapted from kusner2017counterfactual russell2017worlds) and help reducing bias in ratings wrt sensitive attributes. Finally, we introduce the novel metric to quantify degree of fairness employed by our FairyTED pipeline. To best of our knowledge, FairyTED is first fair prediction pipeline for public speaking datasets and can be applied to any dataset of similar grounds. Apart from theoretical contribution, our work also has practical implications in helping both the viewers and organizers make informed and unbiased choices for the selection of talks and speakers.

**DATA SCIENCE  
INTERVIEW  
PREPARATION  
(30 Days of Interview Preparation)**

**# Day29**

## Q1. What is SuperGlue?

**Answer:**




SuperGlue is a Learning Feature Matching with Graph Neural Networks. Correspondences between points in images are essential for estimating 3D structure and camera poses in geometric computer vision(OpenCV) tasks such as SLAM(Simultaneous Localization and Mapping) and SfM(Structure-from-Motion). Such correspondences are generally estimated by matching local features, the process called as data association. Broad viewpoint and lighting changes, occlusion, blur, and lack of texture are factors that make 2D-to-2D data association particularly challenging.

In this paper, we present new way of thinking about feature matching problem. Instead of learning better task-agnostic local features followed by simple matching heuristics and tricks, we propose to determine the matching process from pre-existing local features using a novel neural architecture called SuperGlue. In the context of SLAM, which typically decomposes the problem into the visual feature extraction *front-end* and the bundle adjustment or poses estimation *back-end*, our network lies directly in middle. SuperGlue is a learnable *middle-end* (see in above Figure).

In this work, *learning feature matching* is viewed as finding partial assignment between two sets of local feature. We revisit classical graph-based strategy of matching by solving the linear assignment problem, which, when relaxed to the optimal transport problem, can be solved differentiably. The cost function of this optimization is predicted by a GNN(Graph Neural Network). Inspired by success of the Transformer, it uses self- (intra-image) and cross- (inter-image) attention to leveraging both spatial relationships of


keypoints and their visual appearance. This formulation enforces assignment structure of the prediction while enabling cost to learn complex priors, handling occlusion, and non-repeatable keypoints. Our method is trained end-to-end from images pair we learn priors for pose estimation from large annotated dataset, enabling SuperGlue to reason about 3D scene and assignment. Our work can be applied to a variety of multiple-view geometry problems that require high-quality features correspondences (see in below Figure).

We show superiority of SuperGlue compared to both handcrafted matches and learned inlier classifiers. When combined with SuperPoint, a deep front-end, SuperGlue advances the state-of-the-art on the tasks of indoor and outdoor pose estimation and paves the way towards end-to-end deep SLAM.



## Q2. What is MixNMatch?

**Answer:**



It is a Multifactor Disentanglement and Encoding for Conditional Image Generation Consider the real image of the yellow bird in the above Fig, First column What would a bird look like in a different background, say that of a duck? How about in the different texture, perhaps that of the rainbow textured bird in the second column? What if we wanted to keep its texture but changes its shape to that of rainbow bird and background and pose to that of duck, as in the 3rd column? How about sampling shape, pose, texture, and experience from 4 different reference images and combining them to create entirely new image (last column)

#### □ **problem**

While research in conditional image generation has made tremendous progress, no actual work can simultaneously disentangle *background*, *object pose*, *shape*, and *texture* with minimal supervision, so that these factors can be combined from *multiple real images* for fine-grained controllable image generations Learning disentangled representations with minimal supervision is the extremely challenging problem since the underlying factors that give rise to the data are often highly correlated and intertwined Work that disentangles *two* such factors, by taking as input 2 reference images, e g , one for appearance and another for pose, do exist [huang-eccv2018, joo-cvpr18, lee-eccv18, lorenz-cvpr2019, xiao-iccv2019], but they cannot disentangle other factor such as pose vs shape or foreground vs background appearance Since only two factors can be controlled, these approaches cannot arbitrarily change,e g , the object s background, shape, and texture, while keeping its pose the same Others require intense supervision in the form of keypoint or pose or mask annotations [peng-iccv2017, Balakrishnan-cvpr2018, ma-cvpr2018, esser-cvpr2018], which limit their scalability and still fall short of disentangling all of four factors outlined above

Our proposed conditional generative model, *MixNMatch*, aim to fill this void MixNMatch learns to disentangle and encode background, object pose, shape, and texture latent factors from the real images, and importantly, does so with minimal human supervision This allows, e g , each factor to be extracted from a different actual image, and then combined for mix-and-match image generation; see in above fig During training, MixNMatch only requires a loose bounding box around the object to the model background but requires no other supervision for modeling the object s pose, shape, and texture

### Q3. FAN: Feature Adaptation Network

**Answer:**




Figure: Visual results on four datasets. Vertically we show input in row first and our results in row third. For LFW and SCface datasets, we show the ground truth and gallery images in second row, respectively. For WIDER FACE and QMUL-SurFace datasets which do not have ground truth high-resolution images, we compare with two state-of-the-art(SOTA) methods: Bulat et al [bulatyang2018learn] and FSRGAN [CT-FSRNet-2018] in row 2, respectively.

It is used for Surveillance Face Recognition and Normalization. Surveillance Face Recognition (FR) is a challenge and a significant problem yet less studied. The performance on conventional benchmarks such as LFW [LFWTech] and IJB-A have been greatly improved by state-of-the-art (SOTA) (Face Recognition(FR) methods [wang2018cosface, wen2016discriminative, deng2019arcface], which still suffer when applied to surveillance Face Recognition(FR). One intuitive approach is to perform Face Super-Resolution (FSR) on surveillance face to enhance facial details. However, existing Face Super-Resolution(FSR) methods are problematic to handle surveillance faces, because they usually ignore the *identity* information and require to *paired* training data. Preserving identity information is more crucial for surveillance of all face than recovering other information, e.g., background, Pose, Illumination, Expression (PIE).

In this work, we study surveillance face recognition(FR) and normalization. Specifically, given the surveillance face image, we aim to learn robust identity features for Face recognition(FR). Meanwhile, the feature are used to generate a normalized face with enhanced facial details and neutral PIE. Our normalization is performed mainly on the aspect of the resolution. While sharing same goal as traditional SR, it differs in removing the pixel-to-pixel correspondence between original and super-resolved images, as required by conventional SR. Therefore, we term it as face normalization. For same reason, we

compare ours to FSR instead of prior normalization methods operating on pose or expression To the best of our knowledge, this is a *first* work to study surveillance face normalization

We propose the novel Feature Adaptation Network(FAN) to jointly perform face recognition and normalization, which has 3 advantages over conventional FSR i Our joint learning scheme can benefit each other, while most FSR methods do not consider a recognition task ii Our framework enables training with both paired and unpaired data while conventional SR methods only support paired training iii Our approach simultaneously improves resolution and alleviates the background and PIE from real surveillance faces while traditional methods only act on recommendation Examples in below Fig One demonstrates the superiority of FAN over SOTA SR methods



Our Feature Adaptation Network (FAN) consists of 2 stages In first stage, we adopt disentangled features learning to learns both identity and non-identity characteristics mainly from high-resolution(HR images, which are combined as input to the decoder for pixel-wise face recovering In second stage, we propose feature adaptation to facilitate the feature further learning from the low-resolution (LR images by approximating feature distribution between the low-resolution and high-resolution identity encoders There are two advantages to use Feature Adaption Network(FAN) for surveillance facial-recognition(FR) and normalization First, Feature Adaption Network (FAN) focuses on learning disentangled identity features from Low-resolution(LR images, which is better for facial recognition (FR) than extracting features from super-resolved faces [tran2017disentangled, zhang2018facesr, wu2016j] 2nd, our adaptation is performed in disentangled identity feature space, which enables training with unpaired data without pixel-to-pixel

correspondences As shown in the last fig , the synthetic paired data used in prior works [CBN\_ECCV16, CT-FSRNet-

2018, bulatyang2018learn, wu2016j, zhang2018facesr, DRRN, MemNet\_ICCV17, rad2019srobb] can not accurately reflect difference between real low-resolution(LR and high-resolution(HR in-the-wild faces, which is also observed in [cai2019toward]

Furthermore, to better handle surveillance faces with the unknown and diverse resolution, we propose the Random Scale Augmentation (RSA) method that enables the network to learn all kinds of scales during training Prior FSR [CT-FSRNet-2018, CBN\_ECCV16, URDGN\_ECCV16] methods either *artificially* generate the LR images from the HR ones by simple *down-sampling*, or *learn* the degradation mapping via a Convolutional Neural Network (CNN). However, their common drawback is to learn reconstruction under *fixed* scales, which may greatly limit their applications to surveillance faces. In contrast, our RSA efficiently alleviates the constraint on scale variation.

## Q5. WSOD with PSNet and Box Regression

### Answer:

The object detection task is to find objects belonging to specified classes and their locations in images. Benefiting from the rapid development of deep learning(DL) in recent years, the fully supervised object detection task has made significant progress. However, fully supervised task requires instance-level annotation for training, which costs lot of time and resources. Unlabeled or images labeled datasets cannot be effectively used by fully supervised method. On another hand, image-level annotated datasets are easy to generate and can even be automatically generated by web search engines. To effectively utilize these readily available datasets, we focus on weakly-supervised object detection(WSOD) tasks. The WSOD task only takes image-level annotations to train instance-level object detection network, which is different from the fully supervised object detection task.





Fig : Examples of PSNet outputs: (i a dog without proposal occlusion, (ii a dog whose head is occluded by the proposal box, (iii a dog that proposal covers part of the body, and (iv proposal completely cover the entire dog If proposal does not completely include the whole dog, PSNet gives a high score If proposal ultimately consists of the whole dog, PSNet gives a low score

There are 3 main methods for weakly supervised object detection: The first is to update detector and pseudo labels from inaccurate pseudo labels iteratively; The second is to construct an end-to-end network that can take image-level annotation as supervision to train this object detection network. The third two-stage method is that taking an algorithm to optimize pseudo labels from other WSOD networks and training a fully supervised object detection network. In addition, according to different modes of proposing proposals, each of above methods can be divided into 2 classes: one is to propose proposals based on feature map that predicts probability of each pixel belonging to each class, and then get the possible instances and their locations in image; The second is detector-based method that uses the trained detector to identify multiple proposals and determines whether each proposal belongs to a specific object class or not. Comparing the effects of these methods, the end-to-end detector-based approach performs well, and our work follows this series of process

The earliest end-to-end detector-based WSOD network is WSDDN Bilen and Vedaldi (2016), which trains a two-streams network to predict the classification accuracy of each proposal and its contributions to each class. The results of the two streams are combined to get the image classification score so that the WSDDN can take advantage of image-label annotations for training. Subsequent other work aims to improve performance of this network, like adding more classification streams, using the clustering method, adding a fully supervised module, and so on. The end-to-end detector-based approach has 2 drawbacks: one is that context information cannot be fully used to classify proposal; The second is that the most discriminative parts of the object may be detected instead of the entire object



To make full use of the context information of the proposal and avoid finding only the most discriminative part, we design a new network structure that adds a box regression branch to the traditional WSOD network. In the previous WSOD network, there is usually no box regression part, while this branch plays an essential role in fully supervised object detection networks. The box regression network can adjust position and scale of proposal, make it closer to the ground truth. In the fully supervised object detection task, we can use the instance-level label as supervision to train box regression network; but in WSOD task, network cannot obtain the instance-level annotation and thus cannot train this branch. To obtain reliable instance annotation to train the regression network, we designed the proposal scoring network named PSNet that can detect whether proposal completely covers the object. The PSNet is specially trained multi-label classification network. Even if the object in the image is occluded or incomplete, the PSNet can detect the presence of the object. The PSNet can be used to evaluate images without proposal area. If the proposal completely covers whole object, rest of the image will not contain information about it. We use PSNet to evaluate the output of the WSOD network, and then select appropriate proposals as pseudo labels to train box regression network. Examples of the output of PSNet are shown in the above Figure.

## Q6. Autonomous Driving Assistance Systems (ADAS) and Vehicle Automation.

### Answer:

Vehicles are being equipped with increasingly complex autonomous driving assistance systems (ADAS) that take over parts of driving tasks previously performed by the human driver. There are several different ADAS technologies in vehicles, starting from basics that have been in vehicles for several years, such as automatic windscreen wipers and anti-lock braking systems. More advanced techniques are already on

---

the road today, where both the longitudinal (braking/accelerating, e.g., adaptive cruise control) and lateral (steering, e.g., assisted lane-keeping) control of the vehicle is shifting to ADAS. Further enhanced levels of automated driving functionality include autopilot (Tesla), intellisafe (Volvo), and Distronic plus steering assist (Mercedes). Overall, this fast pace of market penetration of ADAS in vehicles has not allowed drivers to develop understanding of new systems over an extended period.

The most common taxonomy to capture the development of ADAS technology in cars are SAE's levels of automation. This approach is based on six levels of automation, ranging from no automation (level 0) to full automation (level 5). In particular, in levels 2/3, the automated system can take partial control of the vehicle, where level 2 expectations of the human driver are to monitor the system and intervene appropriately, while the level 3 expectation of the human driver is to intervene appropriately upon a request from the system. Today, most ADAS technology equipped cars are at level 1, in which progression to partial/semi-automation (level 2/3) with in-built ADAS technology in even lower-priced car models is becoming more common. Also, level 2/3 automation will likely be reality for some time to come, given that fuller automation (4/5) is emerging slowly without clear market deployment roadmap.

One of the main challenges that arise in level 2/3 automation is transition of control from the ADAS to the human driver, often referred to as the handover problem. This transition is, according to social factors and safety research, a phase where human attention and reliability is critical, but where humans tend to underperform in those respects (son2017situation). E.g., research has indicated that automatic cruise control technology leads to a reduction in mental workload and, thus, to problems with regaining control of the vehicle in failure scenarios (stanton1998vehicle). Additionally, a common misconception concerning ADAS technology is that when more automation is introduced, human error will disappear (atlantic2015save), which may give rise to the problematic idea that driver training is not necessarily needed. However, social factors research advises against not training for the use of new sophisticated automation technology (lee2006human; salas2006design; saetren2015effects), as humans in the technology loop will still be needed for use, maintenance or design of the technology. It may even be that increased automation increases the level of competence required for the driver, as the driver must know both how to handle the system manually, for instance, if the sensors in a car stop working due to bad weather, in addition to knowing how to control and supervise the advanced automation technology.

In our previous work (rismani2018qualitative), we performed a qualitative survey and found that the handover problem is challenging, and it is unclear to drivers how this could best be handled securely. Furthermore, drivers were worried about the implications of vehicle automation due to lack of knowledge and experience of level 2/3 systems and seemed concerned about the kind of training and licensing that accompanies these developments in vehicle automation. The lack of certainty around training and licensing concerning emerging ADAS technologies is a relevant ethical concern, as it exposes a gap in regulation and industry best practices that have not been the focus of much research to date.

This lack of certainty around driver training and licensing wrt level 2/3 automation systems underscores the need to understand better the following research questions: (i) What are drivers' awareness of ADAS in their vehicles, (ii) How knowledgeable are drivers about ADAS in their vehicles, and (iii) How willing are drivers to engage or use ADAS in their vehicles? Overall we expect to see people's engagement or use pattern of ADAS technologies in their vehicle correlate to their awareness and knowledge of those techniques.

Previous work has looked at driver perception of ADAS and vehicle automation, including understanding learner drivers' perspective of Blind Spot Detection(BSD) and Adaptive Cruise Control(ACC) systems. That work found that driver's awareness, use, and perceived safety of Blind Spot Detection(BSD) was higher than that of ACC tsapi\_introducing\_2015, and contributed to a greater understanding of driver preparation and acceptance of ADAS crump2016differing, and how drivers learn and prefer to learn about ADAS, and what their expectations are regarding ADAS and vehicle automation hoyos2018consumer.

To answer our research questions, we performed a quantitative public survey of issues specific to the public's awareness, knowledge, and use of ADAS technologies in level 2/3 automation. Also, based on previous work tsapi\_introducing\_2015; crump2016differing; hoyos2018consumer, we analyzed gender and age relationships as well as income and type of training with regards to our research questions above.

## **Q7. Robot Learning and Execution of Collaborative Manipulation Plans from YouTube Videos.**



**Answer:**


We focus on problem of learning collaborative action plans for robot. Our goal is to have robot watch unconstrained videos on web, extract the action sequences shown in the videos and convert them to an executable plan that it can perform either independently or as part of a human-robot or robot-robot team.

Learning from online videos is hard, particularly in collaborative settings: it requires recognizing the actions executed, together with manipulated tools and objects. In many collaborative tasks, these actions include handing objects over or holding object for the other person to manipulate. There is a very large variation in how the actions are performed and collaborative actions may overlap spatially and temporally.

In our previous work [hejia\_isrr19], we proposed a system for learning activities performed by two humans collaborating at the cooking task. The system implements a collaborative action grammar built upon action grammar initially proposed by Yang et al [yang2015robot]. Qualitative analysis in 12 clips showed that parsing these clips with grammar results in human-interpretable tree structures representing

a variety of single and collaborative actions. The clips were manually segmented and were approximate 100 frames each.





In this paper, we generalize this work with a framework for *generating single and collaborative action trees from full-length YouTube videos lasting several minutes and concatenating the trees in an action graph that is executable by one or more robotic arms*

The framework takes as input YouTube video showing collaborative tasks from start to end. We assume that objects in video are annotated with label and bounding boxes, e.g., by running the YOLOv3 algorithm. We also think a skill library that associates a detected action with skill-specific motion primitives. We focus on cooking tasks because of the variety of manipulation actions and their importance in-home service robotics.


In second fig shows the components of proposed framework. We rely on insight that hands are main driving force of manipulation actions. We detect the human hands in the video and use the hand trajectories to split the video into clips. We then associate objects and hands spatially and temporally to recognize the actions and generate human-interpretable robot commands. Finally, we propose an open-sourced platform for creating and executing an action graph. We provide a quantitative analysis of performance in two YouTube videos of 13401 frames in total and a demonstration in the simulation of robots learning and performing the actions of the third video of 2421 frames correctly.

While the extracted action sequences are executed in the open-loop manner and thus do not withstand real-world failures or disturbances, we find that this work brings us the step closer to having robots generate and execute variety of semantically meaningful plans from watching videos online.

## Q8. JEC-QA: A Legal-Domain Question Answering Dataset

Legal Question Answering (LQA) aims to provide explanations, advice, or solutions for legal issues. A qualified LQA system can not only demonstrate a professional consulting service for unskilled humans but also help professionals to improve work efficiency and analyze real cases more accurately, which makes LQA an important NLP application in the legal domain. Recently, many researchers attempt to

build LQA systems with machine learning techniques and neural networks. Despite these efforts in employing advanced NLP models, LQA is still confronted with the following two significant challenges. The first is that there is less qualified LQA dataset, which limits the research. The second is that the cases and questions in the legal domain are very complex and rigorous. As shown in Table 1, most problems in LQA can be divided into two typical types: the knowledge-driven questions (KD-questions) and case-analysis questions (CA-questions). KD-questions focus on the understanding of specific legal concepts, while CA-questions concentrate more on the analysis of real cases. Both types of questions require sophisticated reasoning ability and text comprehension ability, which makes LQA a hard task in NLP.



To get a better understanding of these reasoning abilities, we show a question of JEC-QA in Fig 1 describing a criminal behavior that results in two crimes. The models must understand Motivational Concurrence to reason out further evidence rather than lexical-level semantic matching. Moreover, the models must have the ability of multi-paragraph reading and multi-hop reasoning to combine the direct evidence and the additional evidence to answer the question, while numerical analysis is also necessary for comparing which crime is more dangerous. We can see that answering one question will need multiple reasoning abilities in both retrieving and answering, makes JEC-QA a challenging task.

To investigate the challenges and characteristics of LQA, we design a unified OpenQA framework and implement seven representative neural methods of reading comprehension. By evaluating the

performance of these methods on JEC-QA, we show that even the best approach can only achieve about 25% and 29% on KD-questions and CA-questions, respectively, while skilled humans and unskilled humans can reach 81% and 64% accuracies on JEC-QA. The experimental results show that existing OpenQA methods suffer from the inability of complex reasoning on JEC-QA as they cannot well understand legal concepts and handle multi-hop logic.

## Q9. SpoC: Spoofing Camera Fingerprints

**Answer:**




Figure 1: *SpoC* learns to spoof camera fingerprints. It can be used to insert camera traces to a generated image. Experiments show that we can fool state-of-the-art camera-model identifiers that were not seen during training.




Figure 2: A digital image of a scene contains camera-related traces of the image formation process that could act as a fingerprint of a camera model. The used lenses and filters, the sensor, and the manufacturer-specific digital processing pipelines result in unique patterns. These patterns can be used to identify camera models.

There have been astonishing advances in synthetic media generation in the last few years, thanks to deep learning, and in particular to Generative Adversarial Networks (GANs). This technology-enabled a

---

significant improvement in the level of realism of generated data, increasing both resolution and quality. Nowadays, powerful methods exist for creating an image from scratch, and for changing its style or only some specific attributes. These methods are beneficial, especially on faces, and allow one to change the expression of a person easily or to modify its identity through face-swapping. This manipulated visual content can be used to build more effective fake news. It has been estimated that the average number of reposts for a report containing an image is 11 times larger than for those without images. This raises serious concerns about the trustworthiness of digital content, as testified by the growing attention to the profound fake phenomenon.

The research community has responded to this threat by developing several forensic detectors. Some of them exploit high-level artifacts, like asymmetries in the color of the eyes, or anomalies arising from an imprecise estimation of the underlying geometry. However, technology improves so fast that these visual artifacts will soon disappear. Other approaches rely on the fact that any acquisition device leaves distinctive traces on each captured image, because of its hardware, or its signal processing suite. They allow associating a media with its acquisition device at various levels, from the type of source (camera, scanner, etc.), to its brand/model (e.g., iPhone6 vs iPhone7), to the individual device. A primary impulse to this field has been given by the seminal work of Lukàš et al., where it has been shown that reliable device identification is possible based on the camera photo-response non-uniformity (PRNU) pattern. This pattern is due to tiny imperfections in the silicon wafer used to manufacture the imaging sensor and can be considered as a type of device fingerprint.

Beyond extracting fingerprints that contain device-related traces, it is also possible to recover camera model fingerprints. These are related to the internal digital acquisition pipeline, including operations like demosaicing, color balancing, and compression, whose details differ according to the brand and specific model of the camera (See Fig 2). Such differences help attribute images to their source camera, but can also be used to highlight better anomalies caused by image manipulations. The absence of such traces, or their modification, is a strong clue that the image is synthetic or has been manipulated in some way. Detection algorithms, however, must confront with the capacity of an adversary to fool them. This applies to any classifier and is also very well known in forensics, where many counter-forensics methods have been proposed in the literature. Indeed, forensics and counter-forensics go hand in hand, a competition that contributes to improving the level of digital integrity over time.

In this work, we propose a method to synthesize traces of cameras using a generative approach that is agnostic to the detector (i.e., not just targeted adversarial noise). We achieve this by training a conditional generator to jointly fool an adversarial discriminator network as well as a camera embedding network. To this end, the proposed method injects the distinctive traces of a target camera model in synthetic images, while reducing the first generation traces themselves, leading all tested classifiers to attribute such images to the target camera (targeted attack).

**DATA SCIENCE  
INTERVIEW  
PREPARATION**  
**(30 Days of Interview Preparation)**

#FinaleDay30

**Most important questions  
Related to Project**

**Disclaimer:** The answers given here are not generic ones. These answers are given based on the attendance system that we have developed to do face detection. The answers will vary based on the projects done, methodologies used and based on the person being interviewed.

## **Face Recognition and Identification system Project**

### **Q1. Tell me about your current project.**


#### **Answer:**

The project is called Attendance System using facial recognition

The goal of the project is to identify the person and mark their attendance. First the user has to register himself/herself in the application providing the required details. The application takes multiple snaps of the user and then stores it into the database. Once the same user comes before the camera again the application captures the image references it against the already stored images in the database and then marks the attendance if the user is present in the database. Reports can be generated for a particular duration based on the user requirement.

Some snaps from the project are as follows:

#### **1<sup>st</sup>-time registration:**



**Marking the Attendance:****With un-registered user:**

The screenshot shows the iNeuron attendance system interface. At the top, there are navigation links: Products, API's, Models, Industries, Case studies, About us, and Connect. Below the header, there are three tabs: Mark Attendance (selected), Register, and Reports. On the left, there is a large video frame showing a man with glasses and a yellow and black checkered shirt. Below the video frame are four smaller thumbnail images of the same man. At the bottom of the video frame is a blue 'Stop' button. To the right of the video frame is a table with columns: Image, Name, Date, Time, and Government Id. The table contains one row with the following data: Image shows a thumbnail of the man; Name is 'Unknown User'; Date is '2019-11-29'; Time is '2:10:40'; and Government Id is 'NA'.

Image	Name	Date	Time	Government Id
	Unknown User	2019-11-29	2:10:40	NA

**With a registered user:**

The screenshot shows the iNeuron attendance system interface. At the top, there are navigation links: Products, API's, Models, Industries, Case studies, About us, and Connect. Below the header, there are three tabs: Mark Attendance (selected), Register, and Reports. On the left, there is a large video frame showing a man with dark hair and a light-colored shirt. Below the video frame is a blue 'Stop' button. To the right of the video frame is a table with columns: Image, Name, Date, Time, and Government Id. The table contains one row with the following data: Image shows a thumbnail of the registered user; Name is 'adarsh'; Date is '2019-11-17'; Time is '21:40:15'; and Government Id is '737291283818'.

Image	Name	Date	Time	Government Id
	adarsh	2019-11-17	21:40:15	737291283818

**Seeing the reports:**

The screenshot shows a web-based attendance management system titled "Attendance system with facerecognition". The interface includes a navigation bar with links for "Products", "API's", "Models", "Industries", "Case studies", "About us", and "Connect". Below the navigation is a main content area with tabs for "Mark Attendance", "Register", and "Reports", with "Reports" currently selected. Under "Reports", there are three sub-tabs: "Attendance", "Registered Users", and "Unknown Users", with "Registered Users" selected. The main table displays the following data:

Image	Name	EmailId	Phone No	Designation	Govt Id	Operations
	Sumit Gupta	sumitbsg85@gmail.com	+91 8447589517	Student	jhgghjgigh	
	sai kumar	saikumar@gmail.com	+91 9989260230	Student	574547574	
	RAHUL GAVHALE	RAHUL@GLOBALTINDIA.COM	+1 7387529245	Employee	EQRFWERGSDHHG	

**Features:**

- Works with generic IP cameras with good quality
- Works even with PC you don't need high-end systems
- Works in both indoor as well as outdoor environments
- Works with limited pose changes
- Works with spectacles
- Works for people of different ethnicity
- Works for tens of thousands of registered faces
- Works with limited lighting conditions
- Works with partial facial landmarks
- Non-recognition of static input images when provided by the user

### Functionalities in the Attendance System

- Registration of users in the system
- Capturing the user details during registration using Passport Adhar Card and Pan Card
- All details will be extracted using the in-house OCR technique
- Tracking of the login and logout timings of the users from the system
- Generation of user logs on a temporal basis
- Generation of timely reports

### Deployment/Installation

- The application can be easily installed as a web-based API on any cloud platform This installation is similar to a plug and play scenario
- The application can also be installed in an edge device (like the Google Coral) This installation provides realtime streaming capabilities to the application

## Q2. What was the size of the data?

### Answer:

The number of images used for training was

## Q3. What was the data type?

### Answer:

The data used for training this model consisted of thousands of images; the images then are converted to tensor objects which have a float representation

## Q4. What was the team size and distribution?

### Answer:

The team consisted of:

- Product Manager
- Solution Architect
- Lead
- Dev-Ops engineers
- QA engineers
- UI developers and
- Data Scientists

## **Q5.What Hadoop distribution were you using?**

**Answer:**

The Hadoop distribution from Cloudera was used as it provides many of the much-needed capabilities out of the box like multi-function analytics shared data experience with optimum security and governance hybrid capabilities for support to clouds on-premise servers as well as multi-clouds

## **Q6.What is the version of distribution?**

**Answer:**

CDH 5 0

## **Q7.What was the size of the cluster?**

**Answer:**

The cluster production setup) consisted of 5 servers with

- Intel i7 processors
- 56 GB of RAM
- 500 GB of Secondary storage each
- Mounted NAS locations

## **Q8. How many nodes were there in all the Dev, UAT, and Prod environments?**

**Answer:**

The necessary coding was done on one development server But as a standalone machine won t give enough speed to train the model in a short time once we saw that the model s loss is decreasing for a few numbers of epochs in the standalone machine the same code was deployed to a cloud-based GPU machine for training Once the model was trained there we used the saved model file for prediction/classification The same model file was deployed to the cloud UAT and Production environments


In total we had:

- 5 nodes in the dev environment
- 5 nodes in UAT and
- 5 nodes in production

## Q9. How were you creating and maintaining the logs?

### Answer:

The logs are maintained using MongoDB. The logging starts with the start of the application. The start time of the application gets logged. After that there are loggings for entry and exits to the individual methods. There are loggings for the error scenarios and exception block as well.



## Q10.What techniques were you using for data pre-processing for various data science use cases and visualization?

### Answer:

There are multiple steps that we do for data preprocessing like data cleaning data integration data scaling etc Some of them are listed as follows:

#### → For Machine Learning:

- ⊕ While preparing data for a model data should be verified using multiple tables or files to ensure data integrity
- ⊕ Identifying and removing unnecessary attributes

For example

	User_ID	Product_ID	Gender	Age	Occupation	City_Category	Stay_In_Current_City_Years	Marital_Status	Product_Category_1
0	1000001	P00069042	F	0-17	10	A	2	0	3
1	1000001	P00248942	F	0-17	10	A	2	0	1
2	1000001	P00087842	F	0-17	10	A	2	0	12
3	1000001	P00085442	F	0-17	10	A	2	0	12
4	1000002	P00285442	M	55+	16	C	4+	0	8

Here the user\_ID column does not contribute to the customer behavior for purchasing the products So it can be dropped from the dataset

- ⊕ Identifying filling or dropping the rows/columns containing missing values based on the requirement

## Checking for columnwise null values


```
: df.isnull().sum()
: Product_ID           0
Gender                 0
Age                    0
Occupation             0
City_Category          0
Stay_In_Current_City_Years 0
Marital_Status          0
Product_Category_1      0
Product_Category_2      245982
Product_Category_3      545809
Purchase                233599
B                       0
C                       0
dtype: int64
```

Here the Product\_Category\_2 has about 5.5 lac missing values. It can be dropped using the command → df.drop('Product\_Category\_2', axis=1, inplace=True)


Or if the count of null values have been lower they could have been imputed using →

```
df['Purchase'] = df['Purchase'].fillna(df['Purchase'].mean()))
```

### Identifying and removing outliers



- + In the image above one point lies very far from the other data points i.e it is an outlier that is not following the general trend of the data So that point can be dropped
- + Based on the requirement form clusters of data to avoid an overfitted model



Contrary to the example in the previous point there can be several points that do not follow a particular pattern or which have a pattern of their own If those points are too many they can't be considered as outliers Then we need to consider those points separately In that kind of scenario we create the clusters of similar points and then we try and train our model on those clusters

- + Scaling the data so that the difference between the magnitudes of the data points in different columns are not very big

	Gender	Age	Occupation	Stay_In_Current_City_Years	Marital_Status	cat1	cat2	cat3	Purchase	B	C	
0	0	1	10		2	0	3	8.0	16.0	8370.0	0	0
1	0	1	10		2	0	1	6.0	14.0	15200.0	0	0
2	0	1	10		2	0	12	8.0	16.0	1422.0	0	0
3	0	1	10		2	0	12	14.0	16.0	1057.0	0	0
4	1	7	16		4	0	8	8.0	16.0	7969.0	0	1
5	1	3	15		3	0	1	2.0	16.0	15227.0	0	0
6	1	5	7		2	1	1	8.0	17.0	19215.0	1	0
7	1	5	7		2	1	1	15.0	16.0	15854.0	1	0
8	1	5	7		2	1	1	16.0	16.0	15686.0	1	0
9	1	3	20		1	1	8	8.0	16.0	7871.0	0	0

In the diagram above the magnitude of the values in the Purchase column is way larger than the other columns This kind of data makes our model sensitive To rectify this we can do →

```
# Feature Scaling So that data in all the columns are to the same scale
from sklearn.preprocessing import StandardScaler
sc = StandardScaler()
X_train = sc.fit_transform(X_train)
```

After scaling the data looks like:

	Gender	Age	Occupation	Stay_In_Current_City_Years	Marital_Status	cat1	cat2	cat3	Purchase	B	C
0	0.572754	-0.367452	0.600884	-0.666350	1.199047	-0.094207	-0.293215	0.369371	0.000026	1.173655	-0.672287
1	0.572754	-0.367452	-1.239139	1.660866	1.199047	-1.125331	-1.688120	0.369371	0.540162	-0.852039	-0.672287
2	0.572754	1.109957	-0.165793	-1.442089	-0.833995	-0.094207	-0.293215	0.369371	0.000026	1.173655	-0.672287
3	0.572754	2.587366	-1.085804	0.885128	1.199047	0.679136	-0.293215	0.369371	-0.815744	-0.852039	-0.672287
4	0.572754	1.848662	0.754219	-0.666350	1.199047	-0.351988	-0.990668	1.098466	-1.520074	1.173655	-0.672287
5	0.572754	-1.106157	-0.932469	0.885128	-0.833995	-0.867550	-1.223152	0.369371	-1.359912	1.173655	-0.672287
6	0.572754	-0.367452	-0.932469	-1.442089	1.199047	-1.125331	-0.293215	0.369371	0.000026	-0.852039	-0.672287
7	0.572754	-0.367452	0.600884	0.885128	-0.833995	-0.094207	-0.758184	-0.724271	0.000026	-0.852039	1.487460
8	0.572754	-0.367452	-0.165793	1.660866	-0.833995	0.679136	0.869206	0.369371	0.175403	1.173655	-0.672287
9	0.572754	-1.106157	1.827566	1.660866	1.199047	-0.094207	-0.293215	0.369371	-0.501124	-0.852039	-0.672287

⊕ Converting the categorical data into numerical data

For example gender data (Male or Female) is a categorical one. It can be converted to numeric values as shown below:

```
df['Gender']=df['Gender'].map({'F':0 'M': 1})
```

⊕ Replacing or combining two or more attributes to generate a new attribute which serves the same purpose

For example if we use one-hot encoding in the example above it will generate two separate columns for males and females. But if we observe a person who is not a male is automatically a female (if we consider only two genders). So the two columns essentially convey the same information in that case. This is called the *dummy variable trap*. So one column can be conveniently dropped.

⊕ Trying out dimensionality reduction techniques like PCA (Principal Component Analysis) which tries to represent the same information but in a space with reduced dimensions

→ **For Deep Learning:**

- ⊕ Data augmentation strategies followed by image annotation. Data augmentation consists of image rotation, contrast, and color adjustments, lighting variations, random erasing, etc.
- ⊕ Then all the images are made of identical size.
- ⊕ Then image annotation is done.

## **Q11. How were you maintaining the failure cases?**

**Answer:**

Let's say that our model was not able to make a correct prediction for an image. In that case, that image gets stored in the database. There will be a report triggered to the support team at the end of the day with all the failed scenarios where they can inspect the cause of failure. Once we have a sufficient number of cases, we can label and include those images while retraining the model for better model performance.

## **Q12. What kind of automation have you done for data processing?**

**Answer:**

We had a full-fledged ETL pipeline in place for data extraction. Employers already have images of their employees. That data can be easily used after doing pre-processing for training the image identification model.

## **Q13. Have you used any scheduler?**

**Answer:**

Yes, a scheduler was used for retraining the model after a fixed time (0 days).

## **Q14. How are you monitoring your job?**

**Answer:**

There are logging set-ups done. We regularly monitor the logs to see for any error scenarios. For fatal errors, we had email notifications in place. Whenever a specific error code, which has been classified as a fatal error occurs, email gets triggered to the concerned parties.

## **Q15. What were your roles and responsibilities in the project?**

**Answer:**

My responsibilities consisted of gathering the dataset, labeling the images for the model training, training the model on the prepared dataset, deploying the trained model to the cloud, monitoring the deployed model for any issues, providing QA support before deployment and then providing the warranty support post-deployment.

## **Q16.What was your day to day task?**

**Answer:**

My day to day tasks involved completing the JIRA tasks assigned to me attending the scrum meetings participating in design discussions and requirement gathering doing the requirement analysis data validation image labeling Unit test for the models providing UAT support etc

## **Q17.In which area you have contributed the most?**

**Answer:**

I contributed the most to image labeling and model training areas Also we did a lot of brainstorming for finding and selecting the best algorithms for our use cases After that we identified and finalized the best practices for implementation scalable deployment of the model and best practices for seamless deployments as well

## **Q18.In which technology you are most comfortable?**

**Answer:**

I have worked in almost all the fields viz Machine Learning Deep Learning and Natural Language Processing and I have nearly equivalent knowledge in these fields But if you talk about personal preference I have loved working in Deep Learning and NLP the most

## **Q19.How you rate yourself in big data technology?**

**Answer:**

I have worked often in the big data computing technology with ample knowledge in distributed and cluster-based computing But my focus and extensive contribution have been as a data scientist

## **Q20. In how many projects you have already worked?**

**Answer:**

It's difficult to give a number But I have worked in various small and large scale projects e g object detection object classification object identification NLP projects chatbot building machine learning regression and classification problems

## **Q21. How were you doing deployment?**

**Answer:**

The mechanism of deployment depends on the client's requirement. For example, some clients want their models to be deployed in the cloud and the real-time calls they take place from one cloud application to another. On the other hand, some clients want an on-premise deployment and then they do API calls to the model. Generally, we prepare a model file first and then try to expose it through an API for predictions/classifications. The mechanism in which the API gets called depends on the client requirement.

## **Q22. What kind of challenges have you faced during the project?**

**Answer:**

The biggest challenge that we face is in terms of obtaining a good dataset, cleaning it to be fit for feeding it to a model, and then labeling the prepared datasets. Labeling is a rigorous task and it burns a lot of hours. Then comes the task of finding the correct algorithm to be used for that business case. Then that model is optimized. If we are exposing the model as an API, then we need to work on the SLA for the API as well, so that it responds in optimum time.

## **Q23. What will be your expectations?**

**Answer:**

It's said that the best learning is what we learn on the job with experience. I expect to work on new projects which require a broad set of skills so that I can hone my existing skills and learn new things simultaneously.

## **Q24. What is your future objective?**

**Answer:**

The field of data science is continuously changing. Almost daily there is a research paper that changes the way we approach an AI problem. So, it really makes it exciting to work on things that are new to the entire world. My objective is to learn new things as fast as possible and try and implement that knowledge to the work that we do for better code, robust application and in turn, a better user/customer experience.

## **Q25. Why are you leaving your current organization?**

**Answer:**

I was working on similar kinds of projects for some time now. But the market is rapidly changing and the skill set required to be relevant in the market is changing as well. The reason for searching a new job is to work on several kinds of projects and improve my skill set. <*Mention about the company profile and if you have the project name that you are being interviewed for as new learning opportunities for you*>.

## **Q26. How did you do Data validation?**

**Answer:**

Data validation is done by looking at the images gathered. There should be ample images for the varied number of cases like change in the lighting conditions, distance from the camera, movement of the user, the angle at which camera is installed, the position at which the camera is installed, the angle at which the snap of the user has been taken, the alignment of the image, the ratio of the face and the other areas in the image etc.

## **Q27. How did you do Data enrichment?**

**Answer:**

Data enrichment in vision problems mostly consists of image augmentation. Apart from image augmentation we tried to train the model with images with different lighting conditions, with b/w and colored images, images from different angles etc.

## **Q28. How would you rate yourself in machine learning?**

**Answer:**

Well honestly my 0 and your 0 will be a lot different as we have different kinds of experiences. On my scale of 0 to 10 I'll rate myself as an

## **Q29. How would you rate your self in distributed computation?**

**Answer:**

I'd rate myself a 7/10 out of 10

### **Q30. What are the areas of machine learning algorithms that you already have explored?**

**Answer:**

I have explored various machine learning algorithms like Linear Regression Logistic Regression L and L Regression Polynomial Regression Multi Linear Regression Decision Trees Random Forests Extra Trees Classifier PCA TSnE UMAP XG Boost CAT Boost ADA Boost Gradient Boosting Light Boost K-Means K-Means ++ LDA QDA KNN SVM SVR Naïve Bayes Agglomerative clustering DBScan Hierarchical clustering TFIDF Word to Vec Bag of words Doc to Vec Kernel Density Estimation are some of them

### **Q31. In which part of machine learning have you already worked on?**

**Answer:**

I have worked on both supervised and unsupervised machine learning approaches and building different models using the as per the user requirement

### **Q32. How did you optimize your solution?**

**Answer:**

Well model optimization depends on a lot of factors

- Train with better data increase the quality) or do data pre-processing steps more efficiently
- Keep the resolution of the images identical
- Increase the quantity of data used for training
- Increase the number of epochs for which the model was trained
- Tweak the batch input size the number of hidden layers the learning rate rate of decay etc to produce the best results
- If you are not using transfer learning then you can alter the number of hidden layers activation function
- Change the function used in the output layer based on the requirement The sigmoid functions work well with binary classification problems whereas for multi-class problems we use a sigmoid model
- Try and use multithreaded approaches if possible
- Reduce Learning Rate in plateau reasons optimizes the model even further

### **Q33. How much time did your model take to get trained?**

**Answer:**

With a batch size of      and the number of epochs  00000 with 7000 images it took around    0 hours to train the model using Nvidia Pascal Titan GPU

### **Q34. At what frequency are you retraining and updating your model?**

**Answer:**

The model gets retrained every  0 days

### **Q35. In which mode have you deployed your model?**

**Answer:**

I have deployed the model both in cloud environments as well in the on-premise ones based on the client and project requirements

### **Q36. What is your area of specialization in machine learning?**

**Answer:**

I have worked on various algorithms So It's difficult to point out one strong area Let's have a discussion on any specific requirement that you have and then we can take it further from there